

**DEPARTMENT OF TRANSPORTATION  
STATE OF GEORGIA**

**SPECIAL PROVISION**

**ATLANTA BELTLINE NORTHEAST TRAIL**

**Section 627 – Mechanically Stabilized Embankment Retaining Wall-  
Contractor Design**

---

*Delete Subsection 627.3.03.B.1 and substitute the following:*

1. Provide one of the following wall systems:
  - ARES (Tensar Earth Technologies)
  - Reinforced Earth Wall (The Reinforced Earth Company) Sine Wall
  - MSE Panel Systems (Sine Wall)
  - Stabilized Earth Wall (Vistawall Systems)
  - Tricon Retained Soil Wall (Tricon Precast)
  - Or approved equal

*Delete Subsection 627.3.03.B.10 and substitute the following:*

10. Ensure the maximum panel area does not exceed 25 square feet (2.32 square meters) and any side does not exceed 5 feet.

*Delete Subsection 627.3.03.B.11 and substitute the following:*

11. Panels shall be rectangular in shape, with any one side not exceeding 5 feet.

*Delete Subsection 627.3.04 and substitute the following:*

**627.3.04 Fabrication**

Meet the requirements of Subsection 626.3.04 of the Specifications.

*Delete Subsection 627.3.05 and substitute the following:*

**627.3.05 Construction**

Meet the requirements of Subsection 626.3.05 of the Specifications.