

**ADDENDUM NINE  
GATEWAY SCULPTURES AT BLUE GOOSE HOLLOW  
CONTRACT NO. D-16-006-201  
CITY OF CHATTANOOGA, TENNESSEE**

The following changes shall be made to the Contract Documents, Specifications, and Drawings:

**I. Bid Form**

1. An updated bid form is included in this Addendum.
2. Deviations from the 40' required length of the helical piers are now differentiated by capacity, resulting in the addition of line items for 10-ton additions/deducts, 15-ton additions/deducts, and 20-ton additions/deducts.

January 19, 2018

---

/s/ Justin C. Holland, Administrator  
City of Chattanooga  
Department of Public Works

## **BID SCHEDULE**

### **GATEWAY SCULPTURES AT BLUE GOOSE HOLLOW**

**CONTRACT NUMBER D-16-006-201**

**CHATTANOOGA, TENNESSEE**

#### **DESCRIPTION**

The project consists of securing all necessary construction permits, installing erosion control measures, excavating for construction of foundations, installing twelve (12) helical piers to an approximate depth of 40' and specified capacity, constructing three isolated reinforced concrete pier caps and setting anchor bolts, and constructing one reinforced concrete mat foundation and setting anchor bolts. After the sculptures are installed (by others), backfill foundation excavations with #57 stone to 4" below finished grade, install weed control fabric, install a 4" layer of decorative landscaping stone, repair any damaged site elements, clean work site, and restore the area to pre-construction conditions.

#### **TOTAL PROJECT BID**

**TOTAL PROJECT BID \$** \_\_\_\_\_  
\$ \_\_\_\_\_

*Note: Dollar amounts are to be shown in both words and figures. In case of discrepancy, dollar amounts shown in words will govern.*

**Contractor certifies that he has reviewed the plans and specifications, and that all items of work not specifically listed in the Bid Schedule are included in the prices for the various items listed on the Bid Schedule.**

**BIDDER:**

**DATE:**

**BY:**

**(Signature) TITLE:**

**ADDRESS:**

**CITY:**

**STATE:**

**ZIP CODE:**

**TELEPHONE NUMBER:**

00301-1

**Bid Schedule**  
**Contract Number D-16-006-201**  
**Gateway Sculptures at Blue Goose Hollow**  
**City of Chattanooga**

**Rev. 1/19/17**

<b>CONTRACT NUMBER D-16-006-201</b>					
<b>Item No.</b>	<b>Description</b>	<b>Estimated Qty.</b>	<b>Unit</b>	<b>Unit Price</b>	<b>Total Price</b>
<b>BASE BID</b>					
717	Mobilization	1	LS		
00 00 23	Removal of Structures & Obstructions	1	LS		
00 00 98	Erosion Control	1	LS		
00 00 98.1	Maintaining Erosion Control Devices	1	LS		
02 22 20	Excavation for foundations	58	CY		
02 22 21	Stripping Topsoil	13	CY		
00 00 73	4" Layer Decorative Rock	26	TON		
00 00 98	No. 57 Backfill	32	TON		
31 26 01	Steel Helical Piers & Embed Plates, 10-ton	4	EA		
31 26 02	Steel Helical Piers & Embed Plates, 15-ton	4	EA		
31 26 03	Steel Helical Piers & Embed Plates, 20-ton	4	EA		
31 26 10	Steel Helical Piers, 10-ton (Additional Length Over 40' Depth, 7' Section)	4	EA		
31 26 11	Steel Helical Piers, 10-ton (Length Under 40' Depth, 7' Section, <b>DEDUCT</b> )	4	EA		
31 26 12	Steel Helical Piers, 15-ton (Additional Length Over 40' Depth, 7' Section)	4	EA		
31 26 13	Steel Helical Piers, 15-ton (Length Under 40' Depth, 7' Section, <b>DEDUCT</b> )	4	EA		
31 26 14	Steel Helical Piers, 20-ton (Additional Length Over 40' Depth, 7' Section)	4	EA		
31 26 15	Steel Helical Piers, 20-ton (Length Under 40' Depth, 7' Section, <b>DEDUCT</b> )	4	EA		
03 31 00	Class A Concrete	21	CY		
03 24 00	Steel Bar Reinforcement	1700	LB		
1413	Repair Pavers, Edge Restraint Curb, Subsurface Drainage	100	SF		

**D-16-006-201 TOTAL BASE BID \$**