

PUTNAM COUNTY



**ADDENDUM #3
FOR**

PROJECT NO. 22-42001-002

**PUTNAM COUNTY LANDFILL SUPPLEMENTAL
MAINTENANCE GRADING**

**PUTNAM COUNTY
BOARD OF COMMISSIONERS**

Addendum #3

Project No. 22-42001-002 Putnam County Landfill Supplemental Maintenance Grading

Date: September 28, 2022

Clarifications

1. Replace the Bid Form in the Contract Bid Documents, page 1-7 with the attached REVISED BID FORM.
2. The construction duration has been revised to be 90 days.
3. An on-site borrow source has been identified, as shown on the attached Supplemental Plan, Revision 2. The Contractor shall provide equipment and operators for construction of the temporary borrow source access road, clearing, excavating, loading, hauling and placing. A quantity has been put on the REVISED BID FORM for bidding purposes.
4. Putnam County will bush hog the Cap prior to Contractor mobilization.
5. Please see the attached revised Supplemental Plan, revision date 9-28-22, for the project. Revisions are as follows and all revisions are clouded:
 - Sheet C200, C500, C501, C502 – The identified borrow source location is shown to the north of the closed MSW. The Contractor shall install a temporary access road consisting of a geotextile stabilization fabric overlain with rip rap.
 - The borrow source shall be of sufficient areal extent to allow removal of soils to a dept of approximately 5-feet and graded to drain to the northwest. Upon completion of work, the roadway will be removed and the disturbed areas of the access roadway and borrow source will be vegetated.
 - The Construction duration has been revised to reflect a 90-day completion requirement.
6. The Contractor shall warranty the work for a period of one year after substantial completion. Substantial completion is defined as all work complete and 90 percent vegetative stabilization of the regraded Cap, the disturbed areas of the on-site borrow source and pipe replacement at the detention pond.