

A. Bidder will perform the following Work at the indicated unit prices:

Item No.	Description	Unit	Estimated Quantity	Bid Unit Price	Bid Amount
<b>ITEM 1 - MOBILIZATION</b>					
a.	Force Account	LS	1	\$ 10,000	\$ 10,000
b.	Mobilization	LS	1	\$	\$
<b>ITEM 2 - SITE WORK</b>					
a.	Construction Entrance/Exit	EA	1	\$	\$
b.	Double Row Silt Fence (Typ. S)	LF	4,100	\$	\$
c.	Stripping and Stockpiling of 6-inch-thick vegetative layer (Cap)	CYD	11,700	\$	\$
d.	Clearing and Grubbing – Borrow Source	LS	1	\$	\$
e.	Borrow Source Access Road/Silt Fence	LS	1	\$	\$
f.	Slope Stabilization Matting (Ss)	LS	1	\$	\$
g.	Maintenance of All Weather Roadways	LS	1	\$	\$
h.	Cut - Cap*	CYD	5,946	\$	\$
i.	Fill - Cap*	CYD	13,864	\$	\$
j.	Spread Vegetative Layer from Stockpile*	AC	14.5	\$	\$
k.	Temporary Grassing (Cap, Borrow Area)	AC	16	\$	\$
l.	Permanent Grassing (Cap, Borrow Area)	AC	16	\$	\$
m.	12-Inch Dia. Down Drain	LF	932	\$	\$
n.	12-Inch Flared Terrace Inlet	EA	13	\$	\$
o.	12-Inch Outlet/Rip Rap	EA	13	\$	\$
p.	18-Inch Dia. Down Drain	LF	135	\$	\$
q.	18-Inch Flared Terrace Inlet	EA	2	\$	\$
r.	18-Inch Outlet/Rip Rap	EA	2	\$	\$
s.	24-Inch Dia. Down Drain	LF	85	\$	\$
t.	24-Inch Flared Terrace Inlet	EA	1	\$	\$
u.	24-Inch Outlet/Rip Rap	EA	1	\$	\$
v.	42-inch CMP Outlet Replacement (Pond)	LS	1	\$	\$
w.	NPDES Monitoring and Reporting	LS	1	\$	\$
x.	As-built Survey	LS	1	\$	\$

**TOTAL UNIT PRICE BID, ITEMS 1 AND 2 IS IN THE AMOUNT OF:**

**TOTAL \$**

**\*EXCAVATION, STRUCTURAL FILL, VEGETATIVE COVER UNIT PRICE INCLUDES LAYOUT, EXCAVATION, HAULING, PLACMENT AND COMPACTION.**

B. Bidder acknowledges that:

1. Each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and
2. Estimated quantities are not guaranteed and are solely for the purpose of comparison of Bids. Final payment for all Unit Price Work will be based on actual quantities, determined as provided in the Contract Documents.

**END OF BID FORM**