

**DR. MELLICHAMP DRIVE  
STREETSCAPE & ROADWAY IMPROVEMENTS  
REVISED BID FORM - UNIT PRICE SCHEDULE**

DATE: / Revised May 30, 2017

BY: JPM  
JOB: 26436.0000

**GENERAL PROVISIONS**

Item	Description	Quantity	Units	Unit Price	Total
1	Mobilization	1	LS	\$ -	\$ -
2	Bonds and Insurance	1	LS	\$ -	\$ -
3	Traffic Control	1	LS	\$ -	\$ -
4	Project Management and Coordination	1	LS	\$ -	\$ -
<b>Sub-Total, GENERAL PROVISIONS</b>					<b>\$ -</b>

**DEMOLITION**

Item	Description	Quantity	Units	Unit Price	Total
1	Rem. & Disp. Full Depth Asphalt	850	SY	\$ -	\$ -
2	Rem. & Disp. Concrete Sidewalk	17	SY	\$ -	\$ -
3	Rem. & Stock Brick Sidewalk	30	SY	\$ -	\$ -
4	Rem. & Disp. Concrete Curb	170	LF	\$ -	\$ -
5	Rem. & Disp. Concrete Paving	120	SY	\$ -	\$ -
6	Rem. & Disp. Brick Planter	2	EA	\$ -	\$ -
7	Rem. & Disp. Wooden Planter and Shrubs	225	LF	\$ -	\$ -
8	Rem. & Disp. Bollards	6	EA	\$ -	\$ -
9	Rem. & Disp. Gravel/Shell Parking	361	SY	\$ -	\$ -
10	Asphalt Milling	242	SY	\$ -	\$ -
11	Relocate Mailboxes	5	EA	\$ -	\$ -
12	Relocate Electrical Meter & Pole	1	LS	\$ -	\$ -
13	Rem. & Disp. Grate Inlet	1	EA	\$ -	\$ -
14	Rem. & Disp. 15" RCP	201	LF	\$ -	\$ -
15	Rem. & Disp. 18" RCP	469	LF	\$ -	\$ -
16	Rem. & Reinstall Signage	1	LS	\$ -	\$ -
17	Rem. & Reinstall Fence	145	LF	\$ -	\$ -
<b>Sub-Total, DEMOLITION</b>					<b>\$ -</b>

**DR. MELLICHAMP DRIVE  
STREETSCAPE & ROADWAY IMPROVEMENTS  
REVISED BID FORM - UNIT PRICE SCHEDULE**

DATE: / Revised May 30, 2017

BY: JPM  
JOB: 26436.0000

**EARTHWORK, PAVING & CONSTRUCTION**

Item	Description	Quantity	Units	Unit Price	Total
1	Clear & Grub	1.4	AC	\$ -	\$ -
2	Grading	6,750	SY	\$ -	\$ -
3	Muck & Fill Ditches & Swales	1,000	CY	\$ -	\$ -
4	Asphalt - Overlay & Leveling	2,030	SY	\$ -	\$ -
5	Asphalt - Full Depth Road Section	340	SY	\$ -	\$ -
6	Concrete Paving	240	SY	\$ -	\$ -
7	Gravel Paving	95	SY	\$ -	\$ -
8	Grassed Parking	198	SY	\$ -	\$ -
9	Pervious Paver Parking	1,315	SY	\$ -	\$ -
10	Pervious Gravel Mix Parking	420	SY	\$ -	\$ -
11	Pervious Pedestrian Paver	151	SY	\$ -	\$ -
12	Concrete Sidewalk	910	SY	\$ -	\$ -
13	Detectable Warning	152	SF	\$ -	\$ -
14	6" Concrete Header Curb	725	LF		\$ -
15	12" Concrete Flush Header Curb	365	LF	\$ -	\$ -
16	18" Concrete Curb & Gutter	500	LF	\$ -	\$ -
17	18" Concrete Curb - Transition	37	LF	\$ -	\$ -
18	24" Concrete Valley Gutter	1,270	LF	\$ -	\$ -
19	24" Concrete Curb - Transition	70	LF	\$ -	\$ -
20	Concrete Wheel Stop	55	EA	\$ -	\$ -
21	Striping & Signage	1	LS	\$ -	\$ -
<b>Sub-Total, EARTHWORK, PAVING &amp; CONSTRUCTION</b>					<b>\$ -</b>

**DRAINAGE**

Item	Description	Quantity	Units	Unit Price	Total
1	18" RCP	470	LF	\$ -	\$ -
2	24" RCP	348	LF	\$ -	\$ -
3	30" RCP	260	LF	\$ -	\$ -
4	Curb Inlet	8	EA	\$ -	\$ -
5	Valley Gutter Inlet	5	EA	\$ -	\$ -
6	Junction Box (Construct on Existing Pipe)	1	EA	\$ -	\$ -
7	Junction Box	1	EA	\$ -	\$ -
8	Grate Inlet	2	EA	\$ -	\$ -
9	Ditch Inlet	1	EA	\$ -	\$ -
10	Modify Roof Inlet	1	LS	\$ -	\$ -
11	Concrete Headwall on 30" RCP	1	EA	\$ -	\$ -
12	Connect to Existing Structure	2	EA	\$ -	\$ -
<b>Sub-Total, DRAINAGE</b>					<b>\$ -</b>

**DR. MELLICHAMP DRIVE  
STREETSCAPE & ROADWAY IMPROVEMENTS  
REVISED BID FORM - UNIT PRICE SCHEDULE**

DATE: / Revised May 30, 2017

BY: JPM  
JOB: 26436.0000

**MISCELLANEOUS**

Item	Description	Quantity	Units	Unit Price	Total
1	Adjust All Structures to Finish Grade	1	LS	\$ -	\$ -
2	4" PVC-C900-DR18 (Future fire lateral)	55	LF	\$ -	\$ -
3	4" Conduit Sleeve	639	LF	\$ -	\$ -
4	2" Conduit Sleeve	64	LF	\$ -	\$ -
5	4" Mechanical Joints & Caps per BJWSA & IFC Spec	1	LS	\$ -	\$ -
6	Connect 2" Irrigation Lateral to Existing 2"	1	LS	\$ -	\$ -
7	2" HDPE Irrigation Lateral	68	LF	\$ -	\$ -
8	2" Valve, Box, and Cover	1	EA	\$ -	\$ -
9	Irrigation Backflow	1	EA	\$ -	\$ -
10	Install & Coordinate New Electrical supply for Irrigation	1	LS	\$ -	\$ -
<b>Sub-Total, MISCELLANEOUS</b>					<b>\$ -</b>

**EROSION CONTROL**

Item	Description	Quantity	Units	Unit Price	Total
1	Erosion Control & Tree Protection	1	LS	\$ -	\$ -
<b>Sub-Total, EROSION CONTROL</b>					<b>\$ -</b>
<b>Total, BASE BID FOR SITE DEVELOPMENT</b>					<b>\$ -</b>

**ADD ALTERNATE #1 - WATER**

Item	Description	Quantity	Units	Unit Price	Total
1	Traffic Control	1	LS	\$ -	\$ -
2	Project Management and Coordination	1	LS	\$ -	\$ -
3	Open Cut, Remove, and Replace Bank Driveway	13	SY	\$ -	\$ -
4	8" PVC-C900-DR18	237	LF	\$ -	\$ -
5	8" DIP Crossing	18	LF	\$ -	\$ -
6	2" HDPE Lateral	30	LF	\$ -	\$ -
7	8" Jack and Bore Under Hwy 46	75	LF	\$ -	\$ -
8	Connection to Existing 8" Complete	2	EA	\$ -	\$ -
9	Connection to Existing 10" Complete	1	EA	\$ -	\$ -
10	Connection to Existing 2" Complete	2	EA	\$ -	\$ -
11	2" Plug	2	EA	\$ -	\$ -
12	2" Valve, Box, and Cover	2	EA	\$ -	\$ -
13	8" Valve, Box, and Cover	2	EA	\$ -	\$ -
14	10" Valve, Box, and Cover	2	EA	\$ -	\$ -
15	2" Connection to 8"	1	EA	\$ -	\$ -
16	8" - 90° Bend	1	EA	\$ -	\$ -
17	8" - 11.25° Bend	1	EA	\$ -	\$ -
<b>Sub-Total, ADD ALTERNATE #1 - WATER</b>					<b>\$ -</b>

**ADD ALTERNATE #2**

Item	Description	Quantity	Units	Unit Price	Total
1	Oyster Shell Finish on Sidewalks*	910	SY	\$ -	\$ -
<b>Sub-Total, ADD ALTERNATE #2</b>					<b>\$ -</b>

\*Note - Price to be an addition to Concrete Sidewalk Price

**DR. MELLICHAMP DRIVE  
STREETSCAPE & ROADWAY IMPROVEMENTS  
REVISED BID FORM - UNIT PRICE SCHEDULE**

DATE: / Revised May 30, 2017

BY: JPM  
JOB: 26436.0000

Total, BASE BID FOR SITE DEVELOPMENT and ALTERNATES 1 & 2	\$	-
-----------------------------------------------------------	----	---