



Georgetown County, South Carolina

129 Screven Street, Suite 239
Post Office Drawer 421270
Georgetown, SC 29442-4200
(843) 545-3083 • Fax (843) 545-3500
E-Mail • purch@gtcounty.org
Website • <http://www.gtcounty.org>

ADDENDUM #1 TO BID #20-048

RFQU NUMBER: 20-048

ISSUE DATE: Tuesday, August 11, 2020

OPENING DATE: Thursday, August 20, 2020

OPENING TIME: 3:30 PM (ET)

Pre-Bid Site Inspection: Independent-On Own

PROCUREMENT FOR: USER FEE ROAD CONSTRUCTION-WILLARD LOOP AND PARTRIDGE LANE

This addendum will amend **BID #20-048, USER FEE ROAD CONSTRUCTION-WILLARD LOOP AND PARTRIDGE LANE** originally issued on Wednesday, July 29, 2020. This clarification is being provided to all known and registered correspondents in response to questions received. All addenda and original bid documents are also available online at: www.gtcounty.org, select "Bid Opportunities" from the Quick Links section and "View Current Bid Solicitations."

Question 1: Is the pipe bedding the same application as for the Brick Chimney project?

Response: The detail on page 5 of the Willard Loop plans shall be used for bidding. The cost of the pipe bedding shall be included in the cost of the pipe.

Question 2: I see in the specs that the mucking price includes the put back compacted with shrinkage, is this correct?

Response: Yes, the mucking price includes the backfill. Item No. 2033000 Borrow Excavation for Willard Loop has been reduced, see revised unit price schedule attached.

Question 3: The utility allowance, is the amount sufficient to move all the overhead power lines to the right of way?

Response: See the last page of the Supplemental Specifications for utility allowance details. Per the specification section 2.1.1, this allowance shall cover the net cost of the work performed by the utility company on the utility relocation required for the construction of the roadway and associated drainage and landscaping features. If the cost, when determined, is more or less than the allowance, the Contract Sum shall be adjusted accordingly by change order which will include overhead and profit due the Contractor from any increase over the original allowance.

[THE REMAINDER OF THIS PAGE IS INTENTIONALLY LEFT BLANK]

“EXHIBIT G”

**UNIT PRICE SCHEDULE (REVISED 8/10/2020)
(Mandatory Bid Submittal Form)**

When changes in the work are ordered by the Owner, and such changes involve the following items, the following unit prices will be used to calculate adjustments to the Contract Sum. These unit prices shall be for the Work as specified, including all labor, materials, equipment, accessories, shipping, preparation, insurance, testing, overhead, profit, applicable taxes, permits, fees, warranties and all other associated costs for the finished and completed Work. All unit prices for utility conduits shall include sweeps, bends, couplings, caps, fittings, etc. which shall be included in the unit price per linear foot. Unit prices for undercut soils shall include material in place, surveyed and compacted pursuant to the Contract Documents.

Submit unit price and proposal amount for the following items. This list may not include all components necessary to provide a completed product, therefore any applicable items necessary to provide a completed product should be considered in your unit price response.

In case of errors in the extension of prices, unit price governs. In case of error in summations, corrected bid amounts will be totaled and will govern.

Contractor shall make quantity take-offs using drawings to determine quantities to his satisfaction, reporting promptly any discrepancies which may affect bidding. This is not a comprehensive list of items included in the contract documents, and represents only a portion of the project total.

PARTRIDGE LANE - D&F Project No.: 031810-02					
ITEM NO.	PAY ITEM	UNIT	ENGINEER'S ESTIMATE	CONTRACTOR'S ESTIMATE	UNIT PRICE
1031000	MOBILIZATION	LS	NEC		
1050800	CONSTRUCTION STAKES, LINES & GRADES	EA	1.000		
1061100	QUALITY CONTROL FOR EARTHWORK	LS	1.000		
1061200	QUALITY CONTROL FOR BASES AND SUBBASES	LS	1.000		
1071000	TRAFFIC CONTROL	LS	NEC		
1090200	AS-BUILT CONSTRUCTION PLANS	LS	1.000		
2011000	CLEARING & GRUBBING WITHIN RIGHT OF WAY	LS	NEC		
2031000	UNCLASSIFIED EXCAVATION	CY	797.248		
2033000	BORROW EXCAVATION	CY	490.000		
2034000	MUCK EXCAVATION	CY	300.000		
2081001	FINE GRADING	LS	NEC		
3050108	GRADED AGGREGATE BASE COURSE (8" UNIFORM)	SY	1,832.000		
3069900	MAINTENANCE STONE	TON	60.000		
3100320	HOT MIX ASPHALT BASE COURSE - TYPE B	TON	31.000		
4010005	PRIME COAT	GAL	495.000		
4011004	LIQUID ASPHALT BINDER PG64-22	TON	14.000		
4020320	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE B	TON	13.000		
4030320	HOT MIX ASPHALT SURFACE COURSE TYPE B	TON	11.000		
4030340	HOT MIX ASPHALT SURFACE COURSE TYPE C	TON	184.000		
6020005	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF	86.000		
6250025	24" WHITE SOLID LINES (STOP/DIAGONAL LINES)-FAST DRY PAINT	LF	16.000		
6250110	4"YELLOW SOLID LINE(PVT.EDGE&NO PASSING ZONE)-FAST DRY PAINT	LF	100.000		

6271025	24" WHITE SOLID LINES (STOP/DIAG LINES)-THERMO.-125 MIL	LF	16.000		
6271074	4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	LF	100.000		
6510105	FLAT SHEET, TYPE III, FIXED SZ. & MSG. SIGN	SF	7.000		
6531210	U-SECTION POST FOR SIGN SUPPORTS - 3P	LF	12.000		
7141112	15" RC PIPE CUL.-CLASS III	LF	284.000		
7142513	18" R. C. PIPE CUL. BEVELED END SECTN-CL 3	EA	1.000		
7141113	18" RC PIPE CUL.-CLASS III	LF	76.000		
7192105	MANHOLE	EA	1.000		
8041020	RIP-RAP (CLASS B)	TON	12.000		
8048215	GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 2)TYPE D	SY	15.000		
8100001	PERMANENT VEGETATION	MSY	1.976		
8103100	TEMPORARY VEGETATION	MSY	1.976		
8151110	TEMPORARY EROSION CONTROL BLANKET (ECB)	MSY	1.240		
8151203	HYDRAULIC EROSION CONTROL PRODUCT (HECP) - TYPE 3	ACRE	0.817		
8152007	SEDIMENT TUBES FOR DITCH CHECKS	LF	128.000		
8153000	SILT FENCE	LF	100.000		
8156490	STABILIZED CONSTRUCTION ENTRANCE	SY	270.000		
7191225	CATCH BASIN -TYPE 9 WITH WEIR	EA	1.000		
7192010	DROP INLET (24" X 24")	EA	1.000		
8156210	INLET STRUCTURE FILTER - TYPE B	EA	2.000		

WILLARD LOOP - D&F Project No.: 031810-02					
ITEM NO.	DESCRIPTION	UNIT	ENGINEER'S ESTIMATE	CONTRACTOR'S ESTIMATE	UNIT PRICE
1031000	MOBILIZATION	LS	NEC		
1050800	CONSTRUCTION STAKES, LINES & GRADES	EA	1.000		
1061100	QUALITY CONTROL FOR EARTHWORK	LS	1.000		
1061200	QUALITY CONTROL FOR BASES AND SUBBASES	LS	1.000		
1071000	TRAFFIC CONTROL	LS	NEC		
1090200	AS-BUILT CONSTRUCTION PLANS	LS	1.000		
2011000	CLEARING & GRUBBING WITHIN RIGHT OF WAY	LS	NEC		
2031000	UNCLASSIFIED EXCAVATION	CY	4,788.000		
2033000	BORROW EXCAVATION	CY	5,336.000		
2034000	MUCK EXCAVATION	CY	2,150.000		
2081001	FINE GRADING	SY	NEC		
2103000	FLOWABLE FILL	CY	172.000		
3050108	GRADED AGGREGATE BASE COURSE (8" UNIFORM)	SY	13,550.000		
3069900	MAINTENANCE STONE	TON	100.000		
3100320	HOT MIX ASPHALT BASE COURSE - TYPE B	TON	30.000		
4010005	PRIME COAT	GAL	3,659.000		
4011004	LIQUID ASPHALT BINDER PG64-22	TON	86.000		
4020320	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE B	TON	27.000		
4030320	HOT MIX ASPHALT SURFACE COURSE TYPE B	TON	14.000		

4030340	HOT MIX ASPHALT SURFACE COURSE TYPE C	TON	1,297.000		
6020005	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	SF	168.000		
6250025	24" WHITE SOLID LINES (STOP/DIAGONAL LINES)-FAST DRY PAINT	LF	95.000		
6250110	4"YELLOW SOLID LINE(PVT.EDGE&NO PASSING ZONE)-FAST DRY PAINT	LF	100.000		
6271025	24" WHITE SOLID LINES (STOP/DIAG LINES)-THERMO.-125 MIL	LF	95.000		
6271074	4" YELLOW SOLID LINES(PVT.EDGE LINES) THERMO-90 MIL.	LF	100.000		
6301100	PERMANENT YELLOW PAVEMENT MARKERS BI-DIR.- 4"X4"	EA	61.000		
6510105	FLAT SHEET, TYPE III, FIXED SZ. & MSG. SIGN	SF	61.750		
6531210	U-SECTION POST FOR SIGN SUPPORTS - 3P	LF	125.000		
714111C	72" RC PIPE CUL.-CLASS III	LF	48.000		
7141112	15" RC PIPE CUL.-CLASS III	LF	128.000		
7141113	18" RC PIPE CUL.-CLASS III	LF	80.000		
7141114	24" RC PIPE CUL.-CLASS III	LF	56.000		
7141124	24" RC PIPE CUL.-CLASS IV	LF	80.000		
7141128	48" RC PIPE CUL.-CLASS IV	LF	48.000		
7141132	15" RC PIPE CUL.-CLASS V	LF	112.000		
7142513	18" R. C. PIPE CUL. BEVELED END SECTN-CL 3	EA	2.000		
7142514	24" R. C. PIPE CUL. BEVELED END SECTN-CL 3	EA	2.000		
7143014	24" R. C. PIPE CUL. BEVELED END SECTN-CL 4	EA	4.000		
7143512	15" R. C. PIPE CUL. BEVELED END SECTN-CLASS V	EA	4.000		
8011400	AGGREGATE UNDERDRAIN (AGGR.NO. 57)	CY	64.000		
8041020	RIP-RAP (CLASS B)	TON	296.000		
8048215	GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 2)TYPE D	SY	389.000		
8051155	MT2 LEADING END TREATMENT TL2	EA	8.000		
8052150	MGS3CS GR COMPRESSED SHOULDER	LF	400.000		
8081000	MOVING ITEM NO.	LS	1.00		
8100001	PERMANENT VEGETATION	MSY	14.973		
8103100	TEMPORARY VEGETATION	MSY	14.973		
8151101	TURF REINFORCEMENT MATTING (TRM) TYPE 1	MSY	0.363		
8151110	TEMPORARY EROSION CONTROL BLANKET (ECB)	MSY	7.950		
8151203	HYDRAULIC EROSION CONTROL PRODUCT (HECP) - TYPE 3	ACRE	6.187		
8152007	SEDIMENT TUBES FOR DITCH CHECKS	LF	624.000		
8153000	SILT FENCE	LF	200.000		
8156490	STABILIZED CONSTRUCTION ENTRANCE	SY	275.000		

Bidder: _____
 Signature: _____
 Title: _____
 Dated: _____