

PLANTING PLAN NOTES

- THE TREES SHALL BE PURCHASED FROM THE FOLLOWING TREE NURSERIES:
1. PALM TREES UNLIMITED, INC.
2. SELECT TREES
3. SHADY GROVE NURSERY
4. CHERRY LAKE FARMS
5. WILDWOOD NURSERIES
6. CAROLINA LANDSCAPE SUPPLY
7. SKINNERS WHOLESALE NURSERY
- THE LANDSCAPE ARCHITECT SHALL PRE-TAG AND APPROVE ALL TREES. IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO PROVIDE ALL COORDINATION AND SCHEDULING NECESSARY WITH THE NURSERY.
- SIZE AND GRADING STANDARDS OF PLANT MATERIAL SHALL CONFORM TO THE LATEST EDITION OF "USA STANDARDS FOR NURSERY STOCK", BY THE AMERICAN ASSOCIATION OF NURSERYMEN, INC.
- ALL TREES AND SHRUBS SHALL CONFORM TO THE TRADE CLASSIFICATION OF "HEAVY SPECIMEN" AND SHALL EXHIBIT DISTINCTIVE CHARACTER AND FORM.
- HEIGHT AND WIDTH SPECIFICATIONS INDICATED ON PLANT SCHEDULE SHALL TAKE PRECEDENCE OVER CONTAINER SIZE.
- ALL ANNUAL/PERENNIAL BEDS SHALL BE AMENDED BY THE CONTRACTOR PER THE SPECIFICATIONS AND RAISED 8" ABOVE EXISTING OR PROPOSED GRADE. CONTRACTOR SHALL PROVIDE TOPSOIL AS REQUIRED TO RAISE GRADES.
- CONTRACTOR SHALL MULCH ALL SHRUB BEDS WITH 4" OF DOUBLE HAMMERED SHREDDED HARDWOOD MULCH. CONTRACTOR SHALL MULCH ALL ANNUAL/PERENNIAL BEDS WITH 1" OF PINE BARK FINES.
- LANTANA AND SEA HOLLY SHALL BE PLANTED WITH PRECISE EDGES AS SHOWN IN THE PLAN.
- CONTRACTOR SHALL REMOVE ALL HARD LUMPS OF CLAY, STONES OVER 1" IN DIAMETER, AND ALL CONSTRUCTION DEBRIS INCLUDING GRAVEL, LIMES AND OTHER DELETERIOUS MATTER WHICH WOULD BE HARMFUL, OR PREVENT PROPER ESTABLISHMENT AND/OR MAINTENANCE OF LAWN AND PLANTING AREAS.
- IN AREAS WHERE CONSTRUCTION GRAVEL IS EMBEDDED IN THE SOIL, CONTRACTOR SHALL REMOVE CONTAMINATED SOIL TO A DEPTH OF 8" AND FILL WITH CLEAN TOPSOIL. CONTRACTOR SHALL IMPORT TOPSOIL AT NO CHARGE TO OWNER IF REQUIRED TO FILL THESE EXCAVATIONS.
- CONTRACTOR SHALL RESEED/RESOIL LAWN AREAS DAMAGED DUE TO PLANT MATERIAL INSTALLATION.
- CONTRACTOR SHALL COORDINATE ALL PLANTING IN THE RIGHT-OF-WAY WITH THE SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION OR LOCAL TRANSPORTATION DEPARTMENT.
- ALL STRAPPING AND TOP 2/3 OF WIRE BASKET SHALL BE CUT AWAY AND REMOVED BY THE CONTRACTOR FROM ROOT BALL PRIOR TO BACKFILLING PLANTING PIT. CONTRACTOR SHALL REMOVE TOP 1/3 OF THE BURLAP FROM ROOT BALL.
- BERMUDA TURF SHALL BE SODDED IN THE CONTEMPLATIVE GARDEN AREA ONLY. AREAS OF SHADE SHALL BE SODDED WITH ST. AUGUSTINE TURF AS INDICATED ON THE PLAN. AREAS OF SUN SHALL BE SODDED WITH CENTREDEE TURF AS INDICATED ON THE PLAN.
- TREES LOCATED WITHIN LAWN AREAS AND EXCLUSIVE OF SHRUB BEDS SHALL HAVE A MAXIMUM MULCH AREA OF 30" DIA. PER TREE. 4" SAUCER BERM SHALL NOT BE INCLUDED AS PART OF THIS ALTERNATE TREE INSTALLATION. 30" DIA. MULCH AREA SHALL BE SHREDDED HARDWOOD MULCH.

SEE SHEET L5.1 FOR PLANT SCHEDULE

LEGEND

- SYMBOL**
- EXISTING TREE
 - PROPOSED TREE
 - PROPOSED PALM TREE
 - PROPOSED SHRUBS
 - PROPOSED GROUNDCOVER (HATCH PATTERN VARIES)
 - PROPOSED SOO
 - PROPOSED ANNUALS

DETAIL


5 & 6/L6.3

7/L6.3

2/L6.3

1/L6.3

SEE NOTE 14



SURVEY DISCLAIMER

TOPOGRAPHIC AND BOUNDARY SURVEY PROVIDED BY DAVID S. YOUNG, 1613 PARIS AVENUE, PORT ROYAL, SC 29955, (843) 524-3261, DATED JANUARY 6, 2002



200 South Tryon Street
Suite 1400
Charlotte, North Carolina 28202
Tel 704.376.1555
Fax 704.376.7851
www.colejeneststone.com

**CITY OF
BEAUFORT**

302 CARTERET STREET
POST OFFICE BOX 1167
BEAUFORT, SC 29901

**HENRY C.
CHAMBERS
WATERFRONT
PARK**

950 BAY STREET
BEAUFORT, SC 29902

**PLANTING PLAN
PART C**

Project No.

2593

Issued

02/28/05 - ISSUED FOR BID

Revised



SCALE: 1" = 20'
0 10 20 40

L5.3 of

The drawings, the project manual and the design shown thereon are instruments of ColeJenest & Stone, P.A. The reproduction or unauthorized use of the documents without consent of ColeJenest & Stone, P.A. is prohibited.

ColeJenest & Stone, P.A. 2005 ©

