

ADDENDUM NO. 2

APRIL 29, 2020

CITY OF ORANGE BEACH, ALABAMA

RECREATION CENTER DRAINAGE AND TENNIS COURT IMPROVEMENTS

CONTRACT DOCUMENTS, PROPOSAL and SPECIFICATIONS

DELETE: SECTION V – PROPOSAL, SCHEDULE OF ITEM PAGES V-1 through V-8

ADD: SECTION V – PROPOSAL, SCHEDULE OF ITEM PAGES V-1 through V-8
*(attached to this addendum)

Noted changes:

- Line item # 9 has been revised to state "Foundation Backfill, Local (12" thick) (214-B). This was a typographical error. This is granular foundation backfill for stormwater boxes and pipe.
- Line item #35 Fence Reset has been added. This is for the existing residential wooden fence that will have to be removed and reset for the installation of the proposed stormdrain improvements east of the north end of Avenue "B" (Tiger Brown Lane) shown on sheets 5 and 8 of the plan set.



Authorized

4-29-20

Date

Acknowledgement

Date

SECTION V

PROPOSAL

DATE: _____

Proposal of _____

Alabama License No. _____ for constructing **Orange Beach REC Center Drainage and Tennis Center Court Improvements**, for the performance of all work and the furnishing of all labor and materials required by the Contract terms, specifications, and special provisions.

The specifications are attached hereto and specified and made a part hereof.

TO: **City of Orange Beach, Alabama**

Dear Sirs:

The following proposal is made on behalf of _____ and no others. Evidence of authority to submit the proposal is herewith furnished. The proposal is made without collusion on the part of any person, firm, or corporation.

___ certify that ___ have carefully examined the plans for this project and the specifications hereto attached including the special provisions, and have also personally examined the site of work. On the basis of the specifications and plans ___ propose to furnish all necessary machinery, tools, apparatus, and other means of construction, and do all the work and furnish all the material in the manner specified.

___ further agree to complete all the work in **EIGHTY (80) working days**.

___ understand that the quantities below are approximate only and are subject to either increase or decrease, and hereby propose to perform any increased or decreased quantities of work at the unit prices bid.

___ further propose to perform all "Force Account or Extra Work" that may be required of ___ on the basis provided in the specifications hereto attached, and to give such work _____ personal attention in order to see that it is economically performed.

___ further propose to execute the attached Contract Agreement as soon as the work is awarded to ___ and to begin and complete the work within the respective time limit provided for in the specifications and Notice to Contractors hereto attached.

The following items shall be constructed in accordance with the State of Alabama Department of Transportation Standard Specifications for Highway Construction, Latest Edition, and the City of Orange Beach Design and Construction Standard, with all the latest additions and amendments, except as modified herein:

NOTES:

1. The following unit prices shall include all labor, materials, equipment removal, overhead, profit, insurance, etc., to cover the finished work of the several kinds called for.
2. Bidder understands that the Owner reserves the right to reject any and all bids.
3. The Bidder understands that he must submit this entire booklet with the bid.
4. The Bidder understands that the unit prices govern for all pay items pricing submitted.

SCHEDULE OF ITEMS
Orange Beach REC Center Drainage and Tennis Center Court Improvements

ITEM #	DESCRIPTION	UNIT	QTY	UNIT PRICE	AMOUNT
DRAINAGE CONSTRUCTION ITEMS					
1	CLEARING AND GRUBBING (201-A)	LS	1		
2	ASPHALT REMOVAL (PARKING LOT AND ROAD) (206-C)	SY	400		
3	CONCRETE CURB REMOVAL (206-D1)	LF	40		
4	PIPE REMOVAL (206-D2)	LF	2,332		
5	CONCRETE REMOVAL (206-C)	SY	17		
6	INLET/BOX REMOVAL (206-E)	EA	3		
7	UNCLASSIFIED EXCAVATION (PONDS AND DITCH) (210-A)	CY	5,550		
8	STRUCTURE EXCAVATION (214-A)	CY	75		
9	FOUNDATION BACKFILL, LOCAL (12" THICK) (214-B)	CY	300		
10	FOUNDATION BACKFILL, COMMERCIAL (6" THICK) (ALDOT #57) (214-B)	CY	65		

11	CRUSHED AGGREGATE BASE COURSE, 825-B, 6" THICK (301-A)	SY	510		
12	TACK COAT (PARKING LOT, ROADWAY) (405-A)	GAL	310		
13	MILLING/PLANING EXISTING PAVEMENT (1" THICK) (408-A)	SY	150		
14	BITUMINOUS CONCRETE WARING SURFACE LAYER, 1.0" THICK (1103/SY) (424-A)	TONS	200		
15	BITUMINOUS BINDER LAYER, 2.0" THICK (220#/SY) (424-B)	TONS	60		
16	12" STORM SEWER PIPE, HDPE (INCLUDES INLET CONNECTION) (533-A1)	LF	10		
17	30" STORM SEWER PIPE, RCP (533-A2)	LF	304		
18	28"X18" STORM SEWER ARCH PIPE, RCP (533-B1)	LF	176		
19	36"X22" STORM SEWER ARCH PIPE, RCP (533-B2)	LF	152		
20	44"X27" STORM SEWER ARCH PIPE, RCP (533-B3)	LF	624		
21	51"X31" STORM SEWER ARCH PIPE, RCP (533-B4)	LF	40		
22	MOBILIZATION (FOR DRAINAGE AND TENNIS COURTS) (600-A)	LS	1		
23	RIP-RAP, CLASS II, 2 FT THICK (610-A)	TONS	88		
24	FILTER BLANKET, 7OZ. NON-WOVEN (610-D)	SY	72		
25	SLOPE PAVING (CONCRETE FLUME) (614-A)	CY	7		

26	CONCRETE SIDEWALKS, 4" THICK (618-A)	SY	15		
27	SLOPED PAVED HEADWALL (DOUBLE 30") (619-A)	EA	1		
28	SLOPED PAVED HEADWALL (SINGLE 36"X22") (619-B1)	EA	2		
29	SLOPED PAVED HEADWALL (SINGLE 44"X27") (619-B2)	EA	3		
30	SLOPED PAVED HEADWALL (SINGLE 51"X31") (619-B3)	EA	1		
31	WEIR INLETS (621-C1)	EA	1		
32	OUTFALL CONTROL BOX (POND 2) (621-C2)	EA	1		
33	GRATE INLETS (621-G)	EA	4		
34	COMBINATION CURB AND GUTTER, TYPE K (623-C)	LF	40		
35	FENCE RESET (637-A) (RESIDENTIAL WOOD PRIVACY FENCE)	LF	40		
36	MINOR UTILITY ADJUSTMENT (WATER) (640-B1)	LS	1		
37	MINOR UTILITY ADJUSTMENT (SEWER) (640-B2)	LS	1		
38	TOPSOIL FROM STOCKPILES (4" THICK) (650-B)	CY	1,500		
39	SEEDING (652-A1)	ACRE	1		
40	HYDROSEED (DITCH, POND BOTTOMS) (652-A2)	ACRE	2		

41	SOLID SODDING (POND SLOPES) (654-A)	SY	3,200		
42	MULCHING (656-A)	ACRE	4		
43	ROLLED EROSION CONTROL BLANKET (NORTH AMERICAN GREEN SC 150BN) (659-C)	SY	2,750		
44	TEMPORARY SEEDING (665-A)	ACRE	4		
45	TEMPORARY MULCHING (665-B)	ACRE	4		
46	HAY BALES (665-F)	EA	25		
47	SAND BAGS (665-G)	EA	100		
48	SILT FENCE, TYPE A (665-J)	LF	3,840		
49	WATTLES (665-Q)	LF	400		
50	STONE CONSTRUCTION ENTRANCE (INCLUDES MAINTENANCE) (999-1)	EA	2		
51	PARKING LOT STRIPING (999-2)	LS	1		
DRAINAGE SUBTOTAL					
TENNIS COURT IMPROVEMENT ITEMS					
52	REMOVE EXISTING PLAYING SURFACE, DISPOSE OF MATERIALS APPROPRIATELY (D-101)	SF	56,746		
53	REMOVE EXISTING LIGHT POLE & BASE, DISPOSE OF MATERIALS APPROPRIATELY (D-102)	EA	48		

54	REMOVE EXISTING FENCING & GATES, DISPOSE OF MATERIALS APPROPRIATELY (D-103)	LF	1,892		
55	REMOVE EXISTING POST & NET ASSEMBLY, DISPOSE OF MATERIALS APPROPRIATELY (D-104)	EA	8		
56	DETACH SHADEW STRUCTURE FROM EXISTING BENCH, COORDINATE STORAGE LOCATION W/OWNER FOR FUTURE RE-USE. REMOVE EXISTING BENCH, DISPOSE OF MATERIAL APPROPRIATELY (D-105)	EA	4		
57	REMOVE EXISTING TREE, DISPOSE OF MATERIALS APPROPRIATELY (D-106)	EA	30		
58	REMOVE EXISTING CONCRETE, SAW CUT EDGE TO ENSURE CLEAN TRANSITION, DISPOSE OF MATERIALS APPROPRIATELY (D-107)	SF	1,055		
59	REMOVE EXISTING NETTING, CABLE & ASSOCIATED HARDWARE, COORDINATE STORAGE LOCATION WITH OWNER FOR FUTURE RE-USE (D-108)	LF	99		
60	REMOVE EXISTING ROCK MULCH, DISPOSE OF MATERIALS APPROPRIATELY (D-109)	SF	7,533		
61	ASPHALT (WEARING SURFACE 110 LBS/SY), ATHLETIC SURFACING WITH LAYKOLD CUSHION PLUS W/TREME SYSTEM FINISH, COLORS TO MATCH EXISTING AND APPROVED BY LANDSCAPE ARCHITECT OR OWNERS AGENT (32-01)	SY	6,235		
62	ASPHALT BINDER LAYER, 220 LBS/SY, INCLUDES TACK COAT LAYER (429-B) (32-01)	TONS	717		
63	CRUSHED AGGREGATE BASE COURSE, 825-B, 6" THICK (301-A) (32-01)	SY	6,235		
64	SEPARATION FABRIC (MIRAFI 500 X) (608-A) (32-01)	SY	6,235		
65	10' BLACK PVC COATED ALUMINUM CHAINLINK WITH 9' BLACK WINDSCREENS (32-02)	LF	1,585		
66	FENCE, 4' BLACK PVC COATED ALUMINUM CHAINLINK (32-03)	LF	309		

67	7' HT GATE, BLACK PVC COATED ALUMINUM CHAINLINK (32-04)	EA	8		
68	GATE, 10' WIDE DOUBLE, BLACK PVC COATED ALUMINUM CHAINLINK (32-05)	EA	4		
69	ASPHALT POST & NET ASSEMBLY, EQUAL TO OR BETTER THAN EDWARDS 40LS (32-06)	EA	8		
70	4' CONCRETE SIDEWALK, 3,000 PSI CONCRETE (32-07)	SF	717		
71	CONCRETE, 16" RIBBON CURB, 3,000 PSI (32-08)	LF	1,909		
72	REINSTALL NETTING, CABLE & ASSOCIATED HARDWARE (32-09)	LF	104		
73	ROCK MULCH, 1"-3" OVERSIZED SMOOTH WHITE ROCK, 3" DEPTH (32-10)	CY	87		
74	POST SLEEVE, SHADE STRUCTURE SLEEVE, CONTRACTOR TO VERIFY SLEEVE SPACING PER EXISTING SHADE STRUCTURE POST SPACING (32-11)	EA	8		
75	4" PVC UNDERDRAIN (INCLUDES PERFORATED PIPE, PIPE FITTINGS, ROCK BACKFILL, FILTER FABRIC, CONNECTION TO INLET)	LF	645		
76	LIGHTING (SHEETS 27-28)	LS	1		
77	FURNITURE (SHEET 29)	LS	1		
TENNIS COURT IMPROVEMENTS SUBTOTAL					
BASE BID (DRAINAGE AND TENNIS COURT IMPROVEMENTS) TOTAL					

ADDITIVE/DEDUCTIVE ALTERNATE NO. 1					
1	ASPHALT (WEARING SURFACE 110 LBS/SY), ATHLETIC SURFACING WITH LAYKOLD MASTERS GEL SYSTEM FINISH, COLORS TO MATCH EXISTING AND APPROVED BY LANDSCAPE ARCHITECT OR OWNERS AGENT (32-01)	SY	6,235		

CONTRACTOR'S NAME & GENERAL CONTRACTOR'S LICENSE NUMBER

_____ also propose to furnish a Contract Performance Bond, approved by the Owner in an amount equal to the total amount of the bid. This bond shall serve not only to guarantee the completion of the work on _____ part, but also to guarantee the excellence of both workmanship, and materials until the work is finally accepted.

Signature of Bidder (If Firm or Individual) _____

By: _____

Address of Bidder _____

Names and Addresses of Members of Firm _____

Signature of Bidder (Corporation) _____

_____ Business Address _____
President

_____ Business Address _____
Sect. & Treas.

Attest: _____ Incorporated in _____ State

(CORPORATE SEAL)