

Addendum No. 1 Proposed Street off of Trillium Drive in the
Arcadian Springs Subdivision
Anderson County Bid No. 2042

This addendum shall become a part of the project plans and specifications and shall be acknowledged on the bid form.

Addendum Date: 07-17-20

Questions and Answers that have been asked since the plans have been issued are as follows.

- 1) ITEM 1 Page 3 states project completion at 120 Days. ITEM 2 Page 2 No. 5 states project completion at 30 Days. Please clarify.

30 days is correct. We will revise the amount on Item 1, Page 3

- 2) When visiting site we noticed an existing private light pole that from drawings seems to indicate it will need to be removed. Where does this pay and is it contractors' responsibility to replace?

The radius will be revised from 50' to 30' to stay away from the light pole and some of the trees.

- 3) Is the intended end-wall to be used detailed in standard drawing D-SEW-1A?

The end-walls should be Straight End-walls shown on TDOT Standard Drawing D-PE-4.

- 4) 15" HDPE pipe is shown on both present and proposed layouts. Is HDPE the intended pipe material for the pipe culvert?

HDPE is the intended pipe material for the pipe culvert.

- 5) The Special Provisions mention payment for span type structures. I would like to confirm that there are no span type structures on this project.

There are no span type structures on this project.

Plans Revisions:

- 1) On Item 1, Page 3, Note 13, the Colander Days were changed from 120 days to 30 days.
- 2) On Sheet 9 of the plans, the radius on the east side of the proposed road was changed from 50 feet to 30 feet.

Revised half sized plan and specifications are attached or full size plans can be picked up if needed at the office of Robert G. Campbell and Associates at 7523 Taggart Lane, Knoxville Tennessee.