



THE CITY OF DAYTONA BEACH OFFICE OF THE PURCHASING AGENT

Post Office Box 2451
Daytona Beach, Florida 32115-2451

Phone (386) 671-8080
Fax (386) 671-8085

ADDENDUM NO. 2

DATE: July 30, 2018
PROJECT: ITB 0318-2060
NOVA ROAD MEDIAN LANDSCAPING

OPENING DATE: August 9, 2018

This addendum is hereby incorporated into the Bid Documents for the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~striketrough~~.

1. Answers to Bidders' written questions:

Q1: How is the contractor to be paid for the revamping of existing irrigation system. I do not see a line item for this service. And being that we as bidders do not know what all to the extent of repairs that would have to be made. Could a cost per item sheet be included in bid form for Pipe, Valves, Heads Etc. so that way the City already has a price cost for each of the items. This price sheet could be part of the bid, but not as part as the total LS of the bid.

A1: Please refer to LANDSCAPE NOTES #8, last 2 sentences: "THE COST OF THIS WORK WILL BE INCLUDED IN THE UNIT COST FOR PLANT MATERIALS. THE COST OF ANY SUCH REPAIRS SHALL BE CONSIDERED PART OF THE UNIT PLANT COSTS." Also, the third sentence should be clarified to read "This work is to include all labor and materials necessary to provide 100% coverage of all new plantings and to insure that spray patterns do not encroach into the existing drive lanes and remain within landscape medians."

Q2: On page LD-4 of the plans Under "Special Bed Preparation" Note #1 reads that the contractor is to perform soil test and percolation test to determine how much excavation will be required to remove and haul in soil mix for all plant beds. But note # 3 says that the contractor is to excavate down 12" to remove existing grass, lime rock and all debris in all plant bed areas and replace with Plant Soil Mix. I do not see a design for the mix or a PH. So we will need this information. My question is, Note #3 tells us what is expected and Note #1 leaves a large "Question" on what we are to bid on. Note #3 seems to be the best way to go for all fairness in bidding. Note #2 Reads that the contractor is to perform a percolation test for the palms by digging a 6"x36" depth hole to monitor percolation rate per hour. That note I understand. So do we follow Note #3 for removing 12" of existing soil and bring in top soil mix design for all plant beds as the Note says?

A2: Under Special Bed Preparation Notes: DELETE NOTE #1, KEEP NOTE #2, AND MODIFY NOTE #3 TO READ "PRIOR TO INSTALLATION OF ANY PLANT MATERIAL, EXISTING SOD, LIMEROCK, COMPACTED SUBGRADE, CONSTRUCTION DEBRIS OR ANY OTHER MATERIAL DETRIMENTAL TO HEALTHY PLANT GROWTH SHALL BE REMOVED AND DISPOSED OF OFFSITE. REPLACEMENT SOIL SHALL BE SIMILAR TO POTTING SOIL MIXES USED BY LOCAL NURSERIES AND CONTAIN 1/3 SAND, 1/3 PEAT AND 1/3 GROUND BARK WITHIN A pH range of 6 to 6.5. CONTRACTOR SHALL PROVIDE A SOIL SAMPLE WITH A TEST RESULT OF pH AND NUTRIENT MAKEUP FOR APPROVAL PRIOR TO INSTALLATION.

2. All other terms and conditions remain the same.

The Bidder shall acknowledge receipt of this addendum on the Bid Proposal Form.

The City of Daytona Beach

Kirk Zimmerman, CPPB
Buyer