



HIGHLANDS COUNTY BOARD OF COUNTY
COMMISSIONERS (HCBCC)
PURCHASING DIVISION
600 S. Commerce Ave
Sebring, FL 33870
(863) 402-6500

DATE: June 1, 2023

BID NO. ITB 20-023-LKD ADDENDUM No. 3

Project.: Istokpoga Marsh Watershed Improvement District (IMWID) Impoundment Project Phase II Highlands County Project No. 14041

The following represents clarification, additions, deletions, and/or modifications to the above referenced solicitation. This addendum shall hereafter be regarded as part of the solicitation. Items not referenced herein remain unchanged. Words, phrases or sentences with a strikethrough represent deletions to the original solicitation. Underlined words and bolded, phrases or sentences represent additions to the original solicitation, as applicable.

This addendum is being issued to revise the deadline for submittal of bids and answer questions received on this solicitation.

1. The deadline for bid submittal is **Tuesday, June 13, 2023**, prior to 3:30 PM, Purchasing Department.
2. The deadline for RFI is Thursday, June 1, 2023.

Questions and Answers

Q1	Project Compliance Requirements: Yes/No Davis Bacon Section 3 WMBE E-Verify Jessica Lunsford Other:
A1	Davis Bacon: not included in this project Section 3: not included in this project WMBE: See page 4, Section 00250-5 E-Verify: See Section 00100-2, 00160-6, 00250-4 Jessica Lunsford: not included in this project Other: would need to better define question.
Q2	General Contractor Project Responsibility: Yes/No Building Permit Fees Permit Submission Payment & Performance Bond

	Construction Material Testing Final As-Built Survey
A2	Building Permit Fees: Section 6.08, page 20 Permit Submission: Would need to better define the question. Payment & Performance Bond: Section 00410 Construction Material Testing: See Section 00700 6.03. 6.26, Article 13 Bid form Section 00300-6, Final As-Built Survey: yes
Q3	We have reviewed the plans and specs for ITB No: 20-023-LKD Istokpoga Marsh Watershed Improvement District (IMWID) Impoundment Project Phase II Highlands County Project No. 14041 and respectfully request Golden Harvest, Inc. be named as an acceptable supplier for the sluice gate as shown on Drawing CD-4. Attached is a typical drawing and specification for your review.
A3	The County will approve Golden Harvest, Inc. as an equal vendor
Q4	For ITB 20-023-LKD for the IMWID Above Ground Impoundment, can you please verify that the County is requiring Ten Million Dollars in Excess/Umbrella insurance coverage (page 28 of the ITB)?
A4	Yes, this is a required coverage and limit for this project.
Q5	What is the GPM's (Flow) of the new pumps?
A5	Pump 1 and pump 2 will be 15,000 gallons per minuet (GPM)
Q6	The discharge pipe is rooted out, it needs to be replaced?
A6	See Construction Specification 11210-Stormwater Pump Relocation
Q7	The platform legs are in concrete I believe. Can we replace it with a new platform?
A7	See Construction Specification 11210-Stormwater Pump Relocation
Q8	The gear head on the pump is leaking oil and will need to be rebuilt?
A8	See Construction Specification 11210-Stormwater Pump Relocation
Q9	Will the pump that is get relocated be converted to grease also?
A9	No
Q10	Lori, would you please also put in the addendum for the people at the meeting on last Thursday.
A10	See attachment A3-3 Pre-Bid Sign-in Sheet.
Q11	The emergency overflow line work information found on plan sheet C-7, revision C-7 of the supplemental drawings and the AutoCAD files does not match the information found on sheet CD-5. Can you clarify which sheet is to be used for the emergency overflow?
A11	The detail on CD-5 will govern.
Q12	Can you provide any information on the existing culverts that need to be removed? (Example size and type)
A12	The culverts are approximately 18" CMP.

Q13	With the revisions to the seepage ditch included in the supplemental drawings is P-4 culvert (sheet C-3 and CD-6) still being constructed? If so is the 25' dimension between TOB and TOB still apply?
A13	Yes. The dimension between TOB and TOB is 40' as indicated on sheet 2 of 9 of the Supplemental Drawings.
Q14	Sheet CD-8 calls out to seed and mulch the side slopes of the seepage ditch to the water line. Can you clarify what elevation the water line is that we need to seed and mulch to?
A14	Elevation 28.5
Q15	In regards to the change to the impoundment area fence that was revised in addendum 1(revised perimeter fence note only shows for sheet C-1 through C-3), Can you clarify if all the existing fence along the north, east and south perimeter of the impoundment area is to get removed and replace with new fence? If so can you clarify if it's the 4 strand barded wire fence or 5 strand barbed wire fence?
A15	All perimeter fencing shall be replaced with four (4) strand barbed wire.
Q16	Can you clarify on what items of the pump house relocation is be replace or relocated?
A16	See Construction Specification 11210-Stormwater Pump Relocation
Attachments:	A3-1 40-SC-WALL-HW Model A3-2 GH 40 Open or Submerged Aluminum Slide Gate A3-3 Pre-bid Sign-in Sheet