



**GRANGER PARK – WATER QUALITY POND
STORMWATER IMPROVEMENT PROJECT**

CITY OF LAGRANGE

ADDENDUM NO. 4

MARCH 13, 2017

To: Bidders

From: City of LaGrange and Rindt-McDuff Associates

CLARIFICATIONS AND RESPONSES TO CONTRACTOR QUESTIONS:

Overall Project Clarification: The average depth of dredged material to excavate over the total area of the pond (within the disturbed limits) is approximately 1.5 feet. The depth of excavation ranges from 0 - 4.3 feet, as shown on the drawings. **Before refilling the pond, the contractor shall submit for approval to the Engineer final survey elevations of the pond bottom at a minimum of 8 locations throughout the pond area including the inlet ditches. A survey point file is sufficient.**

1 – After dewatering the pond, can the contractor get into the pond with equipment without the use of mats or temporary platforms?

Response 1: As a clarification to Dredging Note 3 on Sheet 4 of the Drawings, the contractor may enter the drained pond itself to access the dredge material without the use of swamp mats or temporary platforms. However, swamp mats or temporary platforms are required for equipment crossing any vegetated area within the 25' state water buffer, including the location of access to the pond.

2 – Will the contractor need to get a road bond for the residential roads we are coming out on? Or is the city going to be responsible if something should happen to the road due to dump trucks?

Response 2: No, a road bond will not be required. However, the contractor is expected to keep all streets clear of mud and tracked debris as per outlined in the specs.

3 – Is there a place on the bid form to list Addenda received?

Response 3: No, there is not a place on the bid form. Bidders are to confirm receipt of all Addenda via email to RMA by the date and time of the bid opening.