



- DEMOLITION NOTES:**
1. SEQUENCE DEMOLITION TO MINIMIZE DISRUPTION TO EXISTING ACTIVITIES WITHIN THE CONSTRUCTION ZONE.
 2. VERIFY LOCATION OF ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION. COORDINATE RELOCATION AND PROTECTION OF ALL UNDERGROUND UTILITIES WITH LOCAL SERVICING AGENCIES.
 3. ALL CONSTRUCTION ACTIVITIES ARE TO BE SECURED AND BARRICADED.
 4. CARE MUST BE TAKEN TO PROTECT PRIVATE PROPERTY. DAMAGE CLAIMS ARE THE SOLE RESPONSIBILITY OF THE CONTRACTOR.
 5. DEPTH OF DEMOLITION TO EXTEND TO SUBGRADE.
 6. SAW CUT EXISTING PAVEMENT AND PROVIDE BARRICADES AS REQUIRED DURING CONSTRUCTION.
 7. PROVIDE INLET PROTECTION FOR EROSION CONTROL AS NOTED.
 8. ANY ASPHALT DAMAGED DURING THE COURSE OF CONSTRUCTION SHALL BE REPAIRED BY THE CONTRACTOR.



BRYAN PRICE ENGINEERING
 865 COKER FORD ROAD
 PORTLAND, TENNESSEE 37148
 PHONE: 615-481-3176 EMAIL: BRYAN.PRICE@REACAN.COM

REVISIONS	DATE

DATE:	DECEMBER 2017
DRAWN BY:	PRICE
CHECKED BY:	PRICE
APPROVED BY:	PRICE

DEMOLITION PLAN
 PEAY PARK SPLASH PAD
 CITY OF GOODLETTSVILLE
 DAVIDSON COUNTY, TENNESSEE

SHEET NO.
C2.0