

**Request for Proposal # 1718-10-03-01
Brawley Street Sewer Extension Project
Spartanburg Northside**

submits herewith our proposal in response to the bid request.

_____ (Company Name)

Unit Cost

Item	Description	Unit	Qty.	Unit Price	Total
1	8" PVC sanitary sewer line (0' to 6' deep) See SWS Technical Specifications	L.F.	130		
2	Sanitary sewer man holes (0' to 6' deep) See SWS Technical Specifications	Ea.	2		
3	Sanitary sewer man holes (0' to 6' deep) Dog house over existing sewer line	Ea.	1		
4	Plug and patch existing 6"sewer invert (existing man hole)	L.S.	1		
5	4" schedule 40 pvc service line out of new man hole	L.F.	60		
6	Demo existing 6" VCP sewer line as shown on drawings	L.S.	1		
7	Connect existing house 334 College St. to new sewer line (Work must meet latest City plumbing code)	L.S.	1		
8	Connect existing house 517 N. Forest St. to new sewer line (Work must meet latest City plumbing code)	L.S.	1		
9	Connect existing house 511 N. Forest St.. to new sewer line (Work must meet latest City plumbing code)	L.S.	1		
10	Connect existing house 503 N. Forest St. to new sewer line (Work must meet latest City plumbing code)	L.S.	1		
11	Permanent Grassing, Straw, & Fertilizer (Disturbed Areas)	L.S.	1		
12	Mobilization	L.S.	1		
Totals					

Total Bid Written in Words

Signature of Company Representative

Print Name & Title

Date

The work consists of the approximate quantities shown herein which will be used as a basis for comparison of bids and not for final estimate. The Owner does not, by expression or by implication, agree that the actual amount of work will correspond with the estimated quantities.

In case of error in extension, the unit price shall govern rather than the amount. For lump sum items, the individual amounts shall govern the total of the bid in case of discrepancy. The owner may delete from the contract any of the line items listed in the bid form.

The amounts listed above include all labor, materials, tools, equipment, transportation, removal, overhead, profit, insurance, tax, etc. to cover the finished work in place.