

**ADDENDUM THREE  
STORM STATION 1 REPLACEMENT OF MOTOR CONTROL CENTER (MCC)  
ON-CALL DESIGN AND PLAN PRODUCTION CONTRACT NO. W-20-004-201  
CITY OF CHATTANOOGA, TENNESSEE**

The following changes shall be made to the Contract Documents, Specifications, and Drawings:

**I. Contract Documents**

**The Bid Opening date has been moved to March 24, 2020, Tuesday. Same location and time.**

**Questions:**

1. Spec. Section 26 24 19 Part 2.02 Paragraph K4, Will space heaters be required in the MCC and switchboards? The room appears not to be climate controlled.
  - A. Yes heaters are required per spec.
  
2. Will a corner section in the MCC be required?
  - A. A corner section or provisions to extend cables around corner will be required.
  
3. Spec. Section 26 24 13 Part N Item 1a, This appears to require the switchboard to be NEMA 12. To our knowledge no one makes a NEMA 12 switchboard. NEMA 1 or 3. The MCC's are to be NEMA 12. This can be done. Is NEMA 12 or 3R really needed? If NEMA 1 will work a lot of cost could be saved.
  - A. Switchboard May be Nema 1 construction. MCCs shall remain as Nema 12 construction.

March 17, 2020

---

/s/ Justin C. Holland, Administrator  
City of Chattanooga  
Department of Public Works