

CERTIFIED BID TABULATION

City of Georgetown

Project Name: Kaminski House Museum Wall and Brick Paver Repairs-Rebid

Project No.: N/A

Bid Date: April 2, 2010. Time: 2:15 PM

Item No.	Description	Quantity	Unit	Bidder #1 Southern Restoration Maintenance Inc.		Bidder #2 Green Design and Consultants		Bidder #3 Midwest Maintenance Inc.	
				Unit Price	Total	Unit Price	Total	Unit Price	Total
1	Paver Repairs. Area: 6.58' x 28.5'								
1.1	Remove and preserve existing brick pavers	1	LS	\$1,735.00	\$1,735.00	\$3,430.80	\$3,430.80	\$1,589.00	\$1,589.00
1.2	Remove and dispose existing concrete base material	1	LS	\$9,354.00	\$9,354.00	\$3,590.80	\$3,590.80	\$2,409.00	\$2,409.00
1.3	Remove and dispose of subbase material. 8-in. minimum.	1	LS	\$7,364.00	\$7,364.00	\$4,590.80	\$4,590.80	\$1,640.00	\$1,640.00
1.4	Furnish and install geotextile fabric. Compact subbase.	1	LS	\$2,788.00	\$2,788.00	\$3,090.80	\$3,090.80	\$3,080.00	\$3,080.00
1.5	Backfill 10-inches with GABC	1	LS	\$6,694.00	\$6,694.00	\$5,090.80	\$5,090.80	\$1,540.00	\$1,540.00
1.6	Re-install brick pavers including 2-inches of sand bedding	1	LS	\$9,998.00	\$9,998.00	\$5,090.80	\$5,090.80	\$3,078.00	\$3,078.00
	Subtotal				\$37,933.00		\$24,884.80		\$13,336.00
2	Masonry Wall Repair. Approximate Length of wall: 9'								
2.1	Remove and preserve wrought iron fence	1	LS	\$526.00	\$526.00	\$2,990.80	\$2,990.80	\$500.00	\$500.00
2.2	Remove and dispose existing wall material	1	LS	\$4,087.00	\$4,087.00	\$3,590.80	\$3,590.80	\$5,848.00	\$5,848.00
2.3	Install new wall brick and concrete footing	1	LS	\$6,575.00	\$6,575.00	\$6,590.80	\$6,590.80	\$8,616.00	\$8,616.00
2.4	Re-install wrought iron fence	1	LS	\$526.00	\$526.00	\$3,090.80	\$3,090.80	\$200.00	\$200.00
	Subtotal				\$11,714.00		\$16,263.20		\$15,164.00
	TOTAL BID				\$49,647.00		\$41,148.00		\$28,500.00

Addendum no. 1 Acknowledgment
RFB (initialed)
Mandatory Vendor Submittal Form

Yes	Yes	Yes
Yes	Yes	Yes
Yes	Yes	Yes

Certified By: Orlando Arteaga 4/7/2020
Orlando Arteaga, P.E. Date
City Engineer