

**ADDENDUM TWO
HIGHLAND PARK (ANDERSON AVENUE) GI DEMONSTRATION PROJECT
CONTRACT NO. S-11-001-201
CITY OF CHATTANOOGA, TENNESSEE**

The following changes shall be made to the Contract Documents, Specifications, and Drawings:

I. Q&A

Q? Per Addenda 1 on the Q & A, Please Refer to Question #2. The Filterra Planter Box is Item GI E, Please Clarify the Precast Structure Listed in Bid Item GI C.

- A. Strike the term "precast" from the language of this item. It shall employ the construction of Cast-in-Place Detached Curbing as shown on details "Streetside Planter Box" of Sheet 00C-115**

Q? Per Addenda 1 on the Q & A, Please Refer to Question #5. S. Holly Street will be Milled and Overlayed. The Storm Drain Pipe to be removed on S. Holly is in the Roadway, So once Storm Drain is removed we will have to Trench Patch the Roadway Back. What Item does the Trench Patch need to be included in (See Question 5 of Addenda 1)?

- A. Where storm drain pipe is to be replaced, the stone bedding and backfill is included in the item for pipe "complete-in-place". Where pipe is removed and not replaced, stone backfill shall be paid in item #14 "Mineral Aggregate Base". Patch will be completed using Item #26 "Bituminous Plant Mix Binder" to match the depth of the proposed milling, then the entire roadway width shall be surfaced with Item #27 "Asphalt Concrete Surface" course**

Q? Per Addenda 1 on the Q & A, Please Refer to Question #6. Once the Existing Storm Drain Pipe and Structures are removed on Anderson Ave, will you require the contractor to backfill the trench that the existing storm drain pipe and structures was removed from with stone?

- A. Generally, where pipe is located in traffic bearing areas, the backfill shall be mineral aggregate. Select backfill shall be employed in all other occurrences. This will be determined by field conditions.**

Q? Per the Addenda 1 Revised Bid Form Item 15A upon other items also reads to include Pipe removal within the construction limits, there is also a pay item #23A for Removal of Existing Storm Drain System. Can you please clarify these two Items?

A. Eliminate Item #23 “Removal of Structures/Obstructions” from the bid tab. Price of removal of piping and structures to be included in Item #15A

January 6, 2017

/s/ Justin C. Holland, Administrator
City of Chattanooga
Department of Public Works