

**Quantities for Town Hall Parking Lot Improvements**

Site Work for Parking Area-A



Date:  
10/15/2018

**CLEARING AND DEMOLITION**

Item	Description	Quantity	Unit	Unit Price	Total
1	Mobilization	1	LS		\$ -
2	Remove Existing Asphalt/ Concrete	110	SY		\$ -
3	Tree Removal	1	EA		\$ -
4	Remove Existing Gravel	570	SY		\$ -
5	Additional Surface Striping	1,150	SY		\$ -
6	Removal of Wheel Existing Stops	-	EA		\$ -
<b>CLEARING &amp; DEMOLITION, TOTAL</b>					<b>\$ -</b>

**EROSION CONTROL**

Item	Description	Quantity	Unit	Unit Price	Total
1	Construction Entrance & Concrete Washout	-	LS		\$ -
2	Tree Protection Fencing	150	LF		\$ -
3	Silt Fence	270	LF		\$ -
4	Inlet Protection	-	EA		\$ -
<b>EROSION CONTROL, TOTAL</b>					<b>\$ -</b>

**PAVING**

Item	Description	Quantity	Unit	Unit Price	Total
1	Asphalt Mill & Overlay	-	SY		\$ -
2	Leveling for Overlay Section	-	Ton		\$ -
3	Full Depth Asphalt Base & Surface Course	-	SY		\$ -
4	Saw Cut Existing Asphalt	40	LF		\$ -
5	Concrete Flush Header Curb	1,430	LF		\$ -
6	Metal Landscape Island Edging	-	LF		\$ -
7	4" Concrete Sidewalk	120	SY		\$ -
8	1" #789 Resurfacing of Existing Gravel Paving	-	SY		\$ -
9	New 6" Aggregate Paving	1,000	SY		\$ -
10	4" GW30V4 Presto GeoWeb with Gravel	280	SY		\$ -
11	Signage & Pavement Marking	1	LS		\$ -
12	Concrete Dumpster Pad	-	EA		\$ -
13	Dumpster Enclosure	-	EA		\$ -
14	Concrete Steps	-	LS		\$ -
15	Wheel Stops	33	EA		\$ -
<b>PAVING, TOTAL</b>					<b>\$ -</b>

**GRADING & DRAINAGE**

Item	Description	Quantity	Unit	Unit Price	Total
1	Fine Grading	2,000	SY		\$ -
2	Infiltration Basin	20	CY		\$ -
3	4" Infiltration Monitoring Well	1	EA		\$ -
4	Excess Material to be Hauled Offsite	50	CY		\$ -
<b>GRADING &amp; DRAINAGE, TOTAL</b>					<b>\$ -</b>

**UTILITIES**

Item	Description	Quantity	Unit	Unit Price	Total
1	2" Irrigation Tap, Valve, & Backflow	-	LS		\$ -
2	4" PVC Conduit	95	LF		\$ -
3	Adjust Existing Sewer Manhole Frame	-	EA		\$ -
<b>UTILITIES, TOTAL</b>					<b>\$ -</b>

**PARKING AREA-A, TOTAL**

**\$ -**

Assumptions

No offsite improvements are included outside of the proposed project limits of disturbance. All excavated materials are suitable for replacement, existing subgrade is suitable for use under pavements for areas of overlay, all grassings and stabilization will be performed by landscape contractor

Exclusions

Removal/Replacement of Unsuitable Materials, Temporary & Permanent Grassings Landscaping & Irrigation, Site Lighting, Decorative Signage, Site Furnishings, Decorative Hardscapes & Pathways

**Quantities for Town Hall Parking Lot Improvements**

Site Work for Parking Area-B



Date:  
10/15/2018

**CLEARING AND DEMOLITION**

Item	Description	Quantity	Unit	Unit Price	Total
1	Mobilization	1	LS		\$ -
2	Remove Existing Asphalt/ Concrete	-	SY		\$ -
3	Tree Removal	-	EA		\$ -
4	Remove Existing Gravel	150	SY		\$ -
5	Additional Surface Striping	-	SY		\$ -
6	Removal of Wheel Existing Stops	23	EA		\$ -
<b>CLEARING &amp; DEMOLITION, TOTAL</b>					<b>\$ -</b>

**EROSION CONTROL**

Item	Description	Quantity	Unit	Unit Price	Total
1	Construction Entrance & Concrete Washout	-	LS		\$ -
2	Tree Protection Fencing	340	LF		\$ -
3	Silt Fence	350	LF		\$ -
4	Inlet Protection	1	EA		\$ -
<b>EROSION CONTROL, TOTAL</b>					<b>\$ -</b>

**PAVING**

Item	Description	Quantity	Unit	Unit Price	Total
1	Asphalt Mill & Overlay	-	SY		\$ -
2	Leveling for Overlay Section	-	Ton		\$ -
3	Full Depth Asphalt Base & Surface Course	-	SY		\$ -
4	Saw Cut Existing Asphalt	-	LF		\$ -
5	Concrete Flush Header Curb	-	LF		\$ -
6	Metal Landscape Island Edging	500	LF		\$ -
7	4" Concrete Sidewalk	-	SY		\$ -
8	1" #789 Resurfacing of Existing Gravel Paving	830	SY		\$ -
9	New 6" Aggregate Paving	80	SY		\$ -
10	4" GW30V4 Presto GeoWeb with Gravel	-	SY		\$ -
11	Signage & Pavement Marking	1	LS		\$ -
12	Concrete Dumpster Pad	-	EA		\$ -
13	Dumpster Enclosure	-	EA		\$ -
14	Concrete Steps	-	LS		\$ -
15	Wheel Stops	24	EA		\$ -
<b>PAVING, TOTAL</b>					<b>\$ -</b>

**GRADING & DRAINAGE**

Item	Description	Quantity	Unit	Unit Price	Total
1	Fine Grading	250	SY		\$ -
2	Infiltration Basin	-	CY		\$ -
3	4" Infiltration Monitoring Well	-	EA		\$ -
4	Excess Material to be Hauled Offsite	-	CY		\$ -
<b>GRADING &amp; DRAINAGE, TOTAL</b>					<b>\$ -</b>

**UTILITIES**

Item	Description	Quantity	Unit	Unit Price	Total
1	2" Irrigation Tap, Valve, & Backflow	1	LS		\$ -
2	4" PVC Conduit	120	LF		\$ -
3	Adjust Existing Sewer Manhole Frame	-	EA		\$ -
<b>UTILITIES, TOTAL</b>					<b>\$ -</b>

**PARKING AREA-B, TOTAL**

**\$ -**

Assumptions

No offsite improvements are included outside of the proposed project limits of disturbance. All excavated materials are suitable for replacement, existing subgrade is suitable for use under pavements for areas of overlay, all grassings and stabilization will be performed by landscape contractor

Exclusions

Removal/Replacement of Unsuitable Materials, Temporary & Permanent Grassings Landscaping & Irrigation, Site Lighting, Decorative Signage, Site Furnishings, Decorative Hardscapes & Pathways

**Quantities for Town Hall Parking Lot Improvements**

Site Work for Parking Area-C



Date:  
10/15/2018

**CLEARING AND DEMOLITION**

Item	Description	Quantity	Unit	Unit Price	Total
1	Mobilization	1	LS		\$ -
2	Remove Existing Asphalt/ Concrete	590	SY		\$ -
3	Tree Removal	-	EA		\$ -
4	Remove Existing Gravel	310	SY		\$ -
5	Additional Surface Striping	750	SY		\$ -
6	Removal of Wheel Existing Stops	27	EA		\$ -
<b>CLEARING &amp; DEMOLITION, TOTAL</b>					<b>\$ -</b>

**EROSION CONTROL**

Item	Description	Quantity	Unit	Unit Price	Total
1	Construction Entrance & Concrete Washout	1	LS		\$ -
2	Tree Protection Fencing	510	LF		\$ -
3	Silt Fence	150	LF		\$ -
4	Inlet Protection	1	EA		\$ -
<b>EROSION CONTROL, TOTAL</b>					<b>\$ -</b>

**PAVING**

Item	Description	Quantity	Unit	Unit Price	Total
1	Asphalt Mill & Overlay	350	SY		\$ -
2	Leveling for Overlay Section	40	Ton		\$ -
3	Full Depth Asphalt Base & Surface Course	165	SY		\$ -
4	Saw Cut Existing Asphalt	150	LF		\$ -
5	Concrete Flush Header Curb	1,000	LF		\$ -
6	Metal Landscape Island Edging	-	LF		\$ -
7	4" Concrete Sidewalk	200	SY		\$ -
8	1" #789 Resurfacing of Existing Gravel Paving	-	SY		\$ -
9	New 6" Aggregate Paving	590	SY		\$ -
10	4" GW30V4 Presto GeoWeb with Gravel	-	SY		\$ -
11	Signage & Pavement Marking	1	LS		\$ -
12	Concrete Dumpster Pad	1	EA		\$ -
13	Dumpster Enclosure	1	EA		\$ -
14	Concrete Steps	1	LS		\$ -
15	Wheel Stops	38	EA		\$ -
<b>PAVING, TOTAL</b>					<b>\$ -</b>

**GRADING & DRAINAGE**

Item	Description	Quantity	Unit	Unit Price	Total
1	Fine Grading	2,000	SY		\$ -
2	Infiltration Basin	-	CY		\$ -
3	4" Infiltration Monitoring Well	-	EA		\$ -
4	Excess Material to be Hauled Offsite	200	CY		\$ -
<b>GRADING &amp; DRAINAGE, TOTAL</b>					<b>\$ -</b>

**UTILITIES**

Item	Description	Quantity	Unit	Unit Price	Total
1	2" Irrigation Tap, Valve, & Backflow	-	LS		\$ -
2	4" PVC Conduit	-	LF		\$ -
3	Adjust Existing Sewer Manhole Frame	1	EA		\$ -
<b>UTILITIES, TOTAL</b>					<b>\$ -</b>

**PARKING AREA-C, TOTAL**

**\$ -**

**Assumptions**

No offsite improvements are included outside of the proposed project limits of disturbance. All excavated materials are suitable for replacement, existing subgrade is suitable for use under pavements for areas of overlay, all grassings and stabilization will be performed by landscape contractor

**Exclusions**

Removal/Replacement of Unsuitable Materials, Temporary & Permanent Grassings Landscaping & Irrigation, Site Lighting, Decorative Signage, Site Furnishings, Decorative Hardscapes & Pathways

**Quantities for Town Hall Parking Lot Improvements**

Total Site Work



Date:  
10/15/2018

**CLEARING AND DEMOLITION**

Item	Description	Quantity	Unit	Unit Price	Total
1	Mobilization	1	LS		\$ -
2	Remove Existing Asphalt/ Concrete	700	SY		\$ -
3	Tree Removal	1	EA		\$ -
4	Remove Existing Gravel	1,030	SY		\$ -
5	Additional Surface Striping	1,900	SY		\$ -
6	Removal of Wheel Existing Stops	50	EA		\$ -
<b>CLEARING &amp; DEMOLITION, TOTAL</b>					<b>\$ -</b>

**EROSION CONTROL**

Item	Description	Quantity	Unit	Unit Price	Total
1	Construction Entrance & Concrete Washout	1	LS		\$ -
2	Tree Protection Fencing	1,000	LF		\$ -
3	Silt Fence	770	LF		\$ -
4	Inlet Protection	2	EA		\$ -
<b>EROSION CONTROL, TOTAL</b>					<b>\$ -</b>

**PAVING**

Item	Description	Quantity	Unit	Unit Price	Total
1	Asphalt Mill & Overlay	350	SY		\$ -
2	Leveling for Overlay Section	40	Ton		\$ -
3	Full Depth Asphalt Base & Surface Course	165	SY		\$ -
4	Saw Cut Existing Asphalt	190	LF		\$ -
5	Concrete Flush Header Curb	2,430	LF		\$ -
6	Metal Landscape Island Edging	500	LF		\$ -
7	4" Concrete Sidewalk	320	SY		\$ -
8	1" #789 Resurfacing of Existing Gravel Paving	830	SY		\$ -
9	New 6" Aggregate Paving	1,670	SY		\$ -
10	4" GW30V4 Presto GeoWeb with Gravel	280	SY		\$ -
11	Signage & Pavement Marking	3	LS		\$ -
12	Concrete Dumpster Pad	1	EA		\$ -
13	Dumpster Enclosure	1	EA		\$ -
14	Concrete Steps	1	LS		\$ -
15	Wheel Stops	95	EA		\$ -
<b>PAVING, TOTAL</b>					<b>\$ -</b>

**GRADING & DRAINAGE**

Item	Description	Quantity	Unit	Unit Price	Total
1	Fine Grading	4,250	SY		\$ -
2	Infiltration Basin	20	CY		\$ -
3	4" Infiltration Monitoring Well	1	EA		\$ -
4	Excess Material to be Hauled Offsite	250	CY		\$ -
<b>GRADING &amp; DRAINAGE, TOTAL</b>					<b>\$ -</b>

**UTILITIES**

Item	Description	Quantity	Unit	Unit Price	Total
1	2" Irrigation Tap, Valve, & Backflow	1	LS		\$ -
2	4" PVC Conduit	215	LF		\$ -
3	Relocation of Existing Sewer Manhole Frame	1	EA		\$ -
<b>UTILITIES, TOTAL</b>					<b>\$ -</b>

**PARKING AREAS A, B & C, TOTAL**

\$ -

Assumptions

No offsite improvements are included outside of the proposed project limits of disturbance. All excavated materials are suitable for replacement, existing subgrade is suitable for use under pavements for areas of overlay, all grassings and stabilization will be performed by landscape contractor

Exclusions

Removal/Replacement of Unsuitable Materials, Temporary & Permanent Grassings Landscaping & Irrigation, Site Lighting, Decorative Signage, Site Furnishings, Decorative Hardscapes & Pathways