



Jackson County Board of Commissioners

67 Athens Street
Jefferson, Georgia 30549
Phone: (706) 367-6309
Fax: (706) 708-2505
Email: myarbrough@jacksoncountygov.com

Date: March 21, 2022

To: Road Contractors

From: Myrna Yarbrough, Purchasing Manager

RE: Addendum 2 to Jackson County ITB 220002, Construction of New Skelton Rd., Jackson County GA.

1. Please see answer to question about GDOT Asphalt Cement Index. Since the duration of this project is anticipated to be no more than 365 days, this project will not utilize the GDOT Asphalt Cement Index. Additional questions are answered below. All other information remains the same.
2. All other terms and conditions in ITB 220002 remain unchanged.
3. Any inquiries concerning Addendum 2 should be made to Myrna Yarbrough, Purchasing Manager, (706) 367-6309 or via email at myarbrough@jacksoncountygov.com
4. Jackson County reserves the right to reject any and all proposals, to waive any technicalities or irregularities and to award the offer based upon the most responsive, responsible submission.
5. Bidders must acknowledge receipt of addenda, by either signing and attaching this copy, or by writing "Acknowledge Addenda #2" at bottom of the proposal.
6. Will Jackson Co or GDOT oversee the project? Jackson County
7. With the current concrete pipe supply shortage they are estimating 12 weeks to get pipe. Would the county consider an alternate? The county will consider it after the contract is awarded.
8. The pay items for Long Line striping is listed as paint in the pay items but is shown as thermoplastic on page 06-002 in the plans. Which is correct? Thermoplastic for all striping.
9. The Pay items for long line striping is listed as 6" in the pay items, however; the striping plans show it as 5". Which is correct? 6" striping will be required.
10. All the arrows and words are listed as Paint in the pay items except for the Hatching, which is thermoplastic. Is this correct? Yes
11. The plans show 8" striping for crosswalks but there is no pay item. How will this be paid? It is item #653-8070. Bid document has been revised to include this item and is attached.
12. Two soils reports have been completed for the Jackson County Board of Education on property adjacent to the project and have been made available. A PDF of both of these reports are posted with this addendum.

BID DOCUMENT

Base bid = \$ _____

Completion time – _____

ITEM NO.	UNITS	DESCRIPTION	QUANTITY	PRICE	TOTAL PRICE
150-1000	LS	TRAFFIC CONTROL -	1		
163-0232	AC	TEMPORARY GRASSING	9,41		
163-0240	TN	MULCH	140		
163-0301	EA	CONSTRUCT AND REMOVE CONSTRUCTION EXITS	5		
163-0310	EA	CONSTRUCTION EXIT TIRE CLEANING STATION (PER DAY)	4		
163-0527	EA	CONSTRUCT AND REMOVE RIP RAP CHECK DAMS, STONE PLAIN RIP RAP/SAND BAGS	118		
163-0550	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP	15		
165-0010	LF	MAINTENANCE OF TEMPORARY SILT FENCE, TP A	1900		
165-0030	LF	MAINTENANCE OF TEMPORARY SILT FENCE, TP C	350		
165-0041	LF	MAINTENANCE OF CHECK DAMS - ALL TYPES	38		
165-0101	EA	MAINTENANCE OF CONSTRUCTION EXIT	26		
165-0105	EA	MAINTENANCE OF INLET SEDIMENT TRAP	15		
165-0310	EA	MAINTENANCE OF CONSTRUCTION EXIT TIRE WASH AREA (PER EACH)	3		
167-1000	EA	WATER QUALITY MONITORING AND SAMPLING	1		
167-1500	MO	WATER QUALITY INSPECTIONS	9		
171-0010	LF	TEMPORARY SILT FENCE, TYPE A	8827		
171-0030	LF	TEMPORARY SILT FENCE, TYPE C	1312		
201-1500	LS	CLEARING & GRUBBING -	1		
210-0100	LS	GRADING COMPLETE -	1		
310-1101	TN	GR AGGR BASE CRS, INCL MATL	7174		
318-3000	TN	AGGR SURF CRS	240		
402-1812	TN	RECYCLED ASPH CONC LEVELING, INCL BITUM MATL & H LIME	120		
402-3103	TN	RECYCLED ASPH CONC 9.5 MM SUPERPAVE, TYPE II, GP 2 ONLY, INCL BITUM MATL & H LIME	1851		
402-3111	TN	RECYCLED ASPH CONC 19 MM MIX, GP 1 OR 2, INCL BITUM MATL & H LIME	1555		
402-3121	TN	RECYCLED ASPH CONC 25 MM SUPERPAVE, GP 1 OR 2, INCL BITUM MATL & H LIME	3361		
413-0750	GL	TACK COAT	1131		

432-5010	SY	MILL ASPH CONC PVMT, VARIABLE DEPTH	10383		
441-0016	SY	DRIVEWAY CONCRETE, 6 IN TK	40		
441-0104	SY	CONC SIDEWALK, 4 IN	1273		
441-6222	LF	CONC CURB & GUTTER, 8 IN X 30 IN, TP 2	5175		
441-7011	EA	CURB CUT WHEELCHAIR RAMP, TYPE A	6		
446-1100	LF	PVMT REINF FABRIC STRIPS, TP 2, 18 INCH WIDTH	4595		
550-1180	LF	STORM DRAIN PIPE, 18 IN, H 1-10	804		
550-1181	LF	STORM DRAIN PIPE, 18 IN, H 10-15	718		
550-1240	LF	STORM DRAIN PIPE, 24 IN, H 1-10	390		
550-1364	LF	STORM DRAIN PIPE, 36 IN, H 25-30	157		
550-2180	LF	SIDE DRAIN PIPE, 18 IN, H 1-10	467		
550-3518	EA	SAFETY END SECTION 18 IN, STORM DRAIN, 6:1 SLOPE	7		
550-3524	EA	SAFETY END SECTION 24 IN, STORM DRAIN, 6:1 SLOPE	1		
550-3530	EA	SAFETY END SECTION 30 IN, STORM DRAIN, 6:1 SLOPE	3		
550-3618	EA	SAFETY END SECTION 18 IN, SIDE DRAIN, 6:1 SLOPE	16		
603-2181	SY	STN DUMPED RIP RAP, TP 3, 18 IN	23		
603-7000	SY	PLASTIC FILTER FABRIC	23		
634-1200	EA	RIGHT OF WAY MARKERS	20		
636-1041	SF	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 9	117.5		
636-1045	SF	HIGHWAY SIGNS, TP 2 MATL, REFL SHEETING, TP 11	40		
636-2070	LF	GALV STEEL POSTS, TP 7	225		
641-1200	LF	GUARDRAIL, TP W	603		
641-5012	EA	GUARDRAIL ANCHORAGE, TP 12	4		
652-0120	EA	PAVEMENT MARKING, ARROW, TP 2	29		
652-0210	EA	PAVEMENT MARKING, WORD, TP 1	3		
652-5301	LF	SOLID TRAF STRIPE, 6 IN, WHITE	14660		
652-5302	LF	SOLID TRAF STRIPE, 6 IN, YELLOW	4678		
652-5701	LF	SOLID TRAF STRIPE, 24 IN, WHITE	106		
652-6301	GLF	SKIP TRAF STRIPE, 6 IN, WHITE	950		
653-6004	SY	THERMOPLASTIC TRAF STRIPING, WHITE	396		
653-6006	SY	THERMOPLASTIC TRAF STRIPING, YELLOW	2221		
653-8070	LF	THERMOPLASTIC SOLID TRAFFIC STRIPE, 8 IN, WHITE	864		
654-1001	EA	RAISED PVMT MARKERS TP 1	148		
654-1003	EA	RAISED PVMT MARKERS TP 3	131		
660-2010	EA	CHECK VALVE -	2		
668-1100	EA	CATCH BASIN, GP 1	15		

668-1110	LF	CATCH BASIN, GP 1, ADDL DEPTH	30.61		
670-0800	EA	WATER METER -	2		
670-4000	EA	FIRE HYDRANT	2		
670-4490	EA	CONCRETE THRUST COLLAR -	2		
670-5000	LF	WATER SERVICE LINE -	45		
670-5801	EA	WATER METER -	2		
670-9730	EA	RELOCATE EXIST WATER METER, INCL BOX	2		
700-6910	AC	PERMANENT GRASSING	9.68		
700-7000	TN	AGRICULTURAL LIME	0.32		
700-8000	TN	FERTILIZER MIXED GRADE	1.72		
700-8100	LB	FERTILIZER NITROGEN CONTENT	79.32		
701-0020	LB	FERTILIZER MIXED GRADE	412		
701-0030	TN	AGRICULTURAL LIME	120		
702-9000	TN	FERTILIZER, SPRING APPLICATION	0.03		
702-9005	LB	SPRING APPLICATION FERTILIZER	207		
710-9000	SY	PERMANENT SOIL REINFORCING MAT	100		
713-3001	SY	WOOD FIBER BLANKET, TP I, SLOPES	9474		
713-3002	SY	WOOD FIBER BLANKET, TP II, SLOPES	200		

TOTAL:

Signed: _____

Title: _____

Company Name: _____

Address: _____

City, State, Zip: _____

Phone number: _____

Email: _____

Contractor must acknowledge receipt of any addenda on either this form or by signing and returning a copy of the addenda with their bid package.