

ADDENDUM NO. 1

DATE: October 22, 2019
TO: All Potential Bidders
FROM: Karisa Scott, Procurement Specialist, City of Knoxville
SUBJECT: Addendum No. 1 – Structure Removal on Second Creek

BIDS TO BE OPENED: October 24, 2019, at 11:00:00 a.m. (Eastern Time)

This addendum is being published to provide information for bidders regarding bid submission deadline as well as questions asked at the Pre-Solicitation meeting. This addendum becomes a part of the Contract Documents and modifies the original specifications as noted.

The Bid Submission deadline is extended to Thursday, October 24, 2019 at 11:00:00 EST.

Question 1: How should drainage from the existing detention pond be handled?

Response: The most effective method to controlling the discharge from the existing detention basin will be to temporary plug the basin and provide and include measures to pump the basin, if needed. The existing detention basin already has an easement which may allow this work. If not, then there would need to be a small coffer dam at the basin's discharge and pump from there. Please review the attached excerpts for this information.

Question 2: Is this creek stream fed?

Response: Yes, the creek is stream fed. The fact that we have been extremely dry may reduce or eliminate the flow temporarily but plan on constant flow to be safe.

Question 3: Is RLS staking required?

Response: The specifications do not require an RLS but do state "*The CONTRACTOR shall provide and have available to the project, an adequate engineering or surveying staff which is competent and qualified to set all lines and grades needed to construct the stream restoration.*"

Question 4: Will a final survey be required?

Response: The contract documents do not require an as built or final survey.

Attached with this addendum are the excerpts referenced regarding drainage for the existing detention pond.