

SEQUENCE OF CONSTRUCTION

1. CONTRACTOR TO OBTAIN ALL NECESSARY APPROVALS AND PERMITS.
2. CONTRACTOR TO INSTALL CONSTRUCTION ENTRANCE AT LOCATION SHOWN ON PLANS.
3. CONTRACTOR TO CLEAR AREA TO BE DISTURBED AND REMOVE FROM SITE.
4. CONTRACTOR TO INSTALL SILT FENCE AT LOCATIONS SHOWN ON THE PLANS AND IN AREAS WITH SILT LADEN RUNOFF.
5. CONTRACTOR TO INSTALL BYPASS PUMPING OF FLOW AROUND AREAS TO BE DISTURBED WITH DEMOLITION AND STREAM GRADING.
6. CONTRACTOR TO PROVIDE A MEANS TO DIVERT FLOW FROM EXISTING STORMWATER DETENTION BASIN DURING CONSTRUCTION BY EITHER PLUGGING THE BASIN'S OUTLET OR INSTALLATION OF A COFFERDAM AT THE BASIN'S DISCHARGE. CONTRACTOR MAY PRESENT OTHER MEANS FOR REVIEW AND APPROVAL.
7. CONTRACTOR TO REMOVE EXISTING ITEMS SHOWN ON DEMOLITION PLAN.
8. CONTRACTOR TO STRIP TOPSOIL AND STOCKPILE IN LOCATION THAT WILL NOT INHIBIT CONSTRUCTION OF STREAM GRADING.
9. CONTRACTOR TO PERFORM STREAM GRADING WHILE MAINTAINING ESC MEASURES.
10. CONTRACTOR SHALL INSTALL TOPSOIL AND STABILIZE ALL DISTURBED AREAS WITH PERMANENT SEEDING.
11. CONTRACTOR SHALL REMOVE ALL TEMPORARY ESC DEVICES UPON ADEQUATE COVER IS ESTABLISHED WITH VEGETATION.