



ADDENDUM #1

1. REMOVE ALL EXISTING ROOFING TO BASE PLYWOOD
2. (1) LAYER FLINTASTIC SA PLYBASE (60) MILS
3. (1) LAYER FLINTASTIC SA CAP SHEET (160) MILS

LEGEND

---	HIDDEN STRUCTURE
● DS	4X4 NEW ALUM DOWNSPOUT TO CONCRETE SPLASHBLOCK

GENERAL NOTES:

1. VERIFY MEASUREMENTS WITH CORRESPONDING CONSTRUCTED OR EXISTING CONDITIONS PRIOR TO PROCEEDING WITH THE WORK, AND NOTIFY THE ARCHITECT IMMEDIATELY OF SIGNIFICANT DISCREPANCIES USING THE "CONSTRUCTION REQUEST FOR INFORMATION" FORM AND SUPPLEMENTARY CONTRACTOR-PRODUCED DETAILS AS REQUIRED.
2. ALL ROOF PENETRATIONS FOR MINOR ROOF VENTS AND SIMILAR ITEMS MAY NOT BE INDICATED ON THIS ROOF PLAN; HOWEVER, ALL ROOF FLASHING WORK SHALL BE PROVIDED BY THE ROOFING CONTRACTOR SO AS TO OBTAIN ROOFING WARRANTIES.
3. DO NOT RELY ON THESE DIMENSIONS FOR ACCURACY. ALL BIDDER TO OBTAIN AS-BUILT MEASUREMENTS.

SCOPE OF WORK: (DEMO)

1. REMOVE ALL EXISTING SHINGLE ROOFING AND BASE PLY DOWN TO PLYWOOD
2. REMOVE ALL FLASHING / DRIP EDGE / RIDGE VENT / GUTTERS + DOWNSPOUT
3. REMOVE FROM SITE AND DISPOSE OF ALL EXISTING ROOFING MATERIALS.

ROOF DECK REATTACHMENT:

1. INSTALL RSRs-01 (2 3/8" X 0.113") RING SHANK NAILS AT 4" EDGE / 6" FIELD OF EXISTING PLYWOOD DECK

ROOF PLAN
1/8" = 1'-0"

REROOF FOR:
 OKEECHOBEE COUNTY FIRE STATION #1
 501 NW 6TH ST, OKEECHOBEE COUNTY,
 FLORIDA, 34972

CASTELLANOS + TRAMONTE ARCHITECTS
 1625 SE 46TH STREET SUITE 2A CAPE CORAL, FLORIDA 33904
 (239) 549-0997 AA 26003303

DRAWN BY	NGM
CHECKED BY	AAC
ISSUED FOR:	PERMIT
OWNER COMMENTS	3-2-18 3/23/18

DRAWING NAME:
ROOF PLAN

SHEET
A-1
OF 5 SHEETS

PLANS HAVE BEEN PREPARED IN COMPLIANCE WITH THE FLORIDA BUILDING CODE, 6TH EDITION (2017) SECTION 1609 FOR 150 MPH WIND SPEED AND THE FLORIDA FIRE PREVENTION CODE 6TH EDITION.
ART A. CASTELLANOS LIC. NO. AR0015473