

BID FORM
THORNWOOD DRIVE CULVERT REPLACEMENT
SPARTANBURG, SOUTH CAROLINA

Item No.	Description	Quantity	Est. Units	Unit Cost	Total Cost
	Lump Sum Items				
1	Mobilization, Bonds, Insurance, Etc.	1	LS		
2	Construction Staking	1	LS		
3	Materials Testing	1	LS		
4	Traffic Control	1	LS		
5	Tree Clearing	1	LS		
6	Bypass Pumping Operations	1	LS		
7	Misc. Utility Relocation	1	LS		
8	Storm Drainage Demolition (Pipe, Structures, Etc.)	1	LS		
9	Asphalt Pavement Removal (Full Depth)	80	SY		
10	24" RCP Class III (incl. Trench Bed Compaction)	50	LF		
11	Precast Concrete Headwall	1	EA		
12	Class B Rip Rap (w/ Filter Fabric)	14	SY		
13	Curb Inlet (SCDOT Type 16)	2	EA		
14	Yard Inlet (SCDOT Type 9)	1	EA		
15	Misc. Earthwork / Grading	1	LS		
16	Erosion Control Matting	250	SY		
17	Silt Fence (Install, Maintain, and Removal)	118	LF		
18	Sediment Tube Inlet Protection	3	EA		
19	Misc Erosion Control, Maintenance & Site Clean-up	1	LS		
20	Concrete Curb and Gutter	132	LF		
21	6" Aggregate Base Course	80	SY		
22	2" Asphalt Surface Course (SCDOT Type C)	80	SY		
23	W-Beam Steel Guardrail	92	LF		
24	W-Beam Guardrail End Treatment	2	EA		

TOTAL

Unit Price Items					
	Improved Trench Bedding - Allowance (Washed Stone)	20	TON		
	Unsuitable Soil Removal and Replacement - Allowance	25	CY		