

**BID FORM**  
**THORNWOOD DRIVE CULVERT REPLACEMENT**  
**SPARTANBURG, SOUTH CAROLINA**

Item No.	Description	Quantity	Est. Units	Unit Cost	Total Cost
	<b>Lump Sum Items</b>				
1	Mobilization, Bonds, Insurance, Etc.	1	LS		
2	Construction Staking	1	LS		
3	Materials Testing	1	LS		
4	Traffic Control	1	LS		
5	Tree Clearing	1	LS		
6	Bypass Pumping Operations	1	LS		
7	Storm Drainage Demolition (Pipe, Structures, Etc.)	1	LS		
8	Asphalt Pavement Removal (Full Depth)	80	SY		
9	24" RCP Class III (incl. Trench Bed Compaction)	50	LF		
10	Precast Concrete Headwall	1	EA		
11	Class B Rip Rap (w/ Filter Fabric)	14	SY		
12	Curb Inlet (SCDOT Type 16)	2	EA		
13	Yard Inlet (SCDOT Type 9)	1	EA		
14	Misc. Earthwork / Grading	1	LS		
15	Erosion Control Matting	250	SY		
16	Silt Fence (Install, Maintain, and Removal)	118	LF		
17	Sediment Tube Inlet Protection	3	EA		
18	Misc Erosion Control, Maintenance & Site Clean-up	1	LS		
19	Concrete Curb and Gutter	132	LF		
20	6" Aggregate Base Course	80	SY		
21	2" Asphalt Surface Course (SCDOT Type C)	80	SY		

<b>TOTAL</b>
--------------

<b>Unit Price Items</b>					
	Improved Trench Bedding - Allowance (Washed Stone)	20	TON		
	Unsuitable Soil Removal and Replacement - Allowance	25	CY		