

**ARLINGTON COUNTY, VIRGINIA
OFFICE OF THE PURCHASING AGENT**

INVITATION TO BID NO. 21-CPHD-ITB-271

ADDENDUM NO. 1

Arlington County Invitation to Bid No. **21-CPHD-ITB-271** for **NC Program Project N Highland St From 1st Rd to Arlington Blvd** is amended as follows.

- I. Changes to the ITB attachments: The following section of the ITB has been revised and replaced as follows:
 - a. ATTACHMENT A: PRICING SHEET has been revised to update Table C6 – Watermain Work. Master Item #02550-C6-00010 Unit Price has been changed to reflect EA and not LF. Attached as Annex A is a revised Pricing Sheet. Bidders are required to use this Pricing Sheet in their bid packages, or their bid may be found non-responsive

The balance of the solicitation remains unchanged.

Arlington County, Virginia

Sy Gezachew
Procurement Officer
sgezachew@arlingtonva.us

RETURN THIS PAGE, FULLY COMPLETED AND SIGNED, WITH YOUR BID:

BIDDER ACKNOWLEDGES RECEIPT OF ADDENDUM NUMBER 1.

FIRM NAME: _____

AUTHORIZED SIGNATURE: _____ **DATE:** _____

ARLINGTON COUNTY, VIRGINIA
OFFICE OF THE PURCHASING AGENT
INVITATION TO BID NO. 21-CPHD-ITB-271
PROJECT NO.: Z261

ANNEX - A

THE UNDERSIGNED CERTIFIES THAT (CONTRACTOR NAME) _____ WAS
IS CURRENTLY REGISTERED WITH THE VIRGINIA STATE BOARD OF CONTRACTORS AS REQUIRED BY THE CODE OF VIRGINIA. CERTIFICATE NUMBER _____ WAS
ISSUED ON THE _____ DAY OF _____, 20XX. THE UNDERSIGNED FURTHER CERTIFIES THAT THE REGISTRATION FEE AND ALL RENEWAL FEES REQUIRED UNDER LAW
HAVE BEEN PAID. THE CONTRACTOR AGREES TO FURNISH ALL NECESSARY LABOR, EQUIPMENT, MATERIALS, AND ALL THINGS NECESSARY TO PERFORM THE WORK AS SET FORTH
IN ACCORDANCE WITH THE PLANS AND SPECIFICATIONS. THE CONTRACTOR AGREES TO PERFORM RELATED WORK FOR THE FOLLOWING ITEMS AT THE FOLLOWING STIPULATED
PRICES: (ALL PRICES INCLUDE PROVISION AND INSTALLATION).

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
C1 GENERAL EARTH WORK					
MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
02200-C1-00050	Select Borrow (VDOT Section 207 - Select Material, Type I)	70	CY		\$0.00
02200-C1-00130	Aggregate, VDOT #21-A (Compacted in Place per VDOT standards & Specs)	480	CY		\$0.00
				SUBTOTAL	\$0.00

C2 CONCRETE WORK

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
02750-C2-00020	Concrete Curb, Standard Header Curb C-3 (Arlington County Detail R-2.0), includes curb for aprons, ramps, etc.	125	LF		\$0.00
02750-C2-00060	Concrete Curb & Gutter, Standard C-2 and C-2R (Arlington County Detail R-2.0), includes curb & gutter for aprons, ramps, etc.	1400	LF		\$0.00
02611-C2-00110	Concrete Sidewalk, 4" Thickness (Arlington County Detail R-2.0)	371	SY		\$0.00
02611-C2-00190	CG-12 Detectable Warning Surface - Truncated Domes	12	SY		\$0.00
02611-C2-00170	Concrete Driveway Entrance, 6" Thick Residential (Arlington County Details R-2.4A, R-2.4B, R-2.4C, R-2.4D)	165	SY		\$0.00
03100-C2-00200	Concrete Steps Each (Arlington County Detail R-3.0, including all reinforcing bars as shown in detail)	6	LF-W		\$0.00
				SUBTOTAL	\$0.00

C3 ASPHALT WORK

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
02600-C3-00030	Asphalt Concrete, Base Course (VDOT BM-25.0A)	630	TON		\$0.00
02600-C3-00060	Asphalt Concrete, Surface Course (VDOT SM-9.5A) For Asphalt Driveway only.	11	TON		\$0.00
				SUBTOTAL	\$0.00

C6 WATERMAIN WORK

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
02550-C6-00670	Water Meter Relocations - - 3/4-inch and 1-inch (INSTALL COPPER TUBING, CONNECT TO EXISTING COUNTY AND PRIVATE SERVICE LINES, PROVIDE NEW ANGLE VALVES, RELOCATE METER HOUSING AND METER YOKE, BACKFILL AND EXCAVATION)--UP TO 10 FT.	7	EA		\$0.00
02550-SP-00010	Adjust Water Manhole to New Grade	1	EA		\$0.00
02550-SP-00020	Spiked Water Meter Cover for Water Meters Cast in Concrete, Per Detail on Sheet C051.1	9	EA		\$0.00
				SUBTOTAL	\$0.00

C10 PAVEMENT MARKING AND SIGNAGE WORK

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNIT PRICE	TOTAL
---------------	-------------	-----	------	------------	-------

02900-C10-00050	Twenty Four (24) Inch Transverse Markings, Note: Used For Continental (Ladder) Crosswalk	64	LF		\$0.00
02900-C10-00410	Traffic Control Sign (Typical Stop, Yield, No Parking, Speed Limit, or Similar), Install per Detail SG-1.0	5	EA		\$0.00
02900-C10-00430	Traffic Control Sign (Typical Stop, Yield, No Parking, Speed Limit, or Similar), Relocate with New Post	4	EA		\$0.00
				SUBTOTAL	\$0.00

C11 LANDSCAPE AND HARDSCAPE RESTORATION WORK

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNITPRICE	TOTAL
02200-C11-00010	Imported Topsoil	105	CY		\$0.00
02800-C11-00030	Topsoil for Street Trees, Purchased Mixture (per Arlington County DPR Specification and Special Condition 21 Tree Pits)	25	CY		\$0.00
02801-C11-00060	Sod, Tall Fescue/Bluegrass Mixture	950	SY		\$0.00
02800-C11-00500	Tree/Stump Removal - Class A. Remove and Dispose, Up to 6" DBH to 12" DBH (Diameter at Breast Height)	11	EA		\$0.00
02800-C11-00110	Brick Pavers, Remove and Reset (Arlington County Detail R-2.1)	18	SY		\$0.00
02800-C11-00120	Flagstone Walkway, Remove & Reset or Replace to Match Existing	24	SY		\$0.00
02800-SP-00030	Wooden or Vinyl Fence (Typical Privacy, Picket, or Similar), Reset or Replace to Match Existing	300	LF		\$0.00
02800-SP-00040	Metal Fence, Remove and Reset, at 101 N Highland St.	30	LF		\$0.00
				SUBTOTAL	\$0.00

C13 EROSION AND SEDIMENT CONTROL WORK

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNITPRICE	TOTAL
01500-C13-10000	Temporary Erosion and Sediment Controls	1	LS		\$0.00
				SUBTOTAL	\$0.00

CONTRACT TOTAL (EXCLUDING PERCENTAGE ITEMS) \$0.00

PCT PERCENTAGE LINE ITEMS

MASTER ITEM #	DESCRIPTION	QTY	UNIT	UNITPRICE	TOTAL
01000-C16-00010	Maintenance of Traffic (MOT)	NA	%		\$0.00
01000-C16-00030	Mobilization and De-Mobilization	NA	%		\$0.00
01500-SA-00200	SWPPP Administration	NA	%		\$0.00
				PERCENTAGE LINE ITEMS SUBTOTAL	\$0.00

PRIMARY CONTRACT : \$0.00