

2019-27
184 Bluffton Road Site Improvements
BID FORM – UPDATED 1/30/19

GENERAL PROVISIONS					
Item	Description	Quantity	Units	Unit Price	Total
1	Mobilization	1	LS	\$ -	\$ -
2	Bonds and Insurance	1	LS	\$ -	\$ -
3	Project Management and Coordination	1	LS	\$ -	\$ -
Sub-Total, GENERAL PROVISIONS					\$ -

DEMOLITION					
Item	Description	Quantity	Units	Unit Price	Total
1	Rem. & Disp. Full Depth Asphalt	505	SY	\$ -	\$ -
2	Rem. & Disp. Gravel Paving	630	SY	\$ -	\$ -
3	Rem. & Disp. Septic Tank	1	LS	\$ -	\$ -
4	Rem. & Disp. Trees	9	EA	\$ -	\$ -
5	Abandon Well per DHEC Requirements	1	LS	\$ -	\$ -
Sub-Total, DEMOLITION					\$ -

EARTHWORK, PAVING & CONSTRUCTION					
Item	Description	Quantity	Units	Unit Price	Total
1	Earthwork	1	LS	\$ -	\$ -
2	Grading	1	LS	\$ -	\$ -
3	Gravel Paving	663	SY	\$ -	\$ -
4	Asphalt Paving	865	SY	\$ -	\$ -
5	1.5" Asphaltic Concrete Type C Wearing Surface	865	SY	\$ -	\$ -
6	6" Base Course	865	SY	\$ -	\$ -
7	Pervious Paver Parking	44	SY	\$ -	\$ -
8	Concrete Sidewalk (Tabby Finish)	88	SY	\$ -	\$ -
9	12" Concrete Flush Header Curb	1,200	LF	\$ -	\$ -
10	Concrete Wheel Stop	41	EA	\$ -	\$ -
11	Accessible Parking Signs	2	EA	\$ -	\$ -
12	4" Conduit for irrigation	434	LF	\$ -	\$ -
13	Striping	1	LS	\$ -	\$ -
Sub-Total, EARTHWORK, PAVING & CONSTRUCTION					\$ -

DRAINAGE					
Item	Description	Quantity	Units	Unit Price	Total
1	15" RCP	233	LF	\$ -	\$ -
2	Grate Inlet	2	EA	\$ -	\$ -
3	Storm Manhole	2	EA	\$ -	\$ -
4	Connect to Existing 18" R.C.P.	1	EA	\$ -	\$ -
Sub-Total, DRAINAGE					\$ -
WATER					
Item	Description	Quantity	Units	Unit Price	Total
1	2" Water Service	15	LF	\$ -	\$ -
2	2" Water Valve	1	EA	\$ -	\$ -
3	Backflow in vault	1	EA	\$ -	\$ -
Sub-Total, WATER					\$ -
EROSION CONTROL					
Item	Description	Quantity	Units	Unit Price	Total
1	Erosion Control	1	LS	\$ -	\$ -
2	Silt Fence	680	LF	\$ -	\$ -
3	Tree Protection (allowance)	200	LF	\$ -	\$ -
4	Temporary Grassing	1	LS	\$ -	\$ -
Sub-Total, EROSION CONTROL					\$ -
Total, SITE DEVELOPMENT					\$ -
ADD ALTERNATES					
Item	Description	Quantity	Units	Unit Price	Total
1	Change Gravel Parking to Pervious Paver Parking	663	SY	\$ -	\$ -
Sub-Total, ADD ALTERNATES					\$ -