



**City of Myrtle Beach**  
**SOUTH CAROLINA**

PURCHASING AND  
MATERIALS MANAGEMENT

(843) 918-2170  
FAX: (843) 918-2182

**ADDENDUM 001**

**March 2, 2020**

**20-B0036**

**5<sup>th</sup> Avenue South Force Main Replacement**

A Pre-Bid Conference was held. The following were in attendance:


|               |                        |
|---------------|------------------------|
| Jessie Hurst  | Lawrimore Construction |
| Joey Stinnett | Greenwall Construction |
| Edward Benton | CL Benton              |
| Brian Stewart | RH Moore               |
| Dustin Wagner |                        |

The following questions have arisen from that meeting:

1. For clarification, the asphalt patches have to set for a year before an asphalt overlay on Boundary Street and 5<sup>th</sup> Avenue South?  
A. This information was a misprint. There is no time frame. Final paving can occur after the project is complete.
2. Are certified payroll and/or wage rates required?  
A. No

Please find attachment from DDC for Joint Restraint

Thank you,

  
Ruth Bursleson Garigen/Buyer  
City of Myrtle Beach Purchasing

## Typical Fitting and Joint Restraint

| Pipe size               | 16"                            | 20"                            | 24"                            |
|-------------------------|--------------------------------|--------------------------------|--------------------------------|
| <b>Fitting</b>          |                                |                                |                                |
| <b>11.25 Bend .....</b> | 7 LF or 1 each side            | 8 LF or 1 each side            | 10 LF or 1 each side           |
| <b>22.5 Bend .....</b>  | 14 LF or 1 each side           | 17 LF or 1 each side           | 19 LF or 1 each side           |
| <b>45 Bend .....</b>    | 28 LF or 2 each side           | 34 LF or 2 each side           | 40 LF or 2 each side           |
| <b>90 Bend .....</b>    | 67 LF or 4 each side           | 90 LF or 5 each side           | 95 LF or 5 each side           |
| <b>Tee .....</b>        | 1 each side run<br>2 on branch | 1 each side run<br>2 on branch | 1 each side run<br>2 on branch |