

ROADWAY RESURFACING OF VARIOUS STREETS

CITY OF BRUNSWICK

AUGUST 2018

ADDENDUM #1

1. Add to Scope of Work and asphalt paving quantity:
 - a. Amherst Street from Second Avenue to end (south)

2. Add to Scope of Work and Pavement Marking Quantity:
 - a. Lanier Boulevard – Thermoplastic pavement Marking – Centerline, Edge Lines, Stop Bars - Prince Street to Gloucester Street
 - b. Parkwood Drive – Thermoplastic Pavement Marking – Centerline, Edge Lines, Turn Lanes, Stop Bars, Crosswalks- Altama Ave to Glynn Ave (Hwy 17)
 - c. Union Street – Thermoplastic Pavement Marking – Centerline and Stop Bars - Monck Street to G Street (not including parking stalls)
 - d. Norwich Street – Thermoplastic Pavement Marking – Centerline, Edge Line, Turn Lanes, Stop Bars, Crosswalks - Gloucester Street to Fifth Street

00400 - BID FORM

Roadway Resurfacing - Various Streets

Item #	ITEM DESCRIPTION	UNIT	QUANTITY	UNIT PRICE	TOTAL
1	Mobilization, Traffic Control, Erosion & Sedimentation Control, & other incidental items	ls	1		
2	Mill Existing Asphalt Concrete - 1.5" as required including Hauling to City of Brunswick Public Works	sq. yd.	25,710		
3	Pipe Repair including removal of existing asphalt, excavation, installation of geotechnical fabric, and reconstruction of roadway	each	4		
4	9.5 mm Superpave Recycled Asphalt Concrete - 1.5" Resurfacing	ton	12,220		
5	Solid Traffic Stripe - 5" Yellow - Thermoplastic	lm	7.8		
6	Solid Traffic Stripe - 5" White - Thermoplastic	lm	10.4		
7	Solid Traffic Strip - 8" White - Thermoplastic (Turn Lanes)	lm	0.3		
8	Pavement Marking - Arrows - Thermoplastic	ea	48		
9	Pavement Marking - Stop Bars Thermoplastic - 24"	ea	182		
10	Pavement Marking - Crosswalks - Thermoplastic (GDOT Standard)	ea	13		
11	Sanitary / Storm Manhole Riser Rings	ea	104		
12	Water Valve Riser Rings	ea	96		
				TOTAL	

All items incidental to the work including, but not limited to, worksite traffic control, erosion and sedimentation control, and mobilization shall be included in the unit prices for asphalt paving.

This form includes quantities for items listed in Addendum #1 - Aug. 28, 2018

Street	Begin (From)	End (To)	Approx. Length	Scope of Work	Striping	# of Stop Bars
Shrine	Parkwood	Starling / Lakeside	1650	Resurfacing	CL, EL	4
Wisteria	Wildwood	Boxwood	425	Resurfacing	N	2
Roxboro	Parkwood	Wildwood	615	Resurfacing	CL	2
Dogwood	Boxwood	Redwood	960	Resurfacing	N	2
Wren	Kemble	end (cul-de-sac)	360	Resurfacing	N	1
Maple	Hopkins	Parkwood	1085	Resurfacing	N	3
Kemble	Starling	Fourth Street	1100	Resurfacing	CL	3
Oriole	Altama	Hampton	1810	Resurfacing	N	6
Rosewood	Boxwood	Redwood	960	Resurfacing	N	2
Mimosa	Hopkins	Parkwood	1100	Resurfacing	N	4
Kelwin	Starling	Oriole	530	Resurfacing	N	2
Park	Parkwood	Starling	600	Resurfacing	N	2
R Street	MLK	Altama	563	Resurfacing	N	1
P Street	Norwich	Reynolds	900	Resurfacing	N	2
Lee	Second Street	Fourth Street	1010	Resurfacing	N	2

T Street	Norwich	Altama	2260	Resurfacing	CL	4
O Street	Norwich	Albany	630	Resurfacing	N	2
Gordon	O Street	R Street	1480	Resurfacing	CL	1
O Street	Albany	MLK	471	Resurfacing	N	4
Reynolds	P Street	First Street	2516	Mill Existing, Resurfacing	CL	2
Union	S Street	First Street	1000	Resurfacing	N	4
Wolfe	L Street	N Street	1000	Resurfacing	N	4
Ellis	Q Street	R Street	510	Resurfacing	N	2
Union	R Street	S Street	500	Resurfacing	N	2
O Street	Newcastle	Norwich	1210	Resurfacing	N	6
Gordon	L Street	O Street	1530	Resurfacing	N	2
M Street	Stonewall	Bartow	1100	Resurfacing	N	8
Johnston	M Street	R Street	2350	Resurfacing	N	8
O Street	MLK	Johnston	1104	Resurfacing	N	6
Ellis	G Street	I Street	1020	Resurfacing	N	2
I Street	Ellis	Norwich	390	Resurfacing	N	1

Wolfe	F Street	H Street	1007	Resurfacing	N	4
Johnston	G Street	I Street	1020	Resurfacing	N	2
Gordon	K Street	L Street	490	Resurfacing	N	2
Wilson	Atlanta	G Street	385	Resurfacing	N	2
Tillman	Atlanta	G Street	680	Resurfacing	CL	2
Amherst	Mansfield	Monck	500	Resurfacing	N	2
MLK	George	Monck	1150	Resurfacing	CL	4
Third Ave	Albany	Union	1270	Resurfacing	N	4
Holly	Magnolia	Lanier	1107	Resurfacing	N	4
Monck	Albany	Magnolia	1390	Resurfacing	N	6
Grant	Mansfield	Gloucester	1000	Mill Existing, Resurfacing	N	3
Lanier	Fourth Ave	Prince	3700	Storm Pipe repairs; Mill Existing; Resurfacing	CL, EL	1
Egmont	Prince	London	500	Mill Existing, Resurfacing	N	2
Prince	Albany	Newcastle	1925	Mill Existing; Resurfacing	CL	4
Ellis	Monck	Gloucester	500	Resurfacing	N	2
Emory Dawson	Altama	end of ROW	1670	Resurfacing	CL, EL	1

Rose	Newman	Community	2360	Pipe repair, Resurfacing	CL, EL	2
Community Action Drive	Fourth Street	Glynn Co Stadium	600	Resurfacing	CL	1
Amherst	Second Avenue	dead end (south)	265	Asphalt paving	N	1
Union	Monck	G Street	1550	Pavement Marking - Thermoplastic	CL, EL	6
Parkwood	Altama	Glynn Ave (Hwy 17)	5320	Pavement Marking - Thermoplastic	CL, EL, Turn	2
Lanier	Prince	Gloucester	3275	Pavement Marking - Paint	CL, EL	2
Norwich	Gloucester	Fifth Street	10110	Pavement Marking - Paint	CL, Turn	9

This document includes items listed in Addendum #1 -August 28, 2018