

ADDENDUM NO. I

DATE: April 5, 2017

TO: All Bidders

FROM: Janice McClelland, Assistant Purchasing Agent

SUBJECT: Addendum No. 1 – Knoxville Zoo Drive and Emerald Youth Sports Complex Signalization

BIDS TO BE OPENED: April 18, 2017, at 11:00:00 a.m. Eastern Time

This addendum is being published to respond to questions asked by potential bidders regarding the above-referenced Invitation to Bid. This addendum becomes a part of the Contract Document and modifies the original specifications as noted.

Questions Received

Q: Will there be removal of existing steel signal poles, pole foundations, and electrical work in the contract?

A: Pay Item 730.13, Removal of Existing Signals, has been added to the bid proposal (BD-6). **Important note: Bidders MUST use the Revised Bid Proposal form that immediately follows this Addendum.**

This new pay item includes removal and transportation of five (5) existing signal poles to the City of Knoxville pole yard for the Rutledge Pike & I-40E exit (3 existing poles) and Prosser Road & Knoxville Zoo Drive (2 existing poles) intersections. The pay item will be a single lump sum of the removal and transportation of the five existing signal poles and demolition of their foundations.

The scope of work for the additional pay item is immediately follows this Addendum. Removal of all other signal infrastructure will be completed by the City of Knoxville.

Clarifications and Changes to the Contract Documents & Specifications

1. Pay item 730.10 Roadway Boring includes conduit per scope of work. Pay item 730.6 has been reduced due to this discrepancy (see new BD-6, Revised Bid Proposal form).
2. Pay item 730.6 and scope of work contradicted each other on number of runs of conduit. Pay item 730.6 has been changed to “2 Inch Schedule 80 PVC conduit” (see new BD-6, Revised Bid Proposal form).

END OF ADDENDUM NO. I

REVISED BID PROPOSAL
CITY OF KNOXVILLE, TENNESSEE

**Knoxville Zoo Drive & Emerald Youth Sports Complex Signalization Projects
Project No. 17EH-SG-0001**

TO THE PURCHASING AGENT
CITY OF KNOXVILLE, TENNESSEE

_____ hereby propose(s) to furnish all material, labor, and appliances and do all work required to complete the Contract for the Knoxville Zoo Drive & Emerald Youth Sports Complex Signalization Projects, Project No. 17EH-SG-0001, located in the City of Knoxville, Tennessee, in a workmanlike manner and in accordance with the plans of the Department of Engineering and specifications herewith attached.

_____ further agree(s) that in case of failure on _____ part to sign this within fifteen (15) days, the certified check or bid bond accompanying this proposal and the proceeds thereof shall be the property of the City of Knoxville.

BID SCHEDULE

ITEM NO.	DESCRIPTION	UNITS	TOTAL QUANTITY	PRICE PER UNIT	TOTAL PRICE PER ITEM
730.1	15 Ft Depth Strain Pole Foundation	EA	3	_____	_____
730.2	19-21 Ft Depth Strain Pole Foundation	EA	5	_____	_____
730.3	22-24 Ft Depth Strain Pole Foundation	EA	3	_____	_____
730.4	Mast Arm Placement	EA	8	_____	_____
730.5	Pedestal Pole Foundations	EA	3	_____	_____
730.6	2 Inch Schedule 80 PVC Conduit	LF	1400	_____	_____
730.7	Pull Box Installation	EA	11	_____	_____
730.8	Controller Cabinet Foundation	EA	2	_____	_____
730.9	Rock Excavation	LF	50	_____	_____
730.10	Roadway Boring	LF	500	_____	_____
730.11	Sidewalk Repair	SF	50	_____	_____
730.12	Additional Concrete	CF	50	_____	_____
730.13	Removal of Existing Signals	LS	1	_____	_____
TOTAL BID				\$	_____

TOTAL BID (In Words):

Additional Scope of Work for Removal and Transportation of Five Existing Steel Poles and Demolition of their Foundations

1. Provide a Tennessee One Call excavation ticket number for the location to be designated by the City of Knoxville, Engineering Department for the proposed pole location.
2. After the locations have been properly cleared by the local utilities, remove the existing steel poles and demolish their foundations to 4 inches below existing grade. Place soil and seed on top of each foundation.
3. Transport steel pole from Rutledge Pike/I-40E exit or Prosser Road/Knoxville Zoo Drive location to the City of Knoxville pole yard.
4. Any damage to materials in transport is the responsibility of the contractor and must be repaired or replaced to the original design requirements and be certified as such.