

Finance Department
Fifty Raupp Blvd.
Buffalo Grove, IL 60089-2198
Phone 847-459-2525
Fax 847-459-7906

2019 Local Sewer Lining Project
ADDENDUM #1

TO: Prospective Bidders and Other Interested Parties

FROM: Village of Buffalo Grove Finance Department

ISSUE DATE: June 26, 2019

SUBJECT: ADDENDUM #1

Note: This Addendum is hereby declared a part of the original proposal documents and in case of conflict, the provisions in the following Addendum shall govern.

The following changes and clarifications shall be made to the Bid Documents for 2019 Local Sewer Lining Project. (VoBG-2019-25).

Revision 1 General Condition 4 – Completion Date

The condition shall now read:

The Contractor shall **execute the contract within then working days after contract award. Within 15 calendar days from the contract execution the Contractor will provide the Village with a start date and schedule.** The work shall be prosecuted in such a manner and with such a supply of materials, equipment and labor as considered necessary to ensure its completion according to the time specified in the contract.

Once the work has started, the Contractor shall complete all work in the Contract within 35 working days as described in Article 108.04 of the Standard Specifications. If Alternate 01 is awarded, an additional 20 working days shall be allowed; if Alternate 02 is awarded, an additional 10 working days shall be allowed. Charging of working days will start when the Contractor begins work and be defined as any calendar day between January 1 and December 31 inclusive, except Saturday, Sundays, or legal holidays.

The Contractor shall substantially complete all work under this Contract for the Village of Buffalo Grove by November 15, 2019 with Final Completion by November 29, 2019.

Following substantial completion, the Contractor shall provide the Village written notice in accordance with Article 105.13 of the Standard Specifications. The Contractor will have fourteen (14) calendar days to correct any deficiencies following the scheduled final inspection and punch list submittal by the Village.

In case of failure to complete the work on time, the provisions of Article 108.09 of the Standard Specifications shall apply. In case of failure to complete the work on time and/or the

deficient punch list items, the provisions of Article 108.09 of the Standard Specifications shall apply, except regardless of the Contract amount, the daily charge shall be \$2,000 per calendar day overrun. Landscape restoration planting times shall follow Article 250.07 of the Standard Specifications.

The estimated Village Board award date for this project is Monday, July 15, 2019.

Revision 2 General Condition 9 – Use of Fire Hydrants

Strike the current condition and replace with:

Local Water Plan - The Contractor can obtain non-potable water in bulk at no charge at Buffalo Grove Public Works Department, 50 Raupp Blvd. The Contractor shall provide the water truck and driver to obtain and transport the water. In addition, the Village of Buffalo Grove will provide a water meter and allow a contractor hook up to a hydrant on site if they can supply the appropriate system and responsibly operate the hydrant. The contractor must provide a backflow preventer that has been bench tested in the last 12 months and supply those passing results to the Village before hook up. They also must have a system to support the backflow preventer and meter off of the hydrant so the threaded connections are not the only object supporting all the weight. Wood is an acceptable apparatus but it must be cut to an appropriate length and hold the backflow preventer and meter in a “saddle” so it cannot easily slip out. The hydrant must be operated very slowly as to not create any percussions in the Village’s water system. Failure to operate the hydrant appropriately or provide the correct materials will result in the contractor being required to truck water from the Village’s Public Works building.

Revision 3 Special Provision 1 – Pre-Construction Cleaning and Televising of Sewer

In response to the question of “Is having a vac truck mandatory for all prep of only when necessary?” Per the bid documents:

Debris catchers or baskets will be required to be set in the channel of the downstream manhole during all cleaning operations. Additionally, a ‘Vector’ or similar vacuum truck must be on-site during all cleaning operations and will be required to be setup on the downstream manhole to pull debris out of the sewer during all cleaning operations. As the sewer jet or other cleaning equipment is in use, the vacuum equipment shall be running in order to prevent debris from moving further downstream. The use of the vacuum truck does not constitute heavy cleaning.

The contractor is also required to ensure no passage of construction material makes it into the Village’s sewer systems and therefore must have a vac truck on site outside of cleaning anytime they need to one to accomplish that requirement.

**PROSPECTIVE BIDDERS ARE TO ACKNOWLEDGE RECEIPT OF ADDENDUM #1.
INCLUDE AND NOTE THIS ADDENDUM IN YOUR PROPOSAL.**

PROSPECTIVE BIDDER: _____

SIGNED: _____ **DATE:** _____