



City of Myrtle Beach
SOUTH CAROLINA

PURCHASING AND
MATERIALS MANAGEMENT

(843) 918-2170
FAX: (843) 918-2182

Addendum 001
Bid 17-B0031
Highway 501 Sidewalks and Drainage

The City of Myrtle Beach held a Pre-Bid Meeting on January 5, 2017. Those in attendance were:

| | |
|-------------------|---------------------------|
| Daron Stalvey | Stalvey Concrete |
| Reid Hagwood | King Construction |
| Donnie Strickland | Triangle Grading & Paving |
| Keith Messimer | PSI |
| Keith Benton | Benton Concrete |
| Shane Gibbs | Palmetto Corp. |
| Jerry Wiseman | R.H. Moore |

The following questions have been asked and the answered below:

1. Plans Show 38 LF of 12" CMP located @ Elder Drive. No bid Item Can you add a Bid item?
 - a. **38 LF of 12" CMP added to Bid Tab.**
2. Page 0550-20 & 0550-21. Paragraphs I & J Require the contractor to pay for all testing of the Subgrade & Concrete. Will testing be required, if so how many test will be required?
 - a. **No testing will be required**
3. Will O-Ring Joints be required on the RCP Pipe?
 - a. **Please price and use Class III RCP**
4. Will the drainage piping need to be backfilled according to SCDOT specs? This is much more costly than using excavated materials. Please advise.
 - a. **Excavated material will be fine for pipe backfill provided it is dry free from organics and compacted.**
5. Will borrow excavation be required to achieve desired finished grades? If so can a line item with a unit price per CY be added?
 - a. **No, sidewalk will be at grade and materials will be excavated 6" to get the required thickness of walk only backfill materials will be needed and should be added in the price to fine grade and backfill. All materials can be used as sidewalk backfill as long as they are graded smooth and compacted.**

6. Is this going to be done during the night?
 - a. Not required but you can if you want
7. Will all utility conflicts be moved by others?
 - a. No, other than one fire hydrant in front of Food Lion Shopping Center (the city will provide a new fire hydrant to be installed if needed) and 1 guide wire at Balsam; utility conflicts will be avoided by constructing sidewalk around utility. Contractor to coordinate guide wire arm added to clear walk.
8. What is the pipe bedding?
 - a. Existing soil should be fine as long as it is dry and compacted to provide a firm level bedding to support pipe.
9. Is the contractor responsible for their own laydown yard?
 - a. A laydown yard can be utilized at 3rd Ave S and US Hwy 501
10. Section 1400 states contractor will pay for testing services. Can you provide us the testing requirements?
 - a. No testing required.
11. Will the contractor need to figure any muck/fill for this project?
 - a. Newly installed storm pipe will need to have a firm bedding.
12. The bid tab states Fine grading and backfill. What is the limits of disturbance? What areas will be backfilled?
 - a. The limits of disturbance are up to the contractor. All disturbed areas will be graded and stabilized. The backfill will be the required fill to make the sidewalk flush with the back side of the walk after the concrete is placed at a maximum 2% cross slope.
13. There are not any grades on the set of plans provided by the city. Does the contractor need to figure any imported fill or removal of excess materials.
 - a. All materials can be needed on site. The sidewalk will be at grade for the most part since Hwy 501 stormwater is required to run over walk.
14. During the pre-bid the contractor was asked to add a line item for 5' wide sidewalk. Where do we add this at?
 - a. The newly provided bid tab.
15. Can we get a pre-bid sign in sheet?
 - a. Attached.
16. If an existing driveway is already damaged once work begins who will be responsible? Do you foresee any driveways having to be poured in this contract?
 - a. No existing damaged driveways will be repaired. The plans show only the concrete for a walk. Some saw cutting may be needed to provide a straight edge when meeting a driveway or road. If contractor damages a drive some repair will be needed to fix damage.

Thank you, and if you have any questions please call,


Ruth Burleson

US HWY 501 Sidewalk & Associated Drainage

| Item | Quantity | Unit Cost | Total |
|---------------------------------|----------|-----------|-------|
| Traffic Control | 1 LS | | |
| 15" Class III RCP | 216 ft | | |
| 18" Class III RCP | 328 ft | | |
| 12" CMP | 38 ft | | |
| Catch Basin | 5 ea | | |
| 6' Sidewalk 6" thick | 6200 ft | | |
| 2'x5' Detectable Warning strips | 9 ea | | |
| Thermoplastic Striping | 1 LS | | |
| Fine grading and back fill | 1 LS | | |
| Subtotal | | | |
| Project Total | | | |
| 5' Sidewalk 6" thick | 6200 ft | | |