

CITY OF GRIFFIN
SPRINGER DRIVE CULVERT REPLACEMENT

FROM: PARAGON CONSULTING GROUP, INC.
118 NORTH EXPRESSWAY
GRIFFIN, GA 30223

TO: ALL BIDDERS OF RECORD

RE: Addendum No. 1, dated March 20, 2018

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated March 2018.

This Addendum consists of two (2) pages, two (2) Bid Tab pages, three (3) Supplemental Drawings.

CONTRACT DOCUMENTS AND SPECIFICATIONS

- Add. 1.1 Clarification: The City of Griffin will not supply the GDOT 1019A grate inlets or risers. The Contractor should price the grates under the “GDOT 1019A GRATE INLET WITH HOOD & BRICK RISER FROM BOX CULVERT” Bid Tab item. Precast holes will be provided in the box culvert for installation.
- Add. 1.2 Modification: Supplemental Drawing SD-1 is attached to this addendum and becomes a part of the Contract Documents.
- Add. 1.3 Modification: Supplemental Drawing SD-2 is attached to this addendum and becomes a part of the Contract Documents.
- Add. 1.4 Modification: Supplemental Drawing SD-3 is attached to this addendum and becomes a part of the Contract Documents.
- Add. 1.5 Modification: Delete Bid Tab item “BOX CULVERT BASE PREPARATION, ROCK, & FABRIC COMPLETE”.
- Add. 1.6 Modification: Add Bid Tab item “ROCK FOR CULVERT AND WINGWALL FOUNDATION PER PLAN DETAIL” with a quantity of 450 TN.
- Add. 1.7 Modification: Add Bid Tab item “GEOTEXTILE FABRIC FOR CULVERT AND WINGWALL FOUNDATION PER PLAN DETAIL” with a quantity of 350 SY.
- Add. 1.8 Modification: Add Bid Tab item “CONCRETE APRONS COMPLETE PER SUPPLEMENTAL DRAWINGS” with a quantity of 2 EA.

- Add. 1.9 Modification: Change the quantity of Bid Tab item “ROCK PREPARATION FOR INSTALLATION OF FOUNDATION AND WINGWALLS” from 0 CY to 10 CY.
- Add. 1.10 Modification: Change the quantity of Bid Tab item “G.A.B. COMPACTED IN PLACE FOR BACKFILL OF CULVERT” from 500 TN to 1,850 TN.
- Add. 1.11 Clarification: The preliminary shop drawings of the box culvert indicate that each of the four wing walls is a single piece. In addition, there are two parapets which required bolting to each end of the box.
- Add. 1.12 Clarification: The stone and geotextile fabric sub-base foundation is consistent under the box culvert and concrete aprons. The stone and geotextile fabric quantities on the Bid Tab were determined using the footprint of the box culvert and concrete aprons.

End of Addendum No. 1