CITY OF GRIFFIN SPRINGER DRIVE CULVERT REPLACEMENT BID TAB

Item	Description	Unit	Quantity	Unit Price	Item Total		
GENERAL							
1.	PAYMENT & PERFORMANCE BONDS	LS	1				
2.	GENERAL CONDITIONS	LS	1				
3.	CONSTRUCTION STAKING BY REGISTERED SURVEYOR	LS	1				
4.	AS-BUILT SURVEY BY REGISTERED SURVEYOR	LS	1				
	General Subtotal =						
DEMOLITION/REMOVAL							
5.	DEMOLITION OF EXISTING CMP CULVERT INCLUDING OFFSITE DISPOSAL	LS	1				
6.	SAW CUT ASPHALT (VARIOUS DEPTHS)	LF	50				
7.	REMOVAL OF ASHPALT PAVING COMPLETE INCLUDING OFFSITE DISPOSAL (VARIOUS THICKNESS)	SY	261				
8.	CONCRETE RIBBON CURB REMOVAL & OFFSITE DISPOSAL	LF	200				
9.	MILLING	SY	130				
10.	REMOVE AND DISPOSE OF 6" WATER MAIN	LF	115				
11.	TREE REMOVAL - 8-INCH CALIPER	EA	2				
12.	TREE REMOVAL - 15-INCH CALIPER	EA	1				
			Demolition/	/Removal Subtotal =			
	CULVERT INSTALLATION						
13.	INSTALLATION OF NEW BOX CULVERT & WING WALLS COMPLETE (CULVERT TO BE PROVIDED BY OWNER)	LS	1				
14.	ROCK FOR CULVERT, WINGWALL, AND APRON FOUNDATION PER PLAN DETAIL	TN	450				
15.	GEOTEXTILE FABRIC FOR CULVERT, WINGWALL, AND APRON FOUNDATION PER PLAN DETAIL	SY	350				
16.	CONCRETE APRONS COMPLETE PER SUPPLEMENTAL DRAWINGS	EA	2				
17.	GRADING COMPLETE (TOPSOIL, FINE GRADING, & REPLACEMENT OF EXISTING FILL EXCAVATED AND/OR OFFSITE REMOVAL)	LS	1				
18.	ROCK PREPARATION FOR INSTALLATION OF FOUNDATION AND WINGWALLS	CY	10				
19.	G.A.B. COMPACTED IN PLACE FOR BACKFILL OF CULVERT	TN	1,850				
20.	ASPHALT PAVING (8:2:2 SECTION)	SY	261				
21.	24" STANDARD CURB & GUTTER	LF	200				
22.	TYPE III RIP RAP - IN BOX FLOOR	SY	144				
			Culvert Ins	stallation Subtotal =			
	WATER MAIN						
23.	6-INCH PRESSURE CLASS 350 DIP WATER MAIN	LF	105				
24.	6-INCH GATE VALVE RODDED TO PULL BLOCK COMPLETE	EA	2				
25.	CONCRETE PULL BLOCK PER PLANS	EA	2				
26.	WATER MAIN CHLORINATION & TESTING	LS	1				
	Water Main Subtota						

Item	Description	Unit	Quantity	Unit Price	Item Total		
STORM DRAINAGE							
27.	GDOT 1019A GRATE INLET WITH HOOD & BRICK RISER FROM BOX CULVERT	EA	2				
	Storm Drainage Subtotal =						
EROSION CONTROL							
28.	TYPE 'C' SILT FENCE INLCUDING MAINTENANCE & REMOVAL	LF	350				
29.	SAND BAGS, INCLUDING MAINTENANCE & REMOVAL	LF	120				
30.	HAY BALES, INCLUDING MAINTENANCE & REMOVAL	LF	100				
31.	STRAW/COCONUT MATTING	SF	1,500				
32.	PERMANENT GRASSING, INCLUDING MULCH	SF	2,000				
33.	TYPE III RIP RAP- MISC E&S	TN	300				
34.	TYPE I RIP RAP	TN	30				
35.	CONCRETE WASHDOWN PER PLANS	EA	1				
36.	CONCRETE EROSION BARRIER MATERIAL	SF	1,200				
37.	BERMUDA SOD	SF	2,000				
	Erosion Control Subtotal =						
MISCELLANEOUS							
38.	5-FOOT WIDE CONCRETE SIDEWALK (4-INCHES THICK)	SF	500				
39.	G.D.O.T. W-BEAM GUARD RAIL & SUPPORTS WITH REFLECTORS COMPLETE	LF	100				
40.	TEMPORARY STREAM BYPASS PUMPING AS REQUIRED FROM CONSTRUCTION	LS	1				
41.	STREAM BANK EROSION RESTORATION	LS	1				
	Miscellaneous Subtotal =						
		TOTAL CONSTRUCTION					