

ADDENDUM 4

**SOLID WASTE DISPOSAL DISTRICT
INDIAN RIVER COUNTY LANDFILL
PHASE 2 - CELL 3 - SEGMENT 3 EXPANSION (11.5 AC.)
BID FORM, REV. 2**

| Item No. | Work Description/Item | Units | Estimated Quantity (Note VI) | Unit Cost (\$) | | Total Cost (\$) |
|--|--|-------|------------------------------|---------------------------------------|-------|-----------------|
| | | | | Material | Labor | |
| General Site Preparation | | | | | | |
| 1 | Mobilization and Demobilization (not-to-exceed 5% of total bid) (Note I) | LS | 1 | | | |
| 2 | Surveying & As-Built Drawings (Note II) | LS | 1 | | | |
| | | | | Subtotal Site Preparation = | | |
| Earthwork (Includes Grading and In-place Compaction Note III) | | | | | | |
| 3 | General and Structural Fill | | | | | |
| | A. Site Grading and Leveling of Top of Liner Subbase Prior to Geosynthetics Installation (Primarily Cut) | cyd | 1,400 | | | |
| | | | | Subtotal Earthwork = | | |
| Cell 3 Liner System (Note IV) | | | | | | |
| 4 | Liner Protective Layer | | | | | |
| | A. 24-in. Liner Protective Layer with Grading and Compaction | cyd | 36,000 | | | |
| | B. Intercell Separation Berm | cyd | 1,200 | | | |
| | C. Temporary Intercell Berm with Rain Flap | cyd | 1,700 | | | |
| 5 | Primary Geocomposite Drainage Layer | sq ft | 499,500 | | | |
| 6 | Primary 60 mil Textured HDPE Geomembrane | sq ft | 499,500 | | | |
| 7 | Secondary Geocomposite Drainage Layer | sq ft | 499,500 | | | |
| 8 | Secondary 60 mil Textured HDPE Geomembrane | sq ft | 499,500 | | | |
| 9 | Geosynthetic Clay Liner | sq ft | 499,500 | | | |
| 10 | Electrical Leak Location Survey | LS | 1 | | | |
| 11 | Liner System Tie-in (Extrusion Weld/Double-track Fusion Weld) | LF | 1,300 | | | |
| 12 | Geomembrane Rainflap | | | | | |
| | A. Geomembrane Rainflap | sq ft | 37,100 | | | |
| | B. Extrusion Weld - Geomembrane Sacrificial Rainflap to Primary HDPE Geomembrane | LF | 1,300 | | | |
| 13 | Anchor Trench | LF | 2,900 | | | |
| | | | | Subtotal Cell 3 Liner System = | | |
| Leachate Collection & Detection System | | | | | | |
| 14 | LCS Corridor | | | | | |
| | A. Granular Drainage Material (AASHTO No. 57) | cyd | 1,000 | | | |
| | B. Geotextile Filter/Cushion with 2-in. overlap and sewn at seam | sq yd | 900 | | | |
| 15 | LDS Additional Geonet Drainage Layer in Corridor | sq yd | 1,920 | | | |
| 16 | LDS Granular Drainage Material (AASHTO No. 4) | cyd | 80 | | | |
| 17 | 10-in. Dia. SDR 17 Solid HDPE Carrier Pipe (Leachate Collection + Leachate Detection + Leachate Gravity Line + Horizontal Direction Drill) | LF | 510 | | | |
| 18 | 12-in. Dia. SDR 21 Solid HDPE Containment Pipe (Leachate Collection + Leachate Detection + Leachate Gravity Line + Horizontal Direction Drill) | LF | 510 | | | |
| 19 | 10-in. Dia. SDR 17 LDS Perforated Pipe & Fittings | LF | 350 | | | |
| 20 | 10-in. Dia. SDR 17 LCS Perforated Pipe & Fittings | LF | 1,300 | | | |
| 21 | Toe Drain (Note VII.) | | | | | |
| | A. 6-in Dia. SDR 17 Perforated HDPE Pipe | LF | 1,250 | | | |
| | B. Toe Drain Connector and Reducer | each | 2 | | | |
| | C. Granular Drainage Material (AASHTO No. 57) | cyd | 200 | | | |
| | D. Geotextile Filter/Cushion with 2-in. overlap and sewn at seam | sq yd | 1,560 | | | |
| 22 | Jet Cleaning and Video Inspection of LCS and LDS | LS | 1 | | | |
| 23 | Trenches with Unpaved Easements | LF | 300 | | | |
| 24 | Excavation, Grading, and Compaction for Sump | LS | 1 | | | |
| 25 | 10-in. Dia. Perforated Leachate Detection Manifold | each | 1 | | | |
| 26 | LCS & LDS Cleanout | | | | | |
| | A. 10-in. Dia. Solid SDR-17 LCS Cleanout Pipe with Gasket, Secure Boot and all other Fittings | LF | 20 | | | |
| | B. 4'X5'X5" Fiber Reinforced Concrete Collar | each | 3 | | | |
| | C. 10-in. Dia. Solid SDR-17 LDS Cleanout Pipe with Gasket, Secure Boot and all other Fittings | LF | 130 | | | |
| | D. LCS & LDS Cleanout Cap and fittings | each | 3 | | | |
| | E. WYE Fittings for LCS Cleanout | each | 1 | | | |
| 27 | Wall Sleeve with Mechanical Seal | each | 12 | | | |
| 28 | Liner Penetration Box | each | 3 | | | |

ADDENDUM 4

**SOLID WASTE DISPOSAL DISTRICT
INDIAN RIVER COUNTY LANDFILL
PHASE 2 - CELL 3 - SEGMENT 3 EXPANSION (11.5 AC.)
BID FORM, REV. 2**

| Item No. | Work Description/Item | Units | Estimated Quantity (Note VI) | Unit Cost (\$) | | Total Cost (\$) |
|--|---|-------|------------------------------|----------------|-------|-----------------|
| | | | | Material | Labor | |
| 29 | Valve and Box with Box Pad | each | 1 | | | |
| 30 | Concrete Slab for Control Panel | each | 1 | | | |
| 31 | Electrical, Control Panel, Grounding & Lightning Protection (Note V) | LS | 1 | | | |
| 32 | LDS Pump Station Sump Pump | each | 1 | | | |
| 33 | LCS Manhole | each | 1 | | | |
| 34 | Reinforcements around openings | LS | 1 | | | |
| 35 | Liner Markers (Post- 4"x4"x8") | each | 2 | | | |
| 36 | Bollard Post with Encasement | each | 5 | | | |
| 37 | Limit of Waste Markers | each | 6 | | | |
| 38 | Marker Tape | LF | 800 | | | |
| 39 | Post Mounted Pipe Support | each | 2 | | | |
| 40 | 8-Ft. Aluminium Sign Post with 2-Ft. Dia. Concrete Footing | each | 1 | | | |
| 41 | 24-in. x 20-in. Warning Sign | each | 1 | | | |
| **42 | Sandbags | each | 1,000 | | | |
| 43 | Rain Tarp (Dura Skirm 12 BV or approved equivalent) with Ropes & Ties | sq ft | 334,000 | | | |
| Subtotal Leachate Collection Sump = | | | | | | |
| Drainage Ditch, Access Road and Entrance Road | | | | | | |
| 44 | Regrading | LF | 100 | | | |
| 45 | Access Roads and Ramps | | | | | |
| | A. RCA - Provided by the Client (Labor Only) | cyd | 150 | | | |
| | B. Stabilizer Material | cyd | 100 | | | |
| 46 | 24-in. by 36-in. RCP Elliptical Culvert | LF | 130 | | | |
| Subtotal Drainage Ditch & Access Road = | | | | | | |
| Miscellaneous | | | | | | |
| 47 | Erosion and Sediment Controls | LS | 1 | | | |
| 48 | Site Restoration including Vegetation | acres | 1.35 | | | |
| Total Miscellaneous = | | | | | | \$0.00 |
| SUBTOTAL = | | | | | | \$0.00 |
| 15% CONTINGENCY = | | | | | | \$0.00 |
| TOTAL = | | | | | | \$0.00 |

- I. Mobilization/Demobilization (Item 1) shall include any partial demobilization required for all components of construction specified herein and in the Construction Drawings and Technical Specifications.
- II. The survey activities (Item 2) shall include surveying of existing conditions prior to construction, as-built surveys, liner protective, leachate collection system, a final survey and any surveying needed throughout the duration of the project.
- III. Earthwork quantities are in-place compacted quantities. Earthwork pay items include all cost to haul, place, compact, and grade general/structural fill. Existing conditions represent top of liner subbase resulting from Phase I Site Preparation construction project. For bidding purposes assume 2 inches of fill material will be placed. Payment will be based on actual quantity placed based on initial and final as-built survey of top of liner subbase.
- IV. All geosynthetic quantities provided are installation quantities for bid estimate purposes. Material supply quantities shall be based on installed panels and layout, surveyed by the Owner's surveyor and approved by the Engineer. Supply quantities shall include waste, slope, anchor trench, overlap, and any other adjustment factors necessary to supply all material to complete the work. Install pay quantities will be based on actual square footage verified by 3rd party survey.
- V. Includes all material, equipment and labor required to install pumps, piping, meters, valves, and other components/instrumentation at the leachate collection and detection systems and sumps.
- VI. Quantities presented herein are estimated quantities and should be verified by Contractor. If quantities are found to be significantly different, Contractor shall notify Construction Manager. Quantities not provided shall be estimated and verified by Contractor. Payment shall be made on surveyed and calculated quantities in accordance with the Technical Specifications.
- VII. Toe drain is currently pending permit modification approval by FDEP.