
To:	Addendum #2 Hutchinson Square Park Improvements for Town of Summerville	From:	Josh Lilly, PE 4969 Centre Pointe Drive, Suite 200 North Charleston SC 29418-6952
File:	178420699	Date:	February 16, 2018

Reference: Addendum – Hutchinson Square Park Improvements – Road and Park Bid

This Addendum is being issued for both bids associated with the Hutchinson Square Park and should be acknowledged in the bid form for both the Park and the Road.

The following changes have been made to the bidding and contract documents dated January 24th, 2018:

Clarification:

1. All acorn lights as specified and called out on the plan shall be 10' tall and the color shall be "Summerville Green" to match the existing light poles along Little Main. The top ornamental spike on the globe shall be green to match the pole.

Road Plan Set – Plan Sheet C10

2. Detail 6 – Heavy Duty Asphalt Pavement Section: Pavement Section should be constructed with 1.5" of Intermediate Course SCDOT **Type C** and 1.5" of Surface Course SCDOT **Type C** Asphalt. Materials and construction methods are to meet SCDOT Specifications.

Park Plan Set – Plan Sheet E3.1

3. Lighting Fixture Schedule, add the following: Fan shall be manufactured by Big Ass Fan, model 10' Essence. See Architectural sheets for additional information.

Questions – Roadway Improvement Project:

4. Q – Per the geo report on page 1 (Executive Summary 1.0) states that 2 feet of undercutting may be required below little main street. Can you confirm that the undercutting of unsuitable material should be added to line item 10 of the bid form (demolition little main street) and the structural fill up to 18 inches should be added under line item 25 of the bid form (grading roadway)?

A – Contractor shall add Line Item #25 to the bid form with the following: "Remove, dispose, and place suitable Fill Material - 400 CY". Material will be measured as a placed volume and not based on truck load tickets.

Reference: Addendum – Hutchinson Square Park Improvements – Road and Park Bid

Once subgrade is exposed and the existing material is suitable for a proof roll, this amount will be credited back to the owner.

Questions – Park Improvement Project:

5. Q – Can you please confirm there should be structural fill placed under the new pavilion per the geo report? If so, which unit price item should this be put under?
- A – Fill material for the Pavilion is included in Line Item # 12 on the bid form.

STANTEC CONSULTING SERVICES INC.



Josh Lilly, P.E.
Civil Engineer
Phone: (843) 740-6332
Fax: (843) 740-7707
Josh.Lilly@stantec.com

End of Addendum