

**LaGRANGE THREAD PHASE 8-CLOCK TOWER (SOUTHBEND PARK TO KEX MILL) - BID FORM PROPOSAL**

Section A: Roadway / Trail					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
140-1000	1	LS	MOBILIZATION		
150-1000	1	LS	TRAFFIC CONTROL		
210-0100	1	LS	GRADING COMPLETE (INCLUDING DEMOLITION, & TREE REMOVAL)		
310-5060	275	SY	GR AGGR SUBBASE CRS, 6 IN, INCL MATL		
402-3103	25	TN	1 1/2 IN RECYCLED ASPH CONC 9.5MM SUPERPAVE GP 2 ONLY, INCL BITUM MTL & H LIME		
402-3910	250	TN	RECYCLED ASPH CONC 12.5MM SUPERPAVE GP 2 ONLY, INCL BITUM MTL & H LIME. VARIABLE DEPTH PER PLAN SHEET RC-01		
402-4012	32	TN	2 IN RECYCLED ASPH CONC 19MM SUPERPAVE GP 1 OR 2, INCL BITUM MTL & H LIME		
413-1000	68	GL	BITUM TACK COAT		
432-0200	1580	SY	MILL EXISTING ASPHALT SURFACE, MILL DEPTH VARIES (CHERRY & DOUGLAS STREETS)		
441-0018	170	SY	CONC DRIVEWAY APRON, 8 IN PER GDOT STD. A2 (Labor, form, finish only) Materials furnished by city		
441-0105	2125	SY	CONCRETE TRAIL, SIDEWALK, CL 3000 PSI, 5 IN, 9-12 FT, INCL ADA RAMPS & POCKET PARK (Labor,form,finish only) Concrete finished by City		
441-0106	25	SY	CONC. FLUME, CL 3000 PSI, 6 IN, PER PLANS (Labor,form,finish only) Concrete finished by City		
444-1000	1,400	LF	SAWED JOINTS IN EXISTING PAVEMENTS, (Space btw joint to equal trail width)		
441-5001	750	LF	CONCRETE HEADER CURB, 4 IN, TP. 2 (Labor, form, finish only) Concrete furnished by City		
441-5002	130	LF	CONCRETE HEADER CURB, 6 IN, TP. 2 (Labor, form, finish only) Concrete furnished by City		
441-6012	55	LF	CONC CURB & GUTTER, 6 IN X 24 IN, TP 2. (Labor, form, finish only) Concrete furnished by City		
500-3800	2	SY	CLASS A CONCRETE STAIRS (INCL REINF) - PER PLANS. (Labor, form, finish only) Concrete furnished by City		
611-5002	1	EA	RESET CH LK FENCE GATE		
611-5010	150	LF	RESET CH LK FENCE		
611-5360	4	EA	RESET HWY SIGN		
611-5550	1	EA	RESET EXISTING SIGN, 'NEW COVENANT CHURCH' (STA: 2+10)		
611-5552	4	EA	RESET EXISTING MAILBOX		
611-8120		EA	ADJUST UTILITY TO GRADE (WATER, GAS, ELECTRIC, ETC.)		not in contract- city responsibility
636-1014	36	SF	MUTCD HIGHWAY SIGNS		
636-1042		SF	THREAD TRAIL SQUARE MATL 0.125 ALUM, DIRECT PRINT		not in contract- city responsibility
636-1043		LF	THREAD TRAIL SQUARE 3"X3" POST		not in contract- city responsibility
636-3010	98	LF	MUTCD HIGHWAY SQUARE POSTS, 14 FT PER GDOT		
643-1462	390	LF	VINYL-COATED CHAIN LINK FENCE, 6' TO 8' HT PER PLANS, BLACK, W/ EXT. ARMS & BARBED WIRE.		
643-8050	1	EA	VINYL-COATED CHAIN LINK SECURITY SINGLE GATE & POSTS, 8' HT, BLACK, W/ EXT. ARMS & BARBED WIRE.		
643-8081	1	EA	LEVER WITH MANUAL KEY CODE PAD, INCL GATE BOX & HARDWARE		
643-8200	275	LF	BARRIER TREE FENCE (ORANGE), 4' HT		
652-5301	425	LF	THERMO SOLID TRAFFIC STRIPE, 8 IN WHITE, 10' WIDE (GDOT CROSSWALKS)		
653-1704	68	LF	THERMO SOLID TRAFFIC STRIPE, 24 IN, WHITE (STOP BARS)		
652-6502	1400	LF	PAINTED SKIP STRIPING (YELLOW) (TRAIL CL) , 4 IN, STRIPE LENGTH AND GAP TO EQUAL TRAIL WIDTH		

652-9002	16	SY	PAINTED SOLID YELLOW STRIPING (TRAIL NARROWS WARNING STRIPING), 4 IN		
668-6113	65	LF	9/16" WEATHERED STEEL TRENCH PLATE, SKID RESISTANT, PER PLANS		
900-0526	4	EA	FIXED STEEL BOLLARDS		
900-0527	5	EA	STEEL REMOVABLE BOLLARDS		
999-5200	136	SF	4"X8" DETECTABLE ADA PAVERS (RED),		
754-1050	2	EA	PICNIC TABLE		not in contract- city responsibility
754-4000	1	EA	WASTE RECEPTACLE UNIT		not in contract- city responsibility
Section A Sub Total					

Section B: Structural Slabs/Retaining Walls					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
445-1002	1	LS	TURNDOWN WALL 1 COMPLETE AS SHOWN INC. REINF, POST & CABLE RAILING & FORM LINE FINISH (STA 4+45 TO STA 5+45)		
445-1003	1	LS	10' X 12' CONC. STRUCTURAL SLAB, INCL REINF & POST & CABLE HANDRAIL (STA 12+05)		
445-1004	1	LS	SPCL DESIGN CONC. STRUCTURAL SLAB, INCL REINF & POST & CABLE HANDRAIL (STA 13+50 TO STA 13+70)		
515-1000	38	LF	METAL HANDRAIL, SPCL DESIGN (POST & CABLE) STA 5+80 TO STA 6+07		
<b>TOTAL ON SECTION 2</b>					

Section C: Miscellaneous					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
222-1002	315	SY	#57 STONE (CLEAN), 6 IN, (ROOT BRIDGING AREAS AND GRAVEL DRIVE AT STA 5+50)		
603-7000	275	SY	PLASTIC FILTER FABRIC (ROOT BRIDGING AREAS)		
<b>TOTAL ON SECTION 3</b>					

Section D: Erosion Control / Storm Drainage					
Item Number	Quantity	Units	Item Description	Unit Price	Cost
163-0300	4	EA	CONSTRUCTION EXIT		
163-0301	1	LS	EROSION CONTROL INSPECTIONS, WEEKLY AND MONTHLY		
	1	LS	TEMPORARY REFUELING AREA		
	1	LS	TEMPORARY CONC. WASHDOWN		
	100	LF	CONSTRUCT, MAINTAIN, & REMOVE 18" FILTER MEDIA SOCK CHECK DAMS		
163-0529	1500	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE NS		
	1900	LF	CONSTRUCT AND REMOVE TEMPORARY SEDIMENT BARRIER, TYPE S		
	60	LF	CONSTRUCT, MAINTAIN, & REMOVE TEMPORARY SEDIMENT BARRIER J-HOOKS		
163-0550A	2	EA	CONSTRUCT AND REMOVE INLET SEDIMENT TRAP, TYPE F		
165-0105	1	LS	MAINTENANCE OF INLET SEDIMENT TRAP		
165-0010	1	LS	MAINTENANCE OF TEMPORARY SEDIMENT BARRIER		
165-0101	1	LS	MAINT OF CONSTRUCTION EXIT		
167-1000	1	LS	WATER QUALITY MONITORING AND SAMPLING		
	2	EA	DROP INLET, INCL MANHOLE, FRAME & GRATE (EJ 1130Z FRAME & 1130 02 GRATE, OR APPROVED EQUAL)		
	2	EA	GADOT 1011A J.B., INCL MANHOLE, RING & COVER		
	1	EA	TIE PROPOSED 24" HDPE TO EXISTING 24" HDPE		
	1	EA	TIE PROPOSED 15" HDPE TO EXISTING 15" HDPE		
	1	EA	GADOT 1034D CB		
	1	EA	REMOVE & RESET EXIST C.I. - HOOD & GRATE		
	1	EA	CORE EXIST. CONC. WALL FOR PROPOSED 18" HDPE		
	11	LF	REMOVE EXIST. 18" CMP		
	1	EA	18" HDPE 45 DEG BEND		
	1	EA	15" FLARED END SECTION		
	1	EA	24" FLARED END SECTION		
	1	EA	15" ENERGY DISSIPATING HEADWALL		
550-1150	300	LF	STORM DRAIN PIPE, 15 IN, HDPE, H 1-10		
550-1180	41	LF	STORM DRAIN PIPE, 18 IN, HDPE, H 1-10		
550-1240	40	LF	STORM DRAIN PIPE, 24 IN, HDPE, H 1-10		

603-1012	74	SY	ROCK RIPRAP, GADOT TYPE 3 EQUIVALENT RIVER ROCK (12" THICK)		
	150	SY	RAILROAD BALLAST STONE (6" THICK)		
603-2997	80	SY	FILTER BLANKET		
700-6910	1.1	AC	PERMANENT GRASSING		
700-8000	1.1	AC	FERTILIZER MIX GRADE		
716-2000	1000	SY	EROSION CONTROL MATS, SLOPES		

**Section D Sub Total**

**Section E: Allowances**

Item Number	Quantity	Units	Item Description	Unit Price	Cost
700-9900		ALLOW	LANDSCAPE (TREES, PLANTS, +1 YR MAINT)		not in contract- city responsibility
999-1000	1	ALLOW	MISCELLANEOUS CONSTRUCTION	<b>\$100,000.00</b>	<b>\$100,000.00</b>

**Section G Sub Total**

<b>Section A Sub Total</b>	
<b>Section B Sub Total</b>	
<b>Section C Sub Total</b>	
<b>Section D Sub Total</b>	
<b>Section E Sub Total</b>	
<b>TOTAL ESTIMATED CONSTRUCTION COST</b>	

<b>LS</b>	<b>LUMP SUM</b>
<b>SY</b>	<b>SQUARE YARD</b>
<b>CY</b>	<b>CUBIC YARD</b>
<b>LF</b>	<b>LINEAR FOOT</b>
<b>EA</b>	<b>EACH</b>
<b>ALLOW</b>	<b>ALLOWANCE</b>
<b>SF</b>	<b>SQUARE FOOT</b>
<b>GLF</b>	<b>GALLON PER LINEAR FOOT</b>