

GP1362 Cleveland Ave - 2nd St NW  
Pedestrian Signal and Sidewalk Project, Onesto

# Addendum 1

**City of Canton, Ohio**  
Purchasing Department  
218 Cleveland Ave. SW, 4<sup>th</sup> floor  
Canton, Ohio 44702

Cleveland Ave./2nd St. NW Onesto Streetscape Project, GP1362

**Item/Project**

Engineering Department

**Responsible Department**

March 11, 2022 at 2:00PM

**Bids Due On or Before**

## **Bid Proposal Submitted By:**

\_\_\_\_\_  
**Company Name**

\_\_\_\_\_  
**Street Address**

\_\_\_\_\_  
**City**

\_\_\_\_\_  
**State**

\_\_\_\_\_  
**Zip**

\_\_\_\_\_  
**Contact Person**

\_\_\_\_\_  
**Phone No.**

\_\_\_\_\_  
**Email Address**

**GP1362 Cleveland Ave - 2nd St NW  
Pedestrian Signal and Sidewalk Project, Onesto**

**Change of Information:**

Plan Reference #10 Item 690 Special - Misc.-Surfaces restoration/repair, Caulking, etc.  
Reads 0.00 LS. The Bid Quantity should be 1.00 LS, rather than 0.00 as listed in the original bid sheet.

It is the intent that the contractor performs this Item at a Lump Sum cost. A revised bid sheet is attached.

Please replace the bid sheet included in the original Invitation to Bid with the revised bid sheet included herein as Addendum 1.

**GP1362 Cleveland Ave - 2nd St NW  
Pedestrian Signal and Sidewalk Project, Onesto**

BIDDER

We (I), the above signed hereby propose to furnish the following article(s) and/or service(s) at the price(s) and terms stated subject to all instructions, conditions, specifications, and all attachments hereto. We (I) have read all attachments including the specifications and fully understand what is required.

REF	ITEM	DESCRIPTION	QTY	UNIT	Labor Unit Cost	Material Unit Cost	UNIT COST	COST
1	252	Sawcut Existing Walk/Road	315.00	LF				
2	202	Remove Existing Walk	3700.00	SF				
3	202	Remove Road Pvmnt (Full Depth), As Per Plan	142.00	SY				
4	202	Remove Existing Curb	330.00	LF				
5	304	Aggregate Base 4" (Curb, Walk, Approaches)	90.00	CY				
6	608	Curb Ramp, Type A1	225.00	SF				
7	608	ADA Ramp Installation	3.00	EA				
8	608	5" Concrete Walk	4875.00	SF				
9	609	Canton Type 1 Curb, As Per Plan	350.00	LF				
10	690	Special - Misc.-Surfaces restoration/repair, Caulking, etc.	1.00	LS				
11	690	Special - Brick Walkway Pavers	390.00	SF				
12		Roof Drains, As Per Plan	60.00	LF				
13	625	6' x 30" concrete foundation including 1" x 10' Ground Rod per City specs.	3.00	EA				
14	625	4" PVC Schedule 40 Conduit Lighting	45.00	FT				
15	625	2" PVC Schedule 40 Conduit Lighting	345.00	FT				
16	625	3" PVC Schedule 40 Conduit Traffic Signal interconnect.	325.00	FT				
17	SPECIAL	Union Metal 18' Twin Canton Decorative Streetlight Pole with LED's furnished and installed by City. Contractor to provide & install Bussmann Type II Fused connector kits (HEB-AW-RYC) 3 per pole, Bussmann Type III Solid link connector kit (HET-AW-RYC) 1 per	3.00	EA				
18	625	17" x 30" composite pull box tier 15, labeled Electric.	4.00	EA				

19	625	AWG # 6 XHHW Stranded copper, no underground splices.	1685.00	FT					
20	625	Trench 18" Deep- additional trenching will be in area where conduit not placed in trench for curb.	78.00	FT					
21	SPECIAL	Remove AEP steel pole, and return steel pole to AEP yard.	3.00	EA					
22	611	Catch Basin, Adjust to Grade / 1 ft Concrete Apron	1.00	EA					
23	614	Maintaining Traffic	1.00	LS					
								<b>TOTAL</b>	

**Base Bid Price in Figures** \_\_\_\_\_

**Base Bid Price in Words** \_\_\_\_\_

**Base Bid Prices are for Informational Purposes Only.  
Total Unit Prices will govern.**