



PURCHASING DIVISION

901 Broadway, N.E. • Knoxville, TN 37917-6699
 865.403.1133 • Fax 865.594.8858
 800.848.0298 (Tennessee Relay Center)
 Email: purchasing@kcdc.org
<http://www.kcdc.org/en/DoingBusiness.aspx>

Addendum

SOLICITATION NAME	Demolition Services at 1729 Minnesota Avenue Q1520	ADDENDUM NUMBER	1	DATE	01-30-15
--------------------------	--	------------------------	---	-------------	----------

KCDC is using this addendum to answer the questions raised about this solicitation. To aid in readability, the questions are in black, the answers are in bold, and the answers follow immediately below.

Q1	Does the fence remain or go?
	Under the scope of work, paragraph 5(c) Concrete Slabs is amended to read as follows: The vendor shall remove all concrete slabs, asphalt, surface obstructions, masonry slabs, and appurtenances, including but not limited to (1) the sidewalk between the street and the front door, (2) driveway between the street (at cut line) and the carport slab, and (3) storage shed and slab. See photos for details. All posts for support shall be pulled out or dug up so as to be entirely removed.
Q2	Does the concrete driveway/sidewalk/carport area remain or go?
	It is to be removed (see Scope of Work, paragraph 5(c)).
Q3	Has the mastic under the floor been checked for asbestos?
	Yes (see the bulk samples analysis table in the Helton & Associates report).
Q4	Does the shed in the back, made of block, remain or go?
	Remove (see Scope of Work, paragraph 5(c)).

