

Paul Schwindler, P.E., CPWM  
Director/County Engineer  
[Paul-schwindler@peachcounty.net](mailto:Paul-schwindler@peachcounty.net)

Rebecca L. Cox, EIT, CFM  
Stormwater Manager  
[Becky-cox@peachcounty.net](mailto:Becky-cox@peachcounty.net)



Wayne Smith  
Road Superintendent  
[Wayne-smith@peachcounty.net](mailto:Wayne-smith@peachcounty.net)

Conny Soto  
Office Manager  
[Conny-soto@peachcounty.net](mailto:Conny-soto@peachcounty.net)

## Public Works

410 Old Macon Road  
Fort Valley, Georgia 31030  
Phone 478-825-8717  
Fax 478-825-2684

# REQUEST FOR BID No. RFB 18-034 Addendum No. 2 September 20, 2018

## PEACH COUNTY GEORGIA *Southwest Sanitary Sewer Phase I Road Patching and Asphalt Overlay*

---

**PURPOSE:** The purpose of this addendum is to address written questions.

### ADDENDUM 2:

#### **Address Questions and Requests for information:**

1. **Question:** It appears that the manholes are presently up about an inch onsite. What kind of adjustment are you looking for with pay item 3, Adjust Manhole - 41 each?

**Answer:** *The paving requirement is for 138 lb. / SY of 9.5mm Superpave Hot Mix Asphalt. This represents a thickness of approximately 1.25 in. The manholes were originally set at 7/8 in. above the original surface of the road. This would equate to a 3/8-inch adjustment. Due to such a small adjustment, section 1.03.5 of the specifications shall be deleted and disregarded. bidders shall also disregard Item 3 "Adjust Manhole" – 41 each on the Schedule of Unit Prices.*