
SHEET INDEX

SHEET NO.	DESCRIPTION	SHEET TOTALS
1	TITLE SHEET	1
2	SUMMARY OF QUANTITIES	1
3	GENERAL NOTES	1
OVERALL DF	RAINAGE PLANS	
4	DRAINAGE ALIGNMENT SHEET	1
5A-5C	DRAINAGE IMPROVEMENT PLANS	3
6	FRP WALL PLAN & PROFILE	1
7	HEADWALL DETAILS	1
8	CONSTRUCTION DETAILS	1
9	USCOE PROJECT LIMITS SHEET	1
		TOTAL 11

CITY OF BEAUFORT



MOSSY OAKS DRAINAGE IMPROVEMENT PLANS BASIN 2 = WEST



- PROJECT AREA

SC BEAUFORT

RECORD OF THE RESPONSIBILITY TO DESIGN THIS PROJ

Designs may be obtained from the SCDOT Regional Production Group

For Right Of Way Acquisition: Date Consultant Engineer of Record

Hydraulic Design Reference for these plans is the: 2009

Edition of SCDOT's "Requirements for Hydraulic Design Studies"

Design Reference for these plans is the:

3F

These Plans Were Designed Using "3R" Principles From the 2017 Roadway Design Manual

ENVIRONMENTA	L PERMIT INF	ORMATION	
USACE PERMIT	YES	NO	
NEPA DOCUMENT	YES	NO	
401 CERTIFICATION	YES	NO	
OCRM CAP	YES	NO	
NAVIGABLE WATERSSC	USCG	USACE	N/A

3 DAYS BEFORE DIGGING IN SOUTH CAROLINA

CALL 811

SOUTH CAROLINA 811 (SC811)

WWW.SC811.COM

ALL UTILITIES MAY NOT BE A MEMBER OF SC811

RAILROAD INVOLVEMENT? YES /NO

LAYOUT N.T.S.

	BATTERY CREEK ROAD	TOTAL (MILES)
NET LENGTH OF ROADWAY	0.15	0.15
NET LENGTH OF BRIDGES	_	_
NET LENGTH OF PROJECT	0.15	0.15
LENGTH OF EXCEPTIONS	_	_
GROSS LENGTH OF PROJECT	0.15	0.15

EQUALITIES IN STATIONING:

NOTE: EXCEPT AS MAY OTHERWISE BE SPECIFIED ON THE PLANS OR IN THE SPECIAL PROVISIONS, ALL MATERIALS AND WORKMANSHIP ON THIS PROJECT SHALL TO CONFORM WITH SOUTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION) AND STANDARD DRAWINGS FOR ROAD CONSTRUCTION IN EFFECT AT THE TIME OF LETTING.

CONSULTING ENGINEERING FIRM

JEINFRASTRUCTURE CONSULTING & ENGINEERING

ENGINEER OF RECORD

ISSUED FOR BID

FOR CONSTRUCTION :

DATE

STATE	COUNTY	FILE NO.	PROJECT NO.	ROUTE NO.	SHEET NO.
SC	BEAUFORT			S-7-159	2

SUMMARY OF ESTIMATED QUANTITIES

PAY ITEM	DESCRIPTION	QUANTITY	UNIT
1031000	MOBILIZATION	1	LS
1032010	BONDS AND INSURANCE	1	LS
1050800	CONSTRUCTION STAKES, LINES & GRADES	1	EA
1071000	TRAFFIC CONTROL	1	LS
1090200	AS-BUILT CONSTRUCTION PLANS	1	LS
2012000	CLEARING & GRUBBING WITHIN ROADWAY	1	LS
2023000	REMOVAL & DISPOSAL OF EXISTING PAVEMENT	33.1	SY
2031200	SITE EXCAVATION	1	LS
2027000	REMOVAL & DISPOSAL OF EXISTING CONCRETE	44.0	СҮ
3100310	HOT MIX ASPHALT BASE COURSE - TYPE B	43	TON
4013990	MILLING EXISTING ASPHALT PAVEMENT (VARIABLE)	221.9	SY
4020320	HOT MIX ASPHALT INTERMEDIATE COURSE TYPE B	205	TON
4030320	HOT MIX ASPHALT SURFACE COURSE TYPE C	161	TON
6020005	PERMANENT CONSTRUCTION SIGNS (GROUND MOUNTED)	76	SF
7143615	15" SMOOTH WALL PIPE	28	LF
7143618	18" SMOOTH WALL PIPE	198	LF
7143660	60" SMOOTH WALL PIPE	100	LF
7204100	CONCRETE SIDEWALK (4" UNIFORM)	440	SY
8041020	RIP-RAP (CLASS B)	38	TON
8048200	GEOTEXTILE FOR EROSION CONTROL UNDER RIPRAP(CLASS 2)TYPE A	33	SY
8100100	PERMANENT COVER	0.50	ACRE
8100200	TEMPORARY COVER	0.25	ACRE
8104005	FERTILIZER (NITROGEN)	50	LB
8104010	FERTILIZER (PHOSPHORIC ACID)	50	LB
8104015	FERTILIZER (POTASH)	50	LB
8105005	AGRICULTURAL GRANULAR LIME	1004	LB
8109901	MOWING	2	ACRE
8153000	SILT FENCE	1056	LF
8153090	REPLACE/REPAIR SILT FENCE	106	LF
8154050	REMOVAL OF SILT RETAINED BY SILT FENCE	264	LF





4						BEAUFOR ⁻	Γ COUNTY
3						CITY OF E	BEAUFORT
2							
1						MOSSY	OAKS
REV. NO.	BY	DATE	DESCRIPTION	OF REVISION		BASIN 2	- WEST
DESIGNE	D BY: RNT		DATE <u>01/17/2020</u>			SUMMARY OF ESTI	MATED QUANTITIES
DRAWN	BY: RNT		DATE <u>01/17/2020</u>				
CHECKED	D BY: <u>JCH</u>		DATE <u>01/17/2020</u>		SHEET	2	SCALE: NTS

STATE COUNTY FILE NO. PROJECT ROUTE SHEET NO. SC BEAUFORT S-7-159 3

GENERAL NOTES

GENERAL CONSTRUCTION NOTES:

SEE INDIVIDUAL CURVES ON REFERENCE DATA SHEET FOR SUPERELEVATION RATE AND DESIGN SPEED, AS APPLICABLE.

THE LOCATIONS OF EXISTING UTILITIES SHOWN ON THE PLANS HAVE BEEN DETERMINED FROM AVAILABLE INFORMATION AND ARE PROVIDED FOR THE CONVENIENCE OF THE CONTRACTOR. THE ENGINEER ASSUMES NO RESPONSIBILITY FOR THE ACCURACY OR COMPLETENESS OF THE UTILITIES INFORMATION SHOWN ON THE DRAWINGS. IT IS THEREFORE THE CONTRACTOR'S RESPONSIBILITY TO CONFIRM THAT THE PROPER COORDINATION WITH THE VARIOUS UTILITY OWNERS HAS BEEN PERFORMED.

THE CONTRACTOR SHALL COOPERATE WITH THE UTILITY OWNERS DURING RELOCATION OPERATIONS. THE CONTRACTOR SHALL EXERCISE CAUTION WHEN CROSSING AN UNDERGROUND UTILITY WHETHER SHOWN ON THE DRAWINGS OR LOCATED BY THE UTILITY COMPANY. COST OF DAMAGES TO ANY UTILITIES AS A RESULT OF CONSTRUCTION SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.

ALL WORKMANSHIP AND MATERIALS USED ON THIS PROJECT SHALL CONFORM TO THE SCDOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION (2007 EDITION), SCDOT 2007 SUPPLEMENTAL SPECIFICATIONS, SCDOT SUPPLEMENTAL TECHNICAL SPECIFICATIONS IN EFFECT AT THE TIME OF LETTING, AND SCDOT 2009 STANDARD DRAWINGS EXCEPT WHERE OTHERWISE NOTED IN THE PLANS.

ALL EXISTING ROAD SIGNS AFFECTED BY CONSTRUCTION ACTIVITIES SHALL BE RETAINED, RELOCATED, OR REMOVED AS DIRECTED BY ENGINEER. PAYMENT FOR THIS WORK SHALL BE INCLUDED IN THE LUMP SUM COST FOR CLEARING AND GRUBBING.

ALL NEW SIGNS SHALL BE PLACED IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES AND SCDOT STANDARD DRAWINGS. NEW 2P & 3P SIGN SUPPORTS REQUIRED FOR RELOCATED SIGNS WILL BE PAID PER LINEAR FOOT INSTALLED AND ACCEPTED.

THE CONTRACTOR SHALL FURNISH, INSTALL, AND MAINTAIN ALL NECESSARY PROVISIONS FOR TRAFFIC CONTROL FOR THE DURATION OF THE PROJECT. THESE PROVISIONS, AS IN EACH CASE IS APPLICABLE, WILL CONFORM TO THE REQUIREMENTS CONTAINED IN THE SCDOT STANDARD SPECIFICATIONS, STANDARD DRAWINGS, SUPPLEMENTAL SPECIFICATIONS, SPECIAL PROVISIONS, THE FEDERAL HIGHWAY ADMINISTRATION MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES, AND AS DIRECTED BY THE ENGINEER. THE CONTRACTOR SHALL SUBMIT THE TRAFFIC CONTROL PLAN TO THE COUNTY FOR APPROVAL BEFORE BEGINNING CONSTRUCTION.

THE LUMP SUM COST FOR TRAFFIC CONTROL SHALL INCLUDE ALL WORK AS DIRECTED ABOVE. THIS LUMP SUM COST SHALL INCLUDE TEMPORARY CONSTRUCTION SIGNS, BARRICADES, DRUMS, CONES, LIGHTS, AND OTHER ITEMS AS REQUIRED TO COMPLETE THIS WORK.

CONTRACTOR SHALL REFER TO SCDOT STD. DWG. 605-010-02 FOR PLACEMENT OF PERMANENT CONSTRUCTION SIGNS. THIS PROJECT REQUIRES ONE (1) SCHEME C. SIGNS SHALL BE PAID FOR PER SQUARE FOOT INSTALLED AND ACCEPTED UNDER THE BID ITEM FOR PERMANENT CONSTRUCTION SIGNS.

EROSION CONTROL NOTES:

IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.

STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW.

A) WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICAL. B) WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.

ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED ONCE EVERY CALENDAR WEEK. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.

PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.

ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.

THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.

RESIDENTIAL SUBDIVISIONS REQUIRE EROSION CONTROL FEATURES FOR INFRASTRUCTURE AS WELL AS FOR INDIVIDUAL LOT CONSTRUCTION. INDIVIDUAL PROPERTY OWNERS SHALL FOLLOW THESE PLANS DURING CONSTRUCTION OR OBTAIN APPROVAL OF AN INDIVIDUAL PLAN IN ACCORDANCE WITH S.C REG. 72–300 ET SEQ. AND SCR100000.

TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.

ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CANNOT BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.

LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.

A COPY OF THE SWPPP, INSPECTION RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.

INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND-DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.

MINIMIZE SOIL COMPACTION AND UNLESS INFEASIBLE, PRESERVE TOPSOIL.

MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, ANDOTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THATPROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE.

- THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
 WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;
- FUELS, OILS OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND
- MAINTENANCE; AND
 SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.

AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTION MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.

EROSION CONTROL NOTES (CON'T)

IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM WATER EVENT WHENEVER PRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.

A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT AS APPROVED OTHERWISE.

THE CONTRACTOR IS REQUIRED TO IDENTIFY AND MAINTAIN AN ON-SITE CONCRETE WASHDOWN AREA THAT MEETS ALL REQUIREMENTS / BMPS OF SCDHEC. APPROVED WASHOUT AREAS MAY INCLUDE SECTIONS OF SIDEWALK THAT HAVE BEEN FORMED AND THAT ARE LOCATED AHEAD OF THE CURRENT CONCRETE POUR. THE CONTRACTOR WILL BE RESPONSIBLE FOR REMOVAL OF CONCRETE REMNANTS AND PREPARING THE SUBGRADE IN THESE AREAS PRIOR TO PLACEMENT OF THE NEXT DAYS CONCRETE POUR.

SEQUENCE OF CONSTRUCTION

- 1. OBTAIN NPDES COVERAGE FROM DHEC
- 2. NOTIFY SC DHEC REGIONAL OFFICE AND THE CITY OF BEAUFORT DEPARTMENT OF PUBLIC WORKS 48 HOURS PRIOR TO ANY LAND DISTRUBING ACTIVITIES.
- 3. INSTALL TREE PROTECTION AND DELINEATE CLEARING LIMITS.
- 4. CLEARING & GRUBBING ONLY AS NECESSARY FOR INSTALLATION OF PERIMETER CONTROLS (E.G. SILT FENCE).
- 5. INSTALL PERIMETER CONTROLS (E.G. SILT FENCE).
- 6. CLEARING AND GRUBBING OF SITE (SEDIMENT & EROSION CONTROL MEASURES FOR THESE AREAS MUST ALREADY BE INSTALLED.
- 7. WORK ON SPANISH MOSS TRAIL (IE TEMPORARY COFFER DAM, SHEET PILE WALL, REPLACE CULVERTS, HEADWALL, FLAP GATES, RECONSTRUCT PATHWAY)
- 8. CLEAN DITCHES
- 9. INSTALL UPSTREAM STORM DRAINAGE.
- 10. INSTALL COFFER DAM FOR BATTERY CREEK ROAD.
- 11. DETOUR WORK FOR BATTERY CREEK ROAD STORM DRAINAGE CROSSING
- 12. FINE GRADING ON BATTERY CREEK ROAD.
- 13. ASPHALT PAVING.
- 14. CONSTRUCT SIDEWALK.
- 15. FINISH GRADING AND FINAL GRASSING.
- 16. MAINTAIN ALL SEDIMENT AND EROSION CONTROL DEVICES FOR THE EXTENT OF THE PROJECT
- 17. REMOVAL OF SEDIMENT CONTROLS AFTER SITE HAS BEEN STABILIZED.
- 18. CONTACT THE CITY OF BEAUFORT DEPARTMENT OF PUBLIC WORKS FOR FINAL PROJECT INSPECTION.
- 19. FILE NOTICE OF TERMINATION.

JEINFRASTRUCTURE CONSULTING & ENGINEERING

ISSUED FOR BID

 3
 2

 1
 DESIGNED BY: BJL

 DATE
 DESCRIPTION OF REVISION OF REVISION OF REVISION OF REVISION DATE O8/22/20/9

DRAWN BY: BJL
CHECKED BY: JCH

DATE <u>08/22/201</u>

DATE 08/22/20


CITY OF BEAUFORT


MOSSY OAKS


BASIN 2 – WEST GENERAL CONSTRUCTION NOTES


BEAUFORT COUNTY


SHEET 3 SCALE: NTS




















SEDIMENT

STORAGE

3.5'

6.0'

8.5'

11.0'

TYPICAL ROCK DIKE DIMENSIONS

0.5

1.0

1.5

MAXIMUM 2-ACRE DRAINAGE AREA TO DIKE

MAX. DRAINAGE TOTAL STORAGE SEDIMENT STORAGE (ACRES) VOL. (CU. FT.) VOLUME (CU. FT.)

529

1257

1259

1946

2790

3790

ROCK SEDIMENT DIKE

DOWNSTREAM SIDE


NON-WOVEN GEOTEXTILE FABRIC-


#5 WASHED STONE ON UPSTREAM FACE OF DIKE


----FLOW


MIN 9" D50 RIP-RAP-


----Bo ---











CROSS SECTION A-A THRU STONE DITCH CHECK **ROCK DITCH CHECK**

3. THE BODY OF A ROCK SEDIMENT DIKE SHALL BE COMPOSED OF 9-INCH D50 RIP-RAP AT A MINIMUM.

4. THE UPSTREAM FACE OF THE ROCK SEDIMENT DIKE SHALL BE COMPOSED OF A 1-FOOT THICK LAYER OF 3/4-INCH TO 1-INCH D50 WASHED STONE PLACED AT A SLOPE OF 2H:1V.

3. THE ROCK MUST BE PLACED BY HAND OR MECHANICAL PLACEMENT (NO DUMPING OF ROCK TO FORM

7. A SEDIMENT SUMP SHALL BE LOCATED ON THE UPSTREAM SIDE OF THE STRUCTURE TO PROVIDE SEDIMENT STORAGE. THE UPSTREAM SIDE OF THE SUMP SHALL HAVE A SLOPE OF 5H:1V TO INHIBIT EROSION OF THE SEDIMENT STORAGE AREA. THE MINIMUM DEPTH OF THE SUMP SHALL BE 2-FEET.

ATTENTION TO SEDIMENT ACCUMULATIONS WITHIN THE ROCK SEDIMENT DIKE IS EXTREMELY IMPORTANT. ACCUMULATED SEDIMENT DEPOSITION SHOULD BE CONTINUALLY MONITORED IN THE TRAP

. REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 50% OF THE DESIGNED SEDIMENT STORAGE VOLUME AS MARKED BY THE CLEAN-OUT STAKE.

3. REMOVED SEDIMENT FROM THE ROCK SEDIMENT DIKE SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS THE DISTURBED AREA. STABILIZE THE REMOVED SEDIMENT AFTER IT IS RELOCATED.

REGULAR INSPECTIONS OF ROCK SEDIMENT DIKES SHOULD BE CONDUCTED ONCE EVERY CALENDAR WEEK AND, AS RECOMMENDED, WITHIN 24-HOURS AFTER EACH RAINFALL EVENT THAT PRODUCES

5. ALL ROCK SEDIMENT DIKES SHOULD BE REMOVED WITHIN 30 DAYS AFTER FINAL STABILIZATION IS ACHIEVED. DISPOSE OF ALL CONSTRUCTION MATERIALS APPROPRIATELY. DISTURBED AREA RESULTING FROM REMOVAL SHALL BE PERMANENTLY STABILIZED.

8. MARK THE SEDIMENT CLEAN-OUT LEVEL OF THE SEDIMENT DIKE WITH A STAKE IN THE FIELD.

5. ROCK SEDIMENT DIKES SHALL HAVE A MINIMUM TOP FLOW LENGTH OF 3-FEET (2-FOOT FLOW


THE SEDIMENT DIKE) TO ACHIEVE PROPER DIMENSIONS.


9. SEED AND MULCH ALL DISTURBED AREAS.

INSPECTION AND MAINTENANCE

LENGTH THROUGH THE RIP-RAP AND 1-FOOT FLOW LENGTH THROUGH THE WASHED STONE).


4. REMOVED SEDIMENT SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS DISTURBED AREA. STABILIZE THE REMOVED SEDIMENT AFTER IT IS RELOCATED. RUNOFF BYPASSING THE INSTALLED CHECK. IF EVIDENT REPAIR PROMPTLY AS NECESSARY TO PREVENT EROSION AND BYPASSING. 6. IN THE CASE OF GRASS-LINED DITCHES, CHANNELS, AND SWALES, ROCK DITCH CHECKS SHOULD BE REMOVED WHEN THE GRASS HAS MATURED SUFFICIENTLY TO PROTECT THE DITCH OR SWALE UNLESS THE SLOPE OF THE 7. AFTER CONSTRUCTION IS COMPLETED AND FINAL STABILIZATION IS REACHED, THE ENTIRETY OF THE ROCK DITCH CHECK SHOULD BE REMOVED IF VEGETATION WILL BE USED FOR PERMANENT EROSION CONTROL MEASURES. THE AREA BENEATH THE REMOVED ROCK DITCH CHECK MUST BE ADDRESSED WITH PERMANENT STABILIZATION MEASURES. POST INSTALLATION DETAIL -SEDIMENT FILTER/SCREEN _____






Browntop Mille Rye, Grain Ryegrass Well drained, clayey/loamey Sites Japanese Mille Rye, Grain or Ryegrass

Permanent Seeding - Coastal Lbs/Ac Jan Feb Mar Apr May Jun Jul Aug Sep Oct Nov Dec Sandy, Droughty Sites Well drained, clayey/loamey Sites 40 lbs./ac lbs./ac 0 lbs./a



TYPE A - FILTER FABIC INLET PROTECTION



8" MIN -

FILTER FABRIC

BURIAL DETAIL

BURY & TRENCH MIN_ OF 12" FILTER FABRIC

1. SILT FENCE POSTS MUST BE 48-INCH LONG STEEL POSTS THAT MEET, AT A MINIMUM, THE FOLLOWING PHYSICAL CHARACTERISTICS.

2. COMPOSED OF A HIGH STRENGTH STEEL WITH A MINIMUM YIELD STRENGTH OF 50,000 PSI.

3. INCLUDE A STANDARD "T" SECTION WITH A NOMINAL FACE WIDTH OF 1.38-INCHES AND A NOMINAL "T" LENGTH OF 1.48-INCHES.

4. WEIGH 1.25 POUNDS PER FOOT (± 8%) 2. POSTS SHALL BE EQUIPPED WITH PROJECTIONS TO AID IN FASTENING OF FILTER FABRIC.

 INSTALL POSTS TO A MINIMUM OF 24—INCHES, A MINIMUM HEIGHT OF 1— TO 2— INCHES ABOVE THE FABRIC SHALL BE MAINTAINED, AND A MAXIMUM HEIGHT OF 3 FEET SHALL BE MAINTAINED ABOVE THE GROUND. 4. POST SPACING SHALL BE AT A MAXIMUM OF 3-FEET ON CENTER.

FILTER FABRIC REQUIREMENTS INSTALLATION DETAIL

1. SILT FENCE MUST BE COMPOSED OF WOVEN GEOTEXTILE FILTER FABRIC THAT CONSISTS OF THE FOLLOWING REQUIREMENTS:

- COMPOSED OF FIBERS CONSISTING OF LONG CHAIN SYNTHETIC POLYMERS OF AT LEAST 85% BY WEIGHT OF POLYOLEPINS, POLYESTERS, OR POLYAMIDES THAT ARE FORMED INTO A NETWORK SUCH THAT THE FILAMENTS OR YARNS RETAIN DIMENSIONAL STABILITY RELATIVE TO EACH OTHER;

- FREE OF ANY TREATMENT OR COATING WHICH MIGHT ADVERSELY ALTER ITS PHYSICAL PROPERTIES AFTER INSTALLATION; FREE OF ANY DEFECTS OR FLAWS THAT SIGNIFICANTLY AFFECT ITS PHYSICAL AND/OR FILTERING PROPERTIES; AND,

HAVE A MINIMUM WIDTH OF 38—INCHES. USE ONLY FABRIC APPEARING ON SC DOT'S QUALIFIED PRODUCTS LISTING (QPL), APPROVAL SHEET #34, MEETING THE REQUIREMENTS OF THE MOST CURRENT EDITION OF THE SC DOT STANDARD SPECIFICATIONS FOR HIGHWAY CONSTRUCTION.

3. 12-INCHES OF THE FABRIC SHOULD BE PLACED WITHIN EXCAVATED TRENCH AND TOED IN WHEN THE TRENCH IS BACKFILLED. 4. FILTER FABRIC SHALL BE PURCHASED IN CONTINUOUS ROLLS AND CUT TO THE LENGTH OF THE BARRIER TO AVOID JOINTS 5. FILTER FABRIC SHALL BE INSTALLED AT A MINIMUM OF 24-INCHES ABOVE THE GROUND.


 REGULAR INSPECTIONS OF INLET PROTECTION SHALL BE CONDUCTED ONCE EVERY CALENDAR WEEK AND, AS RECOMMENDED, WITHIN 24-HOURS AFTER EACH RAINFALL EVEN THAT PRODUCES 1/2-INCH OR MORE OF PRECIPITATION. ATTENTION TO SEDIMENT ACCUMULATIONS ALONG THE FILTER FABRIC IS EXTREMELY IMPORTANT. ACCUMULATED SEDIMENT SHOULD BE CONTINUALLY MONITORED AND REMOVED WHEN NECESSARY.

REMOVE ACCUMULATED SEDIMENT WHEN IT REACHES 1/3 THE HEIGHT OF THE FILTER FABRIC. WHEN A SUMP IS INSTALLED IN FRONT OF THE FABRIC, SEDIMENT SHOULD BE REMOVED WHEN IT FILLS APPROXIMATELY 1/3 THE DEPTH OF THE SUMP. REMOVED SEDIMENT SHALL BE PLACED IN STOCKPILE STORAGE AREAS OR SPREAD THINLY ACROSS DISTURBED AREA. STABILIZE THE REMOVED SEDIMENT AFTER IT IS RELOCATED. CHECK FOR AREAS WHERE STORMWATER RUNOFF HAS ERODED A CHANNEL BENEATH THE FILTER FABRIC, OR WHERE THE FABRIC HAS SAGGED OR COLLAPSED DUE TO RUNOFF OVERTOPPING THE INLET PROTECTION

7. INLET PROTECTION STRUCTURES SHOULD BE REMOVED AFTER ALL THE DISTURBED AREAS ARE PERMANENTLY STABILIZED. REMOVE ALL CONSTRUCTION MATERIAL AND SEDIMENT, AND DISPOSE OF THEM PROPERLY. GRADE THE DISTURBED AREA TO THE ELEVATION OF THE DROP INLET STRUCTURE CREST. STABILIZE ALL BARE AREAS IMMEDIATELY.

(SEE DETAIL)

N.T.S.



REPRODUCTION OF THESE PLANS OR THEIR CONTENT IS STRICTLY PROHIBITED WITHOUT PRIOR WRITTEN CONSENT.

ALL WORK WITHIN THE SCDOT R/W SHALL CONFORM TO THE MOST CURRENT


EDITION OF SCDOT STANDARD DRAWINGS.THIS INCLUDES, BUT IS NOT LIMITED TO,

TEMPORARY CONSTRUCTION ENTRANCES, PAVEMENT, PAVEMENT MARKINGS, SIGNS

REFERENCE:

AND DRAINAGE STRUCTURES. IF DETAILS VARY FROM SCDOT STANDARD DRAWINGS, SCDOT STANDARD DRAWINGS SHALL BE ADHERED TO. THE FOLLOWING SCDOT STANDARD DRAWING NUMBERS ARE PROVIDED FOR

625-305-00: STANDARD MARKINGS FOR INTERSECTIONS 719-305-00: RECTANGULAR PRECAST SOLID WALL BOX 719-315-00: RECTANGULAR PRECAST RISER 719-330-00: RECTANGULAR JUNCTION BOX TOPS 719-605-00: END TREATMENT (STRAIGHT HEADWALL FOR CIRCULAR PIPE) 719-610-00: END TREATMENT (RCP BEVELED END) 720-150-01: CURB & GUTTER (CONCRETE) 720-150-02: CURB & GUTTER (CONCRETE) TRANSITION CURBS AND 3" CURB & GUTTER 815-001-01: TYPE A INLET STRUCTURE FILTERS 815-105-00: DITCH CHECK 815-205-00: SEDIMENT TUBE DITCH APPLICATION 815-605-00: TEMPORARY SILT FENCE 815-805-00: FLOATING TURBIDITY CURTAIN



TYPICAL STORM SEWER PIPE BEDDING DETAIL

SEDIMENT BAG SPECIFICATIONS

Materials

NOTES:

1. UTILIZE CORRECT ANCHOR
PATTERN FOR SLOPE GRADIENT
2. INSTALL LANDLOCK OR
PYRAMAT TURF REINFORCEMENT

MAT (OR EQUAL) AND SOIL FILL

STORM SEWER 7

PLAN VIEW

<1% GRADE

PROFILE VIEW

OR CONCRETE RUBBLE

LBS./CU. FT. MIN. STONE SIZE 50 LBS.

SAND AND GRAVEL OR MIRAFI ENGINEERED FABRIC. MAX. SIZE = 3

RIP-RAP OUTLET PROTECTION

DUMPED RIP-RAP

2.5 ANCHORS/m² (2 ANCHORS/YD²)

WOODEN OR PLASTIC STAKES CAN BE USED TO ANCHOR TRMS TO THE

ANCHORS (PER

ANCHOR PATTERN

OR 3H:1V<SLOPES<2H:1V 2. U-SHAPED WIRE STAPLES, METAL GEOTEXTILE PINS, TRIANGULAR

bag. Use Dewatering Bags sewn with high strength double stitched seams. Use Dewatering Bags that have a sewn-in sleeve to receive the pump discharge hose.

LANDLOK OR PYRAMAT

SEE SCDOT STD DRAWING 804-805-03

DEFINED CHANNELS
THE BOTTOM AND
SIDE SLOPES OF THE
CHANNEL SHALL BE
PROTECTED WITH
RIP—RAP FOR THE

ENTIRE LENGTH OF LOUDNER THE MAXIMUM TAILWATER CONDITION

FILTER FABRIC

Table 1: Dewatering Bag Required Properties

TURF REINFORCEMENT MAT

Property	Test Method	Type II Value
Weight (oz/yd²) (typical)	ASTM D5261	10 oz
Grab Tensile Strength (MD)	ASTM D4632	250 lbs
Mullen Burst	ASTM D3786	350 psi
UV Resistance	ASTM D4355	70% @ 500 hrs
Flow Rate (Gal/Min/Ft ²)	ASTM D4491	70
Filtering Efficiency	ASTM D5141	80%
All properties are minimum average roll va	ilues (MARV).	

Quality Assurance

At the time of delivery, provide the Engineer with the Dewatering Bag packing list containing complete identification, including but not limited to the following:

- Manufacturer's name and location.
- Manufacturer's telephone number and fax number.
- Manufacturer's e-mail address and web address. Dewatering Bag name, model, and/or serial number.
- Dewatering Bag dimensions
- Certification that the Dewatering Bag meets the physical and performance criteria of this specification.

Use the following steps to select an appropriately sized Dewatering Bag. Consult with the Engineer to select Dewatering Bag size if insufficient information is known about the site conditions.

- 1. Determine the peak flow rate generated from the dewatering pump in gallons per minute
- 2. Determine the peak flow rate through the Dewatering Bag in gallons per minute based on the Dewatering Bag peak flow rate and the total surface area provided by the manufacturer.
- 3. Select a Dewatering Bag that passes a minimum of two times the peak flow rate generated from the dewatering pump as determined in Step 1 to account for a 50% clogging factor.

Dewatering Bag Installation

Use Dewatering Bags composed of a UV resistant, non-woven geotextile sewn into a completely enclosed Install the Dewatering Bag on a mild slope to ensure incoming water flows downhill through the Dewatering Bag. Secure the hose to bag connection using a heavy duty pipe clamp, rope, or other suitable means to prevent leakage. When using a rope to attach the pump hose to the Dewatering Bag, make a minimum of 6 wraps around the hose over a 6-inch width of the bag and fasten with a secure rope knot.

> The bottom area of Dewatering Bags will not allow flow to pass through when the bag is placed on a lowpermeable or impermeable surface. Place the Dewatering Bag on an aggregate, hay bales, or other highly permeable surface to maximize water flow through the entire surface area of the bag. Monitor the Dewatering Bag at all times while the pump is running. While monitoring, ensure the hose to bag cMonnection is secure with only minimal leaking. Check for flow permeating from the bottom surface of the Dewatering Bag. If flow appears restricted, move bag to a surface with higher permeability.

Use the following guidelines and any specific guidelines provided by the manufacturer for Dewatering Bag

- Transport and place Dewatering Bags with care to prevent ripping or tearing the fabric.
- Avoid installing on steep slopes as the bag may roll, causing failure. . Insert the discharge hose a minimum of 1-foot inside the Dewatering Bag
- Do not insert more than one discharge hose into the Dewatering Bag.

Avoid use of excessive flow rates or overfilling the Dewatering Bag. This may cause the bag to rupture or cause failure to the hose to bag connection.

Pump runoff to an excavated trench to provide short term detainment in order to trap large sediment particles. Construct a well compacted level berm downstream of the trench. Pumped runoff overtops the compacted berm and sheet flow across a vegetated filtering area before entering a stormwater conveyance system or detainment structure. Use a hose connection as shown in the Dewatering by Pumping detail in place of the compacted trench and level berm as a means to disperse inflows.

Dispose of the Dewatering Bag as directed by the Engineer. If allowed, the Dewatering Bag may be cut open and the contents seeded after removing the fabric. Securely tie off the pump hose connection sleeve when transporting full Dewatering Bags for disposal. Do not clean and reuse a Dewatering Bag after the voids are clogged with trapped sediment.

Inspection and Maintenance

Dewater by Pumping

Follow all manufacturer recommendations for inspection and maintenance guidelines. Replace Dewatering Bags when trapped sediment has accumulated to 50% of the bag capacity or in accordance with the

Dewatering Bags are full when they no longer efficiently filter sediment or pass water at a reasonable rate. Incoming flow rates will vary depending on the size of the Dewatering Bag, the type and amount of sediment discharged into the Dewatering Bag, the permeability of the underlying aggregate, and the degree of slope on which the bag lies.

JEINFRASTRUCTURE CONSULTING & ENGINEERING

ISSUED FOR BID

4				
3				
2				
1				
REV. NO.	BY	DATE	DESCRIPTION OF REVISION	_
DESIGNED BY: M. HAMMOND			DATE <u>07/11/2019</u>	
DRAWN BY: L. WILEN			DATE <u>04/10/2020</u>	

DATE <u>04/10/2020</u>

CHECKED BY: A. KLOSTERMAN

CITY OF BEAUFORT

MOSSY OAKS BASIN 2 - WEST CONSTRUCTION DETAILS

BEAUFORT COUNTY

© 2020

SHEET 8 SCALE: NOT TO SCALE

