

CITY OF GRIFFIN  
SHOAL CREEK NEW HEADWORKS AND PUMP STATION

FROM: PARAGON CONSULTING GROUP, INC.  
118 NORTH EXPRESSWAY  
GRIFFIN, GA 30223

TO: ALL BIDDERS OF RECORD

RE: Addendum No. 4, dated September 18, 2018

This Addendum forms a part of the Contract Documents and modifies the original Bidding Documents dated August 2018.

This Addendum consists of two (2) pages, three (3) plan sheets, and one (1) supplemental drawing.

CONTRACT DOCUMENTS AND SPECIFICATIONS

- Add. 4.1 Modification: Revised Plan Sheet C5 SITE PLAN is included with this Addendum and becomes a part of the Contract Documents. The change to the plan sheet is indicated with a revision cloud and detailed in the plan revision block.
- Add. 4.2 Modification: Revised Plan Sheet C11 DRYING BEDS DETAILED GRADING PLAN is included with this Addendum and becomes a part of the Contract Documents. The change to the plan sheet is indicated with a revision cloud and detailed in the plan revision block.
- Add. 4.3 Modification: Revised Plan Sheet C15 GRAVITY EFFLUENT PROFILE is included with this Addendum and becomes a part of the Contract Documents. The change to the plan sheet is indicated with a revision cloud and detailed in the plan revision block.
- Add. 4.4 Modification: Supplemental Drawing SD5 is included with this Addendum and becomes a part of the Contract Documents. This drawing serves as a detail for the decanter lift station shown on Plan Sheet C19 associated with the Sludge Settling Basin pond. The lift station requires only a single pump. The pump requirements are detailed in Specification Section 02532 PLANT INFLUENT LIFT STATION.
- Add. 4.5 Clarification: The pipe material for Sanitary Sewer Line H shall be 8-inch Class 350 ductile iron pipe as indicated on the revised plan and profile sheets. The lateral associated with Sanitary Sewer Line H shall be 6-inch SDR 26.
- Add. 4.6 Clarification: The Clarification in Addendum #1 stating the Storage Building had been removed as an Alternate from the Bid Form is an error. The Contractor should provide pricing for the Storage Building as an Additive Alternate as shown on the revised Bid Form included with Addendum #2.

- Add. 4.7 Clarification: The Contractor is not required to install geotextile fabric under the Sludge Settling Basin pond liner.
- Add. 4.8 Clarification: It is permissible for the Contractor to use the fabricator of their choosing for the floating baffle wall as long as the specified baffle material is used during fabrication.
- Add. 4.9 Clarification: An emergency generator from any of the manufacturers referenced in the specifications is acceptable if the proposed generator meets the minimum requirements indicated. Final review and approval of the emergency generator will occur during the submittal process after the project is awarded.
- Add. 4.10 Clarification: VFDs manufactured by Danfoss, Square D, or ABB are acceptable as long as the proposed VFDs meet the minimum requirements indicated in the specifications. Final review and approval of the VFDs will occur during the submittal process after the project is awarded.
- Add. 4.11 Clarification: The Contractor shall provide plug valves for Pond Bypass Valves BP-1 and BP-2 as indicated on the valve schedule included with Addendum #1. The reference to these valves being gate valves on Plan Sheet C16 is an error.
- Add. 4.12 Clarification: The valves designated as SBPP-1 and SBPP-2 are shown on Plan Sheet C16 on the twin 18-inch pipes between the Sludge Settling Basin and Polishing Pond No. 1. The Contractor shall provide plug valves for SBPP-1 and SBPP-2 as indicated on the valve schedule included with Addendum #1. The reference to these valves being gate valves on Plan Sheet 16 is an error.
- Add. 4.13 Clarification: Although land application of the existing sludge removed during the project is permissible, as stated in the SLUDGE REMOVAL DESCRIPTION attached to Addendum #2, the City of Griffin's current permitted land application sites will **not** be available to any sludge removal subcontractor for disposal of the sludge.
- Add. 4.14 Clarification: The Contractor will not be responsible for off-site hauling of any soils export generated from grading the project site. The Owner will designate an area on the property for the disposal of excess soils.

**End of Addendum No. 4**