



Terry McKee, IT & Procurement Director

901 N. Broadway • Knoxville, TN 37917-6699
 865.403.1133 • Fax 865.594.8858
 purchasinginfo@kcdc.org
 www.kcdc.org

Addendum

Solicitation Name	Infrastructure Work for the former Austin Homes site C20006	Addendum Number	2	Date	03/06/2020
--------------------------	---	------------------------	---	-------------	------------

This addendum answers questions raised about this solicitation. To aid in readability, the questions are in black, the answers are in **bolded blue**, and the answers follow immediately below.

Q1	Are we still expecting electrical and landscaping documents that will need to be added to the scope?
	Site electrical and landscaping will not be included in this bid package.
Q2	Is the allowance of 184,000 CY of imported engineered fill to allow for the import and compaction of this soil?
	The 184,000 cubic yards of engineered fill is the in-place compacted quantity. Refer to Addendum 1 for revised import quantity.
Q3	Will the quantification of soil undercut be calculated from excavated cross sections of the cut area by the geotechnical engineer or by loads hauled to the site?
	Undercut quantities will be calculated from the excavated cross section of the cut area by the geotechnical engineer.
Q4	The alternate is calling for a retaining wall to be shown on the landscaping plans. Since there will be no landscaping plans at the time of the bid, are we to include anything for this wall?
	No

