


- NOTES:**
1. ALL FOUNDATIONS SHALL BE DRILLED PIERS TO AVOID DISTURBING SURROUNDING SOIL. A TEMPORARY STEEL CASING MAY BE REQUIRED. IF UTILITIES OR ANOTHER CONFLICT IS IN CLOSE PROXIMITY TO THE FOUNDATION, THEN THOSE FOUNDATIONS MAY HAVE TO BE EXCAVATED BY HAND.
 2. PRE-CAST LIGHT POLE FOUNDATIONS, 30" X 72", WILL BE PERMITTED AT LOCATIONS WHERE THERE ARE NO CONFLICTS OR UTILITIES PROHIBITING PLACEMENT.
 3. ANCHOR BOLT PATTERN SHALL BE PROVIDED BY POLE MANUFACTURER (U.M.C.).
 4. REINFORCING STEEL SHALL BE ASSEMBLED IN CAGES USING #4 TIES AT 24" (MAX.) CENTER.
 5. FOUNDATION TOP SHALL BE ROUND AND LEVEL TO ACCOMMODATE DECORATIVE BASE.
 6. TOP OF FOUNDATION SHALL BE AT LEAST 1" ABOVE PROJECTED FINISHED SIDEWALK GRADE.

FOUNDATION	DIM-1*	DIM-2
SIGNAL (16" BOLT CIRCLE)	9'-0"	36"
SIGNAL (>16" BOLT CIRCLE)	11'-0"	36"
LUMINARIES	6'-0"	30"
PEDESTRIAN	4'-0"	24"

* MINIMUM DEPTH MAY VARY BASED ON SOIL CONDITION.



CAP FOR SIGNAL POLE WITH >16" BOLT CIRCLE. CAP IS NECESSARY TO ACCOMMODATE DECORATIVE BASE.

REVISIONS

DESCRIPTION	DATE	BY
MODIFIED DIMS AND OTHER CHANGES	4/29/14	NJL
MODIFIED FOUNDATION NOTES	2/21/17	EGM

STANDARD DRAWING NO. 65

NOSTALGIC POLE FOUNDATION & WIRING DIAGRAM



**OFFICE OF THE CITY ENGINEER
CANTON, OHIO**

DANIEL J. MOEGLIN, P.E., CITY ENGINEER
2436 30th St. NE 44705 : 330-409-3381 : www.cantonohio.gov/engineering

APPROVED DATE: MARCH 2014

APPROVED BY: EEM

DRAWING FILE NAME:
ce_61-65_LIGHTPOLES.dwg