



**IFB #364-20 DAWSON COUNTY PAVING PROJECT FOR THREE COLLECTOR
LOCATIONS
ADDENDUM #3**

Bid Closing Date: April 9, 2020, at 10:30AM, EST
Bid Issue Date: March 6, 2020
Addendum Issue Date: April 3, 2020
By: Melissa Hawk, Purchasing Manager

The following are amendments to the IFB #364-20 Dawson County Paving Project for Three Collector Locations:

1. An Executive Order was issued by the State of Georgia Governor, on April 2, 2020, which gives specific instruction on companies maintaining minimum basic operations to maintain the value of a business, the Invitation for Bid opening date will stand.
2. The same Executive Order limits the number of individuals gathered in one location to no more than ten (10), unless able to be within six (6) feet of each other. In light of this directive, please send only one (1) employee per company to all future bid openings until further notice.
3. All dates, other specifications, terms and conditions remain the same as posted in the RFP document.

The following are questions and answers to the IFB #364-20 Dawson County Paving Project for Three Collector Locations:

QUESTION: At 3553 Sweetwater Juno Rd. there is a brick mailbox – Since mailboxes are to be located 2' from the edge of pavement how will this location be handled? Please clarify.

ANSWER: Brick or rock mailboxes are not expected to be moved and the centerline can be adjusted in the field to accommodate. Shall be coordinated with Dawson County Field rep prior to the start of rehab.

QUESTION: Each road has areas of the shoulder that are narrow. How should these areas be handled during the shoulder dressing?

ANSWER: Dawson County agrees there are a few areas that are narrow and our goal is to establish shoulders where practical. The contractors are not expected to backfill slopes to gain shoulder where slopes don't allow. All areas have or will have adequate road bed width to get some shoulders.

QUESTION: All (3) roads have stone side roads and or stone driveways. What will be required from the contractor in these areas?

ANSWER: Where needed to gain a smooth transition if the driveways are gravel, they will need to be dressed with like material.

QUESTION: Will the contractor be required to pave into driveways and side roads or can we run the spreader gate out as we go by each one?

ANSWER: The contractor can run the gate out on driveways if a smooth transition can be achieved. Some drives that are sloped and all paved side roads shall be required to be paved into for smooth transition to be achieved.

QUESTION: Will the Pavement Markings be replaced by the contractor or Dawson Co.? There is not a pay item for Pavement Markings. Please clarify.

ANSWER: All pavement marking shall be the responsibility of the contractor. Both temporary raised pavement markers, temp striping, and permanent striping. Shall be included in the general conditions line item.

QUESTION: Bailey Waters Rd. has existing Thermoplastic Rumble Strips on it. Will these be replaced by the contractor or Dawson Co.? There is not a pay item.

ANSWER: Contractor in the lump sum general conditions line item.

QUESTION: Pay item #4 on all (3) roads has a description: 19mm or B-Mod Asphalt Binder 2” Depth. B-Mod is a 12.5mm asphalt mix. Is this what Dawson Co. is looking for? 12.5mm asphalt mix is more expensive than 19mm.

ANSWER: B-Mod- is preferred.

Company Name

Signature of Authorized Representative

Title

Date

THIS DOCUMENT MUST BE SUBMITTED WITH BID RESPONSE

IFB #364-20 Dawson County Paving Project for Two Collector Locations