



St. Johns River Water Management District

Michael A. Register, P.E., Executive Director

525 Community College Parkway S.E. • Palm Bay, FL 32909 • 321-984-4940 • www.sjrwmd.com

DATE: February 16, 2024
TO: Prospective Respondents
FROM: Amy Lucey, Procurement Specialist
SUBJECT: Addendum #1 to Invitation for Bid, # 39383, Purchase and Delivery of Road Base for Lake George Conservation Area in Volusia County

As a result of inquiries, the following clarifications/changes are provided for your information. Please make all appropriate changes to your bid documents.

Q1: On Page 37 of the IFB states that you are asking for **Stabilized Road Base Lime Rock** but the specifications chart shows DOT Road Base Lime Rock. Stabilized Road Base Lime Rock is 1-1/2" to fines in size and is much more expensive. DOT Road Base Lime Rock is 3-1/2" to fines in size and is what you have purchased in the past. Do you want the DOT Road Base Lime Rock that you have been purchasing?

A1: Yes, the District is wanting to purchase FDOT Road Base Lime Rock.

Corrections:

Page 37, Statement of Work, Road Base Material purchase and Delivery Lake George Conservation Area – Volusia County, III. SCOPE OF WORK, has been modified as follows:

Contractor shall supply and deliver limerock (trucking included) with certified weight tickets at the time of delivery. The material should generally meet Florida Department of Transportation Specifications for ~~stabilized~~ road base **limerock** but does not need to be FDOT certified. However, the moisture content and the gradation schedule shall be met as defined below. The District reserves the right to inspect the material to ensure the quantity and quality meets the District's minimum requirements prior to award.

Attachment:

Page 37, Statement of Work, Road Base Material purchase and Delivery Lake George Conservation Area – Volusia County

NOTE: The Bid Due Date remains **2:00 p.m. Friday, March 1, 2024**

Please acknowledge receipt of this Addendum on the Bid Form provided in the proposal package.

If you have any questions, please e-mail me at alucey@sjrwmd.com.

**STATEMENT OF WORK
ROAD BASE MATERIAL PURCHASE AND DELIVERY
Lake George Conservation Area – Volusia County**

I. INTRODUCTION BACKGROUND

The Land Management group routinely requests that the Bureau of Operations and Maintenance assist in enhancing public/district access on District properties that are used for recreational activities, maintenance and repairs or infrastructure improvements. One such project is improvements to roadways within the Lake George Wildlife Conservation Area. Upon completion of the project, the roadways should be more sustainable and require less long-term maintenance.

II. OBJECTIVE

The objective of this work is for vendors to supply road base material (coquina or limerock) to the Lake George Wildlife Conservation Area (see attached map). The District anticipates purchasing 3,000 tons of limerock to refurbish the travel surfaces.

III. SCOPE OF WORK

Contractor shall supply and deliver limerock (trucking included) with certified weight tickets at the time of delivery. The material should generally meet Florida Department of Transportation Specifications for ~~stabilized~~ road base **limerock** but does not need to be FDOT certified. However, the moisture content and the gradation schedule shall be met as defined below. The District reserves the right to inspect the material to ensure the quantity and quality meets the District’s minimum requirements prior to award.

IV. TASK IDENTIFICATION

Contractor Responsibilities

- Provide limerock to the stockpile location shown on attached map.
- The material shall not exceed 15% moisture content at the time of shipment loading. Loads exceeding 15% moisture content shall not be accepted.
- Material shall have a minimum Limerock Bearing Ratio (LBR) of 100.
- Material shall meet the following general distribution guidelines for gradations:

SIEVE SIZE	GRADATION PERCENT PASSING
3 ½ inch	100
1 ½ inch	95-100
¾ inch	65-90
3/8 inch	40-85
No. 4	25-65
No. 10	20-50
No. 50	5-30
No. 200	0-10

- Provide certified scale (weight) ticket to District representative at time of delivery to verify shipment weight and quantity.