

# ADDENDUM NO. 05 – PORTAGE PUBLIC SCHOOLS – CENTRAL ELEMENTARY SCHOOL BP 4: CONSTRUCTION

June 27th, 2023

The following items are changes, clarifications, corrections of errors, etc., with respect to the Contract Documents previously issued. This addendum shall be a part of the Contract Documents.

Items listed below may or may not affect the cost of the Contractor's Proposal. Changes in cost shall be incorporated in the Contractor's Proposal.

#### ITEM No.1

 BC 09 -Masonry, BC 32 – Educational Casegoods, and BC 45 - Fire Alarm: BID DEALINE/OPENING POSTPONED

Sealed bids, in triplicate, for the Central Elementary School Bid Package 4, BC 09 – Masonry, BC 32 – Educational Casegoods, and BC 45 – Fire Alarm for Portage Public Schools, will be received until 9:00am local time, Monday, July 10<sup>th</sup>, 2023 at Owen-Ames-Kimball Co., 2700 Stadium Dr. Suite 2, Kalamazoo, MI 49008. Bids received after this time will neither be considered nor accepted.

All proposals received by the time and date stated above will be opened and read publicly at 11:00 am local time, Monday, July 10<sup>th</sup>, 2023 at Portage Central High School, Community Room 8135 S. Westnedge Ave, Portage, MI 49002.

Bids may be <u>mailed</u> to Owen-Ames-Kimball Co., 2700 Stadium Dr. Suite 2, Kalamazoo, MI 49008. Mailed bids must be received by 9:00am, Monday, July 10<sup>th</sup>, 2023. FAXED, EMAILED OR UPLOADED TO BUILDING CONNECTED BIDS WILL **NOT** BE ACCEPTED.

Bids may be brought directly to the bid opening at 11:00am and handed to an O-A-K employee only.

#### ITEM No. 2

DRAWING AND SPECIFICATION CHANGES AS NOTED BY TOWER PINKSTER - ATTACHED

- See Tower Pinkster write up
- Drawings: S501, S600, S601, S605, A321, A322, A323, A325

#### ITEM No. 3

 All Pre-Bid RFI's are to be emailed to <u>anastasiaw@oakmi.com</u> by Monday, July 3<sup>rd</sup> at noon. Please do not submit RFI's through building connected.



# ADDENDUM NO. 5 (BP4)

DATE OF ISSUANCE: June 26, 2023

PROJECT: Central Elementary School Bid Package 4: Construction

8422 South Westnedge Avenue

Portage, MI 49002

OWNER: Portage Public Schools

ARCHITECT'S PROJECT NO.: 21-237.10

ORIGINAL BID ISSUE DATE: May 17, 2023

#### SCOPE OF WORK

This Addendum includes changes to, or clarifications of, the original Bidding Documents and any previously issued addenda, and shall be included in the Bid. All of these Addendum items form a part of the Contract Documents. The Bidder shall acknowledge receipt of this Addendum in the appropriate space provided on the Bid Form. Failure to do so may result in disqualification of the Bid.

#### **DOCUMENTS INCLUDED IN THIS ADDENDUM**

This Addendum includes two [2] pages of text and the following documents:

• Bidding Documents: **None.** 

• Contract Conditions: None.

Specification Sections: None.

Drawings: \$501, \$600, \$601, \$605, A321, A322, A323, A325

#### **CHANGES TO PREVIOUSLY ISSUED ADDENDA**

None.

#### CHANGES TO BIDDING REQUIREMENTS

None.

#### **CHANGES TO CONTRACT CONDITIONS**

None.

## CHANGES TO SPECIFICATIONS

None.

#### 2

#### **CHANGES TO DRAWINGS**

#### ADD-5 Item No. D-1 - Bottom Bearing Plate Connection

Refer to Sheet(s): S501

Revision to connection from top plate bolted connection to bottom plate seat connection. Refer to detail 8/S501.

#### ADD-5 Item No. D-2 - CMU Horizontal Reinforcement Requirements

Refer to Sheet(s): S600

Note clarified to fully grout cores with reinforcements only. Detail note revised to clarify conditions of ladder reinforcement as typical. Note 10 issued in ADD-3 omitted for clarity of typical horizontal reinforcement. Refer to Detail 3/S600.

#### ADD-5 Item No. D-3 - Masonry Lintel Shear Reinforcement Requirements

Refer to Sheet(s): S600

Shear stirrups eliminated from lintels <= 8'-0" per constructability comments.

#### ADD-5 Item No. D-4 - Wall Pier Tie Reinforcement Requirements

Refer to Sheet(s): S600

Reinforcing ties within pier elements eliminated per constructability comments.

### ADD-5 Item No. D-5 - Typical Plan Detail for Horizontal Reinforcement

Refer to Sheet(s): S600

Revision to bond beam intersection detail.

#### ADD-5 Item No. D-6 - Interior CMU Wall at Roof

Refer to Sheet(s): S601

Revised the top steel plate connecting the deck to CMU wall at roof level. Reduced the thickness and width of the top plate.


#### ADD-5 Item No. D-7 - Thermal Brackets at Veneer Bearing

Refer to Sheet(s): S605, A321, A322, A323, A325

Fero Fast thermal bracket detail updated. Thickness of continuous shelf angle is revised.

Revised wall sections to remove shelf angle and bracket in alignment with 2<sup>nd</sup> floor openings. Revised shelf angle and bracket note, added typical note to 1/A321, provide membrane flashing, cavity drainage mesh, weeps and vents at shelf angle [12'-0"h locations].

#### **END OF ADDENDUM.**



ADD. No. 5

ADD. No. 1

BID

CHOOL

PROJECT TITLE
CENTRAL ELEMENTARY SC
PACKAGE 4: CONSTRUCTIC
ADDENDUM 5


ISSUED FOR

JUN 26, 2023

JUN 5, 2023


SHEET NUMBER **S 501** 21-237.10

DATE





Thornton Tomasetti, Inc.

DETAIL AT TOP OF V COLUMN




# REINFORCING COLUMN EMBEDDED IN CMU WALL 1 1/2" = 1'-0"








**SASE OF EMBEDDED REINFORCING COLUMN** 





8 S 501













FIRST FLOOR 100'-0"


FOUNDATION 97'-9"


V-COLUMN AT CANOPY


1/2" = 1'-0"


















CHOOL

ADD. No. 5


ISSUED FOR

JUN 26, 2023



JUN 26, 2023

DATE





PROJECT TITLE
CENTRAL ELEMENTARY SCHOOL BID
PACKAGE 4: CONSTRUCTION
PACKAGE 4: CONSTRUCTION

2 LB. SPRAY-APPLIED CLOSED CELL POLYURETHANE INSUL. (3" MIN)

BRICK WITH TIES @ 16" O.C. —

SHEATHING ON 8" CFMS -






CHOOL

ADD. No. 5


ISSUED FOR

JUN 26, 2023



JUN 26, 2023

DATE



PROJECT TITLE
CENTRAL ELEMENTARY SCHOOL BID
PACKAGE 4: CONSTRUCTION
PACKAGE 4: CONSTRUCTION

2 LB. SPRAY-APPLIED CLOSED CELL POLYURETHANE INSUL. (3" MIN)

BRICK WITH TIES @ 16" O.C. —

SHEATHING ON 8" CFMS -