



**ITB #2019-008 CALHOUN MINE ROAD WIDENING
QUESTIONS & ANSWERS
CLARIFICATION ON SPECIFICATIONS
ADDENDUM 1**

Return to: Lumpkin County Board of Commissioners
Ryan McDuffie, Purchasing Agent
99 Courthouse Hill, Suite D
Dahlonega, GA 30533

Bid Closing Date: September 26, 2019 at 2:00 PM, EST
Bid Issue Date: August 28, 2019
Addendum Issue Date: September 13, 2019 at 5:00 PM, EST
Pages: 3
By: Ryan McDuffie, Purchasing Agent

Vendor Name: _____
(A copy must be attached to the Addenda Acknowledgement)

QUESTIONS

1. I do not see line items, is it truly a lump sum bid or are there line items to bid on?
 - a. Lump sum. Estimated quantities have now been provided to assist. It is the responsibility of the contractor to verify the amounts.
2. To clarify, the scope of work on Calhoun Mine Rd will be widening the existing gravel road to 20'?
 - a. Yes 20' asphalt, 22' GAB.
3. There are three driveways between 03+00 and 04+00. The plans specify to resurface two of them 1.5" in depth, 50' from the road. Is this from centerline or edge of pavement and can the same mix be used for the driveways?
 - a. Edge of pavement. Yes, the same mix can be used.
4. The other driveway is specified to be constructed 12', 50' from road and pave 1.5" in depth. Will this new driveway require GAB? If so, how much? Thanks.
 - a. Yes. 6".
5. The documents state that the sub grade must pass a proof roll test. Does this also apply to the base course (GAB)?
 - a. Yes.
6. Will there be any soil testing required for fill dirt brought in from offsite?
 - a. None to be brought in. Grade will be field adjusted to match.



7. Will there be any material testing required?
 - a. All material will need to come from DOT approved sources.
8. Is the contractor required to provide the 50' interval staking described in the scope of work?
 - a. No. Provided by owner 1 time. Any restaking will be the responsibility of the contractor.
9. Is there any striping and/or new signage on this project?
 - a. No.
10. Will permanent road work signs be required or can temporary stands be used?
 - a. Permanent post signs required on Hwy 60, temporary signs can be used on Calhoun Mine Road.
11. Are there any more details for the drop inlets?
 - a. 90-31S DOT standard. Located in the plans.

CLARIFICATIONS

Cut and fill – no import on this project. Field adjust to the road. Hold the ditch line.

Holding right side and clearing to the left. There may be a couple of trees on the right side that need to be cleared. Surveyor will mark the grades.

Quantities are for estimated purposes only. It is up to the contractor to verify the amounts.

(estimated quantity sheet on the following page)



Estimated quantities	
clearing and grubbing (ac.)	0.5
cut (cyd)	550
Fill (cyd)	650
GAB (tons)	690
type B asphalt (tons)	205
type E asphalt (tons)	160
silt fence (ft)	300
ditch matting (sft)	4500
18" smooth lined hdpe pipe (ft)	380
48" x4' concrete manholes w/ 9031-s double spillway tops (ea)	3