

ADDENDUM NUMBER FOUR
MBWWTP CONTROL ROOM UPGRADES
W-15-009-201
CITY OF CHATTANOOGA, TENNESSEE

The following changes shall be made to the Contract Documents and Specifications:

I. CONTRACT DOCUMENT

- Add the following to Section 40 61 13, Paragraph 1.01.N:

Existing signal wiring in any PLC cabinet that is not terminated on the cabinet's local PLC shall be identified as in or out of service. For all signal wiring determined still in service, this wiring shall be relocated to the nearest location so as not to obstruct the PLC upgrade. The nearest location shall be determined through field inspection by the Contractor and verified by the Owner.

II. QUESTION

- After reviewing the existing conditions, I have found that one of the existing cabinets in which the new PLC is to be installed has a lot of analog cabling terminated and/or passing through this cabinet. I am certain this wiring will have to be relocated before installation of new equipment. What are the plans for this, and are there any drawings for this?

Response: The analog cabling will have to be relocated if it is still in service. See Contract Document revision above.

June 30, 2017

Justin C Holland, Administrator
City of Chattanooga