

**OFFICIAL BID FORM - ADDENDUM NO. 2 - 11/19/2021  
SANDY CREEK DRIVE - CULVERT REPLACEMENT  
WILSON, NC**

DESCRIPTION	QUANTITY	UNIT	UNIT PRICE	TOTAL
MOBILIZATION, BOND, INSURANCE	1	LS		
CLEARING, GRUBBING & GENERAL REMOVALS/DEMOLITION	1	LS		
SAWCUT, REMOVE & REPLACE EXISTING ASPHALT & STONE BASE, REPLACE W/ 8" CABC & 3" SF9.5B (2-LIFTS)	620	SY		
SAWCUT, REMOVE & REPLACE EXISTING CONCRETE CURB & GUTTER	227	LF		
REMOVE EXISTING STORM DRAIN	1	LS		
5'X8' BOTTOMLESS PRE-CAST CONCRETE CULVERT	1	LS		
WING WALLS (PRECAST OR CAST-IN-PLACE)	1	LS		
CLASS "B" RIP RAP	150	TN		
#57 STONE FOR FOOTING BEDDING	50	TN		
CONCRETE FOOTING	1	LS		
8" DIP SEWER (0'-6')	184	LF		
16" STEEL PIPE CASING (INCLUDING CONCRETE CRADLES)	20	LF		
4" PVC SEWER SERVICE W/ CLEANOUT	1	EA		
40"X40"X40" 3,000PSI CONCRETE ENCASEMENT	1	LS		
4' STANDARD MANHOLE (0'-6')	2	EA		
CONNECT TO EXISTING MANHOLE	1	EA		
PLUG & BLOCK EXISTING MH #165 SW INVERT	1	EA		
8" DIP WATERLINE	90	LF		
8" INSERT-A-VALVE	2	EA		
1" WATER SERVICE	2	EA		
SELECT BACKFILL (INCLUDES DISPOSAL OF UNSUITABLE MATERIAL)	500	CY		
#57 STONE TRENCH STABILAZATION (INCLUDES TRENCH EXCAVATION & DISPOSAL)	80	TN		
TRAFFIC CONTROL (ROAD CLOSURE)	1	LS		
INLET PROTECTION	2	EA		
SEED & MULCH	1	LS		
TEMPORARY EROSION CONTROL MEASURES	1	LS		
			<b>TOTAL</b>	

ONLY BIDS SUBMITTED ON THIS FORM WILL BE CONSIDERED BY THE CITY OF WILSON.

CONTRACTOR: \_\_\_\_\_ LICENSE # \_\_\_\_\_

ADDRESS: \_\_\_\_\_

SIGNATURE: \_\_\_\_\_

TITLE: \_\_\_\_\_ DATE: \_\_\_\_\_

ADDENDUM NUMBERS ACKNOWLEDGED: \_\_\_\_\_

EMAIL: \_\_\_\_\_ PHONE: \_\_\_\_\_