



THE CITY OF DAYTONA BEACH OFFICE OF THE PURCHASING AGENT

Post Office Box 2451
Daytona Beach, Florida 32115-2451

Phone (386) 671-8080
Fax (386) 671-8085

ADDENDUM NO. 3

DATE: 5/24/2019

PROJECT: ITB 19401

**FIRE ALARM MONITORING, TESTING, AND INSPECTION; FIRE
SUPPRESSION SYSTEM INSPECTION AND MAINTENANCE;
BACKFLOW PREVENTER CERTIFICATION; SECURITY SYSTEM
INSTALLATION AND MONITORING**

OPENING DATE: ~~6/5/2019~~ 6/12/2019 at 2:00 PM

This addendum is hereby incorporated into the Bid Documents for the project referenced above. The following items are clarifications, corrections, additions, deletions and/or revisions to and shall take precedence over the original documents. Additions are indicated by underlining, deletions are indicated by ~~striketrough~~.

1. **Revised bid schedule**. Use the revised bid schedule for Addendum #3 in spreadsheet form located at purchasing.codb.us, then click public solicitation, then FIRE ALARM MONITORING, TESTING, AND INSPECTION; FIRE SUPPRESSION SYSTEM INSPECTION AND MAINTENANCE; BACKFLOW PREVENTER CERTIFICATION; SECURITY SYSTEM INSTALLATION AND MONITORING, then go to Addendum 3.
2. 3.17 b) Those facilities which do not have security monitoring, the Contractor will install their wireless system with the same system as other upgraded facilities to ensure standardization.
 1. New installations will be done only after awarded Contractor gives a quote to the project manager and written authorization is given to the Contractor from the Project Manager by purchase order or work authorization.
 2. New installs systems will be charged at the rates specified on the bid schedule. This Quote will be inclusive of all costs associated with the upgrade. Contractor will not combine this section with the hourly labor rates for maintenance and repair. The City will not accept and additional charges, fees, or surcharges.
3. Answers to Bidders' written questions:

Q1: Are the device counts somewhere in the bid documents because I do not seem to see them.

A1: There are no device counts in the bid. Attached are fire alarm inspection reports most locations. No reports could be found for Fire Station 4 or Dickerson Center.

Q2: We talked about section 65 in the meeting. From my understanding you are looking for a package price (control, keypad, 2-door contacts, 1-motion) and then a price per each additional device. Is that correct?

A2: There seemed to be confusion on what was needed for creating a price for installing security systems. The item for installing security systems has been modified to breakout control panel (including initial programming), keypad, door sensor, window sensor, and motion sensors.

Q3: Can you provide us with the most recent Fire Alarm and Sprinkler System Inspection Reports and what you are you currently paying for each?

A3: See attached, trying to obtain the Police Department yet.

Q4: How are the current Burglar and Fire Alarm System being monitored (Phone Line or Cellular Communicator) and what are you currently paying for each?

A4: Will be answered on a future addendum

Q5: Manufacturer and/or Part Numbers for the current Burglar Alarm Control Panels?

A5: Will be answered on a future addendum

Q6: On current systems that are being monitored through cellular communicators, will the current provider be deactivating or releasing the serial numbers for each unit, to be utilized for new vendor?

A6: Will be answered on a future addendum.

4. The due date for this solicitation has been changed from ~~6/5/2019~~ to 6/12/2019 at 2:00 PM.

5. All other terms and conditions remain the same.

The Bidder shall acknowledge receipt of this addendum on the Bid Proposal Form.

The City of Daytona Beach

Kirk Zimmerman, CPPB
Buyer

FIRE ALARM INSPECTION REPORTS
MIDTOWN CULTURAL CENTER

MIDTOWN CULTURAL CENTER
925 GEORGE W. INGAM BLVD.
DAYTONA BEACH, FL 32117

ANNUAL FIRE ALARM INSPECTION FOR MAY 2018

SILENT KNIGHT FARENHYT IFP-100VP

ZN	AREA	TYPE DEVICE	LOCATION \ DESCRIPTION	STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER - 120VAC	Device Test	Pass
		CONTROL PANEL	SECONDARY POWER - BATTERIES 12 AH	Device Test	Pass
		CONTROL PANEL	BATTERY CHARGER	Device Test	Pass
		CONTROL PANEL	SYSTEM SWITCHES	Device Test	Pass
		CONTROL PANEL	SIGNAL CIRCUIT SUPERVISION	Device Test	Pass
		CONTROL PANEL	SYSTEM LEDS	Device Test	Pass
		CONTROL PANEL	GROUND DETECTION	Device Test	Pass
		CONTROL PANEL	ANNUNCIATOR - RA-100	Device Test	Pass
		CONTROL PANEL	MICROPHONE	Device Test	Pass
	AC SERVICE	BREAKER # 41	MAIN ELECTRIC ROOM PANEL PP1	Device Test	Pass
		EVAC PANEL	OPERATING POWER - 120VAC	Device Test	Pass
			SECONDARY POWER - BATTERIES 12 AH	Device Test	Pass
			BATTERY CHARGER	Device Test	Pass
		GYM REMOTE ANN	ANNUNCIATOR	Device Test	Pass
			MICROPHONE	Device Test	Pass
		MAIN ENTRANCE	ANNUNCIATOR - RA-100	Device Test	Pass
	SYS CTRL	RELAY	M23 AHU SHUTDOWN RELAY MECH 118		
	SYS CTRL	RELAY	M22 AHU SHUTDOWN RELAY MECH 116	Device Test	Pass
	SYS CTRL	RELAY	M20 CULINARY 111 ROLL DOWN DOOR EAST	Device Test	Pass
	SYS CTRL	RELAY	M21 CULINARY 111 ROLL DOWN DOOR WEST	Device Test	Pass
	SYS CTRL	RELAY	M24 GYM - SOUND SYSTEM	Device Test	Pass
	SYS CTRL	RELAY	M25 GYM - SOUND SYSTEM	Device Test	Pass
	SYS CTRL	CTRL	4:001-4:004 VOICE CIRCUITS	Device Test	Pass
	SYS CTRL	CTRL	34:001-34:004 STROBES	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	S01 COMM. ROOM 125 FACP	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	CORR. BY COMM. ROOM 125	Device Test	Pass
	1ST FLOOR	PULL STATION	M09 SOUTH EXIT BY STOR. 117	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	SOUTH EXIT BY STOR. 117	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	S18 STORAGE 117	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	S13 STORAGE 114	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	MEN'S ROOM 110	Device Test	Pass
	1ST FLOOR	STROBE	MEN'S ROOM 110	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	CORR. BY R.R'S & CULINARY	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	CULINARY 111	Device Test	Pass
	1ST FLOOR	HEAT DETECTOR	S14 CULINARY 111 (ROLL DOWN DOOR)	Device Test	Pass
	1ST FLOOR	HEAT DETECTOR	S21 CULINARY 111 (ROLL DOWN DOOR)	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	D12 CULINARY STOR. 112	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	D11 CULINARY REF. STOR. 113	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	S10 CORR. CULINARY (ROLL-DOWN DOOR)	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	WOMEN'S ROOM 109	Device Test	Pass
	1ST FLOOR	STROBE	WOMEN'S ROOM 109	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	CORR. BY ADMINISTRATION	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR	S09 ADMIN. COPY AREA 102A	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	ADMIN. COPY AREA 102A	Device Test	Pass
	1ST FLOOR	TAMPER	M39 ADMIN. OFFICE 102C -BFP/PIV	Verified Zone Rep	Checked OK
	1ST FLOOR	SMOKE DETECTOR	S08 ADMIN. STOR. 102E	Device Test	Pass

MIDTOWN CULTURAL CENTER
925 GEORGE W. INGAM BLVD.
DAYTONA BEACH, FL 32117

ANNUAL FIRE ALARM INSPECTION FOR MAY 2018

SILENT KNIGHT FARENHYT IFF-100VP

ZN	AREA	TYPE DEVICE	LOCATION \ DESCRIPTION	STATUS	REMARKS
	1ST FLOOR	STROBE	ADMIN. R.R. 102D	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GALLERY / LOBBY BY ANNUNCIATOR	Device Test	Pass
	1ST FLOOR	PULL STATION M03	GALLERY / LOBBY EXIT NORTH	Device Test	Pass
	1ST FLOOR	KNOX BOX M04	GALLERY / LOBBY EXIT N. (REF.ONLY)	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GALLERY / LOBBY	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	COMPUTER ROOM 104	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	DANCE 108	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	PRE-K / ART ROOM 105	Device Test	Pass
	1ST FLOOR	PULL STATION M10	PRE-K / ART ROOM 105 EAST EXIT	Device Test	Pass
	1ST FLOOR	HORN/STROBE	OUTSIDE PRE-K / ART EAST SIDE	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S06	PRE-K/ ART KILN STORAGE 106	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S07	PRE-K/ ART KILN STORAGE 105A	Device Test	Pass
	1ST FLOOR	STROBE	PRE-K / ART RESTROOM 107	Device Test	Pass
	1ST FLOOR	PULL STATION M02	MUSIC 123 EAST EXIT	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	MUSIC 123	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S05	MUSIC PRACTICE 122	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S04	MUSIC CONTROL RM 121	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S03	MUSIC RECORDING RM 120	Device Test	Pass
	1ST FLOOR	PULL STATION M01	SOUTH EXIT BY MUSIC	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	SOUTH EXIT BY MUSIC	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S02	ELEC. ROOM 119 - OUTSIDE	Device Test	Pass
	1ST FLOOR	HORN/STROBE	OUTSIDE MUSIC SOUTH	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S20	MECH. ROOM 118 - OUTSIDE	Device Test	Pass
	1ST FLOOR	DUCT DETECTOR S19	MECH. ROOM 118 - OUTSIDE	Device Test	Pass
	1ST FLOOR	REM. TEST SWITCH S19	MECH. ROOM 118 - OUTSIDE	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR S16	MECH. ROOM 116 - OUTSIDE	Device Test	Pass
	1ST FLOOR	DUCT DETECTOR S17	MECH. ROOM 116 - OUTSIDE	Device Test	Pass
	1ST FLOOR	REM. TEST SWITCH S17	MECH. ROOM 116 - OUTSIDE	Device Test	Pass
	1ST FLOOR	WATERFLOW M30	MECH. ROOM 116 - OUTSIDE	Verified Zone Repc	Checked OK
	1ST FLOOR	TAMPER M31	MECH. ROOM 116 - OUTSIDE	Verified Zone Repc	Checked OK
	1ST FLOOR	HORN/STROBE	OUTSIDE S. EX. BETWEEN MECH 116 / 118	Device Test	Pass
	1ST FLOOR	HORN/STROBE	OUTSIDE BY S. GYM NEAR MECH 116	Device Test	Pass
	1ST FLOOR	PULL STATION M08	GYM 101 S.E.	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 S.E.	Device Test	Pass
	1ST FLOOR	PULL STATION M07	GYM 101 S.W.	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 S.W.	Device Test	Pass
	1ST FLOOR	HORN/STROBE	OUTSIDE GYM - WEST SIDE	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 CENTER	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 CENTER	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 CENTER	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 CENTER	Device Test	Pass
	1ST FLOOR	PULL STATION M06	GYM 101 N.W.	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 N.W.	Device Test	Pass
	1ST FLOOR	HORN/STROBE	OUTSIDE GYM - NORTH SIDE	Device Test	Pass
	1ST FLOOR	HORN/STROBE	OUTSIDE ADMIN. AREA NORTH SIDE	Device Test	Pass
	1ST FLOOR	PULL STATION M05	GYM 101 N.E.	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 101 N.E.	Device Test	Pass
	1ST FLOOR	SMOKE DETECTOR D15	GYM 101 EAST BY ROLL-DOWN DOOR	Device Test	Pass

FIRE ALARM INSPECTION REPORT
FIRE STATION #2

DAYTONA BEACH FIRE STATION #2
126 BOTEFUHR AVE.
DAYTONA BEACH , FLORIDA 32118

ANNUAL FIRE ALARM INSPECTION REPORT FOR MAY 2018

FCI SBP-4

ZONE	AREA	TYPE DEVICE	LOCATION \ DESCRIPTION	STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER - 120VAC	Device Test	Pass
		CONTROL PANEL	SECONDARY POWER - BATTERIES 7AH	Device Test	Pass
		CONTROL PANEL	BATTERY CHARGER	Device Test	Pass
		CONTROL PANEL	GROUND DETECTION	Device Test	Pass
	AC SERVICE	BREAKER # 4	MAIN ELECTRICAL ROOM PANEL "LPE"	.	.
2	1ST FLOOR	PULL STATION	MAIN OFFICE	Device Test	Pass
	1ST FLOOR	HORN	CENTER MAIN HALLWAY	Device Test	Pass
2	1ST FLOOR	PULL STATION	CENTER MAIN HALLWAY	Device Test	Pass
1	1ST FLOOR	PULL STATION	WORKOUT ROOM	Device Test	Pass
.....					
2	1ST FLOOR	SMOKE DETECTOR	ROOM 1	Device Test	Pass
2	1ST FLOOR	SMOKE DETECTOR	ROOM 2	Device Test	Pass
2	1ST FLOOR	SMOKE DETECTOR	ROOM 3	Device Test	Pass
.....					
4	1ST FLOOR	WATER FLOW SWITCH	MAIN BAY	Not Tested	Test by Sprinkler Cont
	1ST FLOOR	HORN	MAIN BAY	Device Test	Pass

FIRE ALARM INSPECTION REPORT
FIRE STATION #4

FIRE STATION # 5
627 N. NOVA ROAD
DAYTONA BEACH, FL. 32114

FIRELITE MS-9200 INSPECTION REPORT FOR OCTOBER 2005

ZONE	AREA	TYPE DEVICE	LOCATION\DESCRIPTION	DEVICE\ITEM STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER (120VAC)	DEVICE TEST	PASS
		CONTROL PANEL	SECONDARY POWER - BATTERIES 5AH	DEVICE FAILED	REPLACED DEVICE
		CONTROL PANEL	BATTERY CHARGER	DEVICE TEST	PASS
		CONTROL PANEL	GROUND DETECTION	DEVICE TEST	PASS
	AC SERVICE	BREAKER # 5	MECH ROOM 117 PANEL P-2	DEVICE TEST	PASS
1ST FLOOR		PULL STATION M01	MAIN OFFICE	DEVICE TEST	PASS
1ST FLOOR		HORN/STROBE	LIVING ROOM	DEVICE TEST	PASS
1ST FLOOR		STROBE	MEN'S RESTROOM	DEVICE TEST	PASS
1ST FLOOR		STROBE	WOMEN'S REST ROOM	DEVICE TEST	PASS
1ST FLOOR		HORN/STROBE	MAIN HALLWAY	DEVICE TEST	PASS
1ST FLOOR		PULL STATION M04	WORKOUT ROOM	DEVICE TEST	PASS
1ST FLOOR		HORN/STROBE	WORKOUT ROOM	DEVICE TEST	PASS
1ST FLOOR		HORN/STROBE	MAIN BAY AREA BY MECH ROOM	DEVICE TEST	PASS
1ST FLOOR		SMOKE DETECT I02	MECH ROOM	DEVICE TEST	PASS
1ST FLOOR		HEAT DETECT I03	BLOOD BORNE ROOM 116	DEVICE TEST	PASS
1ST FLOOR		WATERFLOW SW M05	EAST BAY AREA	NOT TESTED	TEST BY SPRINKLER CONT.

FIRE ALARM INSPECTION REPORT
FIRE STATION #6

DAYTONA BEACH FIRE STATION #6
2020 BEVILLE ROAD
DAYTONA BEACH, FL

NOTIFIER SLG-2000 INSPECTION REPORT FOR OCTOBER 2005

ZONE	AREA	TYPE DEVICE	LOCATION\DESCRIPTION	DEVICE\ITEM STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER - 120VAC	DEVICE TEST	PASS
		CONTROL PANEL	SECONDARY POWER - BATTERIES 4AH	DEVICE TEST	PASS
		CONTROL PANEL	BATTERY CHARGER	DEVICE TEST	PASS
		CONTROL PANEL	SYSTEM LEDS/LAMPS	DEVICE TEST	PASS
		CONTROL PANEL	SYSTEM SWITCHES	DEVICE TEST	PASS
		CONTROL PANEL	ZONE SUPERVISION	DEVICE TEST	PASS
		CONTROL PANEL	SIGNAL CKT (NAC) SUPERVISION	DEVICE TEST	PASS
		CONTROL PANEL	GROUND DETECTION	DEVICE TEST	PASS
AC SERVICE	BREAKER #31 20A		PANEL 'LPE' IN ELEC RM NEXT TO FA	DEVICE TEST	PASS
1ST FLOOR	PULL STATION		BY KITCHEN	DEVICE TEST	PASS
1ST FLOOR	HORN/STROBE		HALLWAY BY KITCHEN	DEVICE TEST	PASS
1ST FLOOR	PULL STATION		WEIGHT ROOM	DEVICE TEST	PASS
SS ROOM	SMOKE DETECTOR		WEST ROOM - SINGLE STATION DETECTOR	DEVICE TEST	PASS
SS ROOM	SMOKE DETECTOR		CTR ROOM - SINGLE STATION DETECTOR	DEVICE TEST	PASS
SS ROOM	SMOKE DETECTOR		EAST ROOM - SINGLE STATION DETECTOR	DEVICE TEST	PASS

FIRE ALARM INSPECTION REPORT
FIRE STATION #7

DAYTONA BEACH FIRE STATION #7
2545 LPGA BOULEVARD
DAYTONA BEACH, FLORIDA 32117

ANNUAL FIRE ALARM INSPECTION REPORT FOR MAY 2018

SECUTRON MR-2100

ZONE	AREA	TYPE DEVICE	LOCATION \ DESCRIPTION	STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER - 120VAC	Device Test	Pass
		CONTROL PANEL	SECONDARY POWER - BATTERIES 7 AH	Device Test	Pass
		CONTROL PANEL	BATTERY CHARGER	Device Test	Pass
		CONTROL PANEL	SYSTEM LEDS/LAMPS	Device Test	Pass
	AC SERICE	BREAKER # 19	PANEL P-2 ELECTRIC / FACP ROOM		
		POWER SUPPLY	OPERATING POWER - 120VAC	Device Test	Pass
		ALTRONIX AL300ULB	SECONDARY POWER - BATTERIES 7AH	Device Test	Pass
		CO & DOOR POWER	BATTERY CHARGER	Device Test	Pass
	AC SERVICE	BREAKER #19	PANEL P-2 ELECTRIC / FACP ROOM		
1ST FLOOR		CONTROL RELAY M-16	GAS SHUTDOWN RELAY	Device Test	Pass
1ST FLOOR		ANNUNCIATOR	MAIN ENTRANCE	Device Test	Pass
1ST FLOOR		PULL STATION	0005 MAIN ENTRANCE	Device Test	Pass
1ST FLOOR		STROBE	WATCH OFFICE	Device Test	Pass
1ST FLOOR		HORN/STROBE	OUTSIDE TRAINING ROOM	Device Test	Pass
2 1ST FLOOR		HORN/STROBE	IN TRAINING ROOM	Device Test	Pass
1ST FLOOR		STROBE	IN TRAINING ROOM	Device Test	Pass
1ST FLOOR		STROBE	RESTROOM	Device Test	Pass
1ST FLOOR		HORN/STROBE	IN DINING AREA	Device Test	Pass
1ST FLOOR		PULL STATION	0004 KITCHEN EXIT	Device Test	Pass
1ST FLOOR		HORN/STROBE	KITCHEN EXIT	Device Test	Pass
1ST FLOOR		CO2 DETECTOR	0015 KITCHEN EXIT IN CEILING	Device Test	Pass
1ST FLOOR		CO2 DETECTOR	0016 CUSTODIAL CLOSET	Device Test	Pass
1ST FLOOR		HORN/STROBE	HALLWAY BY BUNK AREA	Device Test	Pass
1ST FLOOR		HORN/STROBE	BY RESTROOMS	Device Test	Pass
2 1ST FLOOR		STROBE	MENS ROOM	Device Test	Pass
1ST FLOOR		STROBE	LADIES ROOM	Device Test	Pass
1ST FLOOR		PULL STATION	0006 ENTRANCE TO APPARATUS BAY	Device Test	Pass
2 1ST FLOOR		HORN/STROBE	OUTSIDE FACP	Device Test	Pass
1ST FLOOR		SMOKE DETECTOR	0008 ABOVE FACP	Device Test	Pass
1ST FLOOR		HEAT DETECTOR	0009 MECH EQUIP ROOM	Device Test	Pass
1ST FLOOR		SMOKE DETECTOR	0010 MECH EQUIP ROOM	Device Test	Pass
1ST FLOOR		STROBE	WEIGHT ROOM	Device Test	Pass
1ST FLOOR		PULL STATION	0007 BY EAST ROLL-UP DOOR	Device Test	Pass
2 1ST FLOOR		HORN/STROBE	OUTSIDE STORAGE ROOM	Device Test	Pass
2 1ST FLOOR		STROBE	IN BIO-HAZARD ROOM	Device Test	Pass
1ST FLOOR		SMOKE DETECTOR	0013 GEAR LOCKER ROOM	Device Test	Pass
1ST FLOOR		CO2 DETECTOR	0012 MECH EQUIP ROOM	Device Test	Pass
2 1ST FLOOR		HORN/STROBE	WEST EXIT IN BAY	Device Test	Pass
1ST FLOOR		WATERFLOW SWITCH	WEST ROLL-UP DOOR	Verified Zone Reportir	Checked OK
1ST FLOOR		TAMPER SWITCH	WEST ROLL-UP DOOR	Verified Zone Reportir	Checked OK
2 1ST FLOOR		HORN/STROBE	OUTSIDE WEST ROLL-UP DOOR	Device Test	Pass
1ST FLOOR		CO2 DETECTOR	0014 EMS BIO - HAZARG ROOM	Device Test	Pass

FIRE ALARM INSPECTION REPORT
YVONNE SCARLETT GOLDEN CENTER

YVONNE SCARLETT-GOLDEN CENTER
1000 VINE STREET
DAYTONA BEACH

ANNUAL FIRE ALARM INSPECTION FOR AUGUST 2018

GE VIGILANT VS1 w/ VOICE EVAC

ZN	AREA	TYPE DEVICE	LOCATION \ DESCRIPTION	STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER - 120VAC	Device Test	Pass
		CONTROL PANEL	SECONDARY POWER - BATTERIES 12AH	Device Test	Pass
		CONTROL PANEL	BATTERY CHARGER OUTPUT	Device Test	Pass
		CONTROL PANEL	GROUND DETECTION	Device Test	Pass
		CONTROL PANEL	ANNUNCIATOR - FRONT DESK	Device Test	Pass
AC SERVICE		BREAKER #12	PANEL 11	.	.
1ST FLOOR		NAC PANEL	FACP/ELECT RM - 7AH BATTERY	Device Test	Pass
		NAC PANEL	OPERATING POWER 120VAC	Device Test	Pass
		NAC PANEL	BATTERY CHARGER OUTPUT 7AH	Device Test	Pass
1ST FLOOR	VOICE EVAC		FACP/ELECT RM - OPERATING PWR - 120V	Device Test	Pass
	VOICE EVAC		OPERATING POWER 120VAC	Device Test	Pass
	VOICE EVAC		BATTERY CHARGER OUTPUT 7AH	Device Test	Pass
SYS OUTPUT	RELAY	M01	AHU SHUTDOWN RTU-13	Device Test	Pass
SYS OUTPUT	RELAY	M04	AHU SHUTDOWN RTU-14	Device Test	Pass
SYS OUTPUT	RELAY	M05	AHU SHUTDOWN RTU-10	Device Test	Pass
1ST FLOOR	PULL-STATION	M06	S.E. GALLERY CORRIDOR	Device Test	Pass
1ST FLOOR	PULL-STATION	M07	N.W. GALLERY CORRIDOR	Device Test	Pass
1ST FLOOR	PULL-STATION	M08	N.E. GALLERY CORRIDOR	Device Test	Pass
1ST FLOOR	PULL-STATION	M09	S.W. GALLERY CORRIDOR	Device Test	Pass
1ST FLOOR	PULL-STATION	M10	MAIN LOBBY	Device Test	Pass
1ST FLOOR	PULL-STATION	M11	MAIN LOBBY	Device Test	Pass
1ST FLOOR	TAMPER	M12	BACKFLOW PREVENTOR	Verified Zone Reporting	Checked Ok
1ST FLOOR	TAMPER	M12	BACKFLOW PREVENTOR	Verified Zone Reporting	Checked Ok
1ST FLOOR	WATERFLOW	M13	LECTURE / THEATRE	Verified Zone Reporting	Checked Ok
1ST FLOOR	TAMPER	M14	LECTURE / THEATRE	Verified Zone Reporting	Checked Ok
1ST FLOOR	DUCT DETECTOR	D02	RTU-10 BY ELECT.	Device Test	Pass
1ST FLOOR	REMOTE TST / LIGHT		HALL OUTSIDE FACP	Device Test	Pass
1ST FLOOR	DUCT DETECTOR	D21	RTU-13 GYM	Device Test	Pass
1ST FLOOR	REMOTE TST / LIGHT		RM 403 JAN / ELECT RM	Device Test	Pass
1ST FLOOR	DUCT DETECTOR	D03	RTU-14 GYM	Device Test	Pass
1ST FLOOR	REMOTE TST / LIGHT		RM 403 JAN / ELECT RM	Device Test	Pass
1ST FLOOR	SMOKE DETECTOR	D15	MAIN LOBBY	Device Test	Pass
1ST FLOOR	SMOKE DETECTOR	D16	FACP / ELECTRIC ROOM	Device Test	Pass
1ST FLOOR	SMOKE DETECTOR	D17	N.E. STORAGE / ELEC.	Device Test	Pass
1ST FLOOR	HEAT DETECTOR	D18	COMPUTER LAB STORAGE	Sensitivity Test	Checked Ok
1ST FLOOR	HEAT DETECTOR	D19	STUDIO STORAGE	Sensitivity Test	Checked Ok
1ST FLOOR	HEAT DETECTOR	D20	GYM / J.A.N. STORAGE	Sensitivity Test	Checked Ok
1ST FLOOR	SPEAKER/STROBE		S.W. BY ELECT RM 201	Device Test	Pass
1ST FLOOR	STROBE		GRAPHIC ARTS RM 203	Device Test	Pass
1ST FLOOR	STROBE		FINE ARTS RM 204	Device Test	Pass
1ST FLOOR	SPEAKER/STROBE		WEST HALL	Device Test	Pass
1ST FLOOR	STROBE		DIGITAL ARTS RM 205	Device Test	Pass
1ST FLOOR	SPEAKER/STROBE		N.W. BY ELECT. RM 207	Device Test	Pass
1ST FLOOR	STROBE		COMMUNITY ROOM 301	Device Test	Pass

YVONNE SCARLETT-GOLDEN CENTER
1000 VINE STREET
DAYTONA BEACH

ANNUAL FIRE ALARM INSPECTION FOR AUGUST 2018

GE VIGILANT VS1 w/ VOICE EVAC

ZN	AREA	TYPE DEVICE	LOCATION \ DESCRIPTION	STATUS	REMARKS
	1ST FLOOR	SPEAKER/STROBE	NORTH HALL	Device Test	Pass
	1ST FLOOR	STROBE	ENVIRONMENT ROOM 302	Device Test	Pass
	1ST FLOOR	STROBE	TECHNOLOGY RM 303	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	NORTH HALL	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	N.E. HALL BY GYM 401	Device Test	Pass
	1ST FLOOR	STROBE	MEN'S ROOM	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	EAST HALL	Device Test	Pass
	1ST FLOOR	STROBE	WOMEN'S ROOM 404	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	S.E. BY GYM 401	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 401	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 401	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 401	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	GYM 401	Device Test	Pass
	1ST FLOOR	STROBE	THEATRE ARTS 101	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	SOUTH HALL	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	LOBBY EAST	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	LOBBY WEST	Device Test	Pass
	1ST FLOOR	STROBE	DEVELOPMENT RM 103	Device Test	Pass
	1ST FLOOR	STROBE	DEVELOPMENT RM 103	Device Test	Pass
	1ST FLOOR	SPEAKER/STROBE	SOUTH HALL	Device Test	Pass

FIRE ALARM INSPECTION REPORT HALIFAX HARBOR PLAZA

Fire Alarm and Life Safety System Inspection Certificate

For

Halifax Harbor Marina
125 Baison Street
Daytona Beach, FL. 32114

Tested to NFPA 72 Standards

This Inspection was performed in accordance with applicable NFPA Standards. The subsequent pages of this report provide performance measurements, listed ranges of acceptable results, and complete documentation of the inspection. Whenever discrepancies exist between acceptable performance standards and actual test results, notes and/or recommended solutions have been proposed or provided for immediate review and approval.


Inspection Date
Feb 2, 2006

Building: Halifax Harbor Marina
Contact: ? ?
Title: ?

Company: Certified Electronic Systems, Inc.
Contact: Mark Reisz
Title: Tech.

Executive Summary

Generated by: BuildingReports.com

Building Information								
Building: Halifax Harbor Marina			Contact: ??					
Address: 125 Baison Street			Phone: 386-672-8530					
Address:			Fax:					
City/State/Zip: Daytona Beach, FL. 32114			Mobile:					
Country: United States of America			Email:					
Inspection Performed By								
Company: Certified Electronic Systems, Inc.			Inspector: Mark Reisz					
Address: 1120 Enterprise Court			Phone: 386-547-0558					
Address: Suite A			Fax:					
City/State/Zip: Holly Hill, FL 32117			Mobile:					
Country: United States of America			Email: sh.oneal@certifiedelectronics.biz					
System Control Unit								
Manufacturer: Fire-Lite			Inspection Date: 02/02/2006			IDC Style:		
Model Number: MS 9200 UD			Install Date: 06/01/1990			SLC Style:		
Software Version:			Version Date: 06/19/2002			NAC Style:		
Location: 1st Northeast Telephone Room			Current Protection:					
Monitoring								
Type: <i>Phone # 800-631-2299</i>			Mfg: <i>Certicon</i>			Model #: <i>UDC-881</i>		
Test Time/Date: 2/2/06 11:08:46 AM			Restore Time:					
Inspection Summary								
Category	Total Items		Serviced		Passed		Failed/Other	
	Qty	%	Qty	%	Qty	%	Qty	%
Initiating	40	85%	40	100%	37	93%	3	8%
Control	7	15%	7	100%	7	100%	0	0%
Totals	47	100%	47	100%	44	94%	3	6%
Certification								
Building: Halifax Harbor Marina			Company: Certified Electronic Systems, Inc.					
Contact: ??			Inspector: Mark Reisz					
Signed:								
			Signed:					




Discrepancy Report

Generated by: BuildingReports.com

Building: Halifax Harbor Marina		Control Panel: Fire-Lite MS 9200 UD		
<i>The Discrepancy Report consolidates each discrepancy listed within the various Testing sections of your Inspection. Discrepancies are listed by Category, and grouped by device type. The description of the problem is provided and where appropriate, code references are listed for your convenience. Any item that was inspected that is listed on the Consumer Product Safety Commission's website and is subject to a recall by the manufacturer is included.</i>				
Device Type	Manufacturer	ModelNumber	Date	Qty
Items listed for Recall by Manufacturer				
Power Supply	Fire-Lite	FCPS-24FS8	03/11/2003	1
More Information: http://www.cpsc.gov/cpscpub/prerel/prhtml03/03527.html				
ScanID	Location	Problem	Address	Reference
Initiating				
Duct Detector				
01669066	2nd Brighthouse ceiling 1	Not attached to system		
01669067	2nd Brighthouse ceiling 2	Not attached to system		
01669068	2nd Brighthouse ceiling 3			

Proposed Solutions Report

Generated by: BuildingReports.com

Building: Halifax Harbor Marina		Control Panel: Fire-Lite MS 9200 UD			
<i>The Proposed Solution Report provides a solution for each discrepancy listed on the Discrepancy Report. Provide a check mark where indicated to approve repairs listed within the report. Items listed as T/M are available for repair on a Time and Materials basis.</i>					
 ScanID	 Location	 Solution	Model #	Cost	Fix
Initiating					
Duct Detector					
01669066	2nd brighthouse ceiling 1			T/M	<input type="checkbox"/>
01669067	2nd brighthouse ceiling 2			T/M	<input type="checkbox"/>
01669068	2nd brighthouse ceiling 3			T/M	<input type="checkbox"/>

Inspection & Testing

Generated by: BuildingReports.com

Building: Halifax Harbor Marina		Control Panel: Fire-Lite MS 9200 UD		
<i>The Inspection & Testing section lists all of the items inspected in your building. Items are grouped by Passed or Failed/Other. Items are listed by Category. Each item includes the services performed, and the time & date at which testing occurred.</i>				
Device Type	Location	Service	Time	Date
<i>Passed</i>				
Control				
Battery	1st Northeast Telephone Room 1 7-amhr	Tested	11:08:41 AM	02/02/2006
Battery	1st Northeast Telephone Room 2-10-amhr/ 4-7 amhr	Tested	11:08:50 AM	02/02/2006
Battery	1st Northeast Telephone Room 2-8-amhr	Tested	11:09:41 AM	02/02/2006
Communicator		Tested	11:08:46 AM	02/02/2006
Control Panel	1st Northeast Telephone Room	Tested	11:08:56 AM	02/02/2006
Power Supply	1st Northeast Telephone Room .	Tested	11:06:44 AM	02/02/2006
Voice Evacuation	1st Northeast Telephone Room .	Tested	11:06:35 AM	02/02/2006
Initiating				
Duct Detector	1st KITCHEN SUIT.102	Tested/Cleaned	11:06:49 AM	02/02/2006
Duct Detector	1st KITCHEN SUIT.102	Tested/Cleaned	11:06:53 AM	02/02/2006
Duct Detector	1st KITCHEN SUIT.102	Tested/Cleaned	11:06:58 AM	02/02/2006
Duct Detector	2nd North SUIT.205	Tested/Cleaned	11:07:10 AM	02/02/2006
Duct Detector	2nd North SUIT.205	Tested/Cleaned	11:07:14 AM	02/02/2006
Duct Detector	2nd North SUIT.205	Tested/Cleaned	11:07:18 AM	02/02/2006
Duct Detector	2nd North SUIT.205	Tested/Cleaned	11:07:23 AM	02/02/2006
Heat Detector	1st Northeast Elevator Equipment	Tested	11:08:08 AM	02/02/2006
Pull Station	1st Center Office 132	Tested	11:06:21 AM	02/02/2006
Pull Station	1st Center Office 130	Tested	11:06:25 AM	02/02/2006
Pull Station	1st Center Office 130 BACK DOOR	Tested	11:06:29 AM	02/02/2006
Pull Station	1st Center Office 105	Tested	11:07:02 AM	02/02/2006
Pull Station	1st Center Office 120	Tested	11:08:03 AM	02/02/2006
Pull Station	1st Center Kitchen	Tested	11:08:17 AM	02/02/2006
Pull Station	1st South Rest Exit	Tested	11:08:22 AM	02/02/2006
Pull Station	1st South Rest Exit	Tested	11:08:28 AM	02/02/2006
Pull Station	1st Northeast Kitchen Exit	Tested	11:08:33 AM	02/02/2006
Pull Station	1st Northeast Exit	Tested	11:08:37 AM	02/02/2006
Pull Station	1st Center Office 110	Tested	11:09:11 AM	02/02/2006
Pull Station	1st Center Office 115	Tested	11:09:16 AM	02/02/2006
Pull Station	1st Center Office 100	Tested	11:09:24 AM	02/02/2006
Pull Station	1st Center Office 100	Tested	11:09:29 AM	02/02/2006
Pull Station	1st Center Office 140	Tested	11:09:33 AM	02/02/2006
Pull Station	1st Center Office 140	Tested	11:09:37 AM	02/02/2006
Pull Station	2nd Center Office 210	Tested	11:06:08 AM	02/02/2006
Pull Station	2nd Center Office 230	Tested	11:06:12 AM	02/02/2006
Pull Station	2nd Center Office 200	Tested	11:07:30 AM	02/02/2006
Pull Station	2nd Center Office 205	Tested	11:07:34 AM	02/02/2006

Device Type	Location	Service	Time	Date
Pull Station	2nd Center Office 205	Tested	11:07:39 AM	02/02/2006
Pull Station	2nd Center Office 205	Tested	11:07:44 AM	02/02/2006
Pull Station	2nd Center Office 203	Tested	11:07:49 AM	02/02/2006
Pull Station	2nd Center Office 203	Tested	11:07:53 AM	02/02/2006
Pull Station	2nd Center Office 203	Tested	11:07:58 AM	02/02/2006
Pull Station	2nd Center Office 200	Tested	11:09:01 AM	02/02/2006
Pull Station	2nd Center Office 215	Tested	11:09:06 AM	02/02/2006
Smoke Detector	1st Northeast Elevator	Tested/Cleaned	11:06:17 AM	02/02/2006
Smoke Detector	1st Northeast Elevator Equipment	Tested/Cleaned	11:08:13 AM	02/02/2006
<i>Failed/Other</i>				
Initiating				
Duct Detector	2nd brighthouse ceiling 1	not connected to system	11:04:26 AM	02/02/2006
Duct Detector	2nd brighthouse ceiling 2	not connected to system	11:05:15 AM	02/02/2006
Duct Detector	2nd brighthouse ceiling 3	not connected to system	11:05:51 AM	02/02/2006

Battery & Power Supply Testing

Generated by: BuildingReports.com

Building: Halifax Harbor Marina			Control Panel: Fire-Lite MS 9200 UD			
<i>The Control & Power Testing section details the readings and measurements of batteries and power supplies used to provide power to the fire alarm and life safety systems. Items are grouped by Passed or Failed/Other.</i>						
Type	Location	Comment	Amps	Volts	Pre Test	Post Test
<i>Passed</i>						
Power Supply						
1st Northeast Telephone Room .						

Inventory & Warranty Report

Generated by: BuildingReports.com

Building: Halifax Harbor Marina			Control Panel: Fire-Lite MS 9200 UD	
<i>The Inventory & Warranty Report lists each of the devices and items that are included in your Inspection Report. A complete inventory count by device type and category is provided. Items installed within the last 90 days, within the last year, and devices installed for two years or more are grouped together for easy reference.</i>				
Device or Item		Category	% of Inventory	Quantity
Duct Detector		Initiating	21%	10
Pull Station		Initiating	57%	27
Smoke Detector		Initiating	4%	2
Voice Evacuation		Control	2%	1
Power Supply		Control	2%	1
Heat Detector		Initiating	2%	1
Battery		Control	6%	3
Communicator		Control	2%	1
Control Panel		Control	2%	1
Type	Qty	Model #	Description	Install Date
<i>In Service - 15 Years to 25 Years</i>				
Battery	3			06/01/1990
Duct Detector	3			06/01/1990
•				
Communicator	1	.		06/01/1990
Edwards				
Heat Detector	1			06/01/1990
Pull Station	27			06/01/1990
Smoke Detector	1			06/01/1990
EVAX				
Voice Evacuation	1	50/25		06/01/1990
Fire-Lite				
Control Panel	1	MS 9200 UD		06/01/1990
Duct Detector	7	D350PL	Photoelectric	06/01/1990
Power Supply	1	FCPS-24FS8		06/01/1990
Smoke Detector	1			06/01/1990

FIRE ALARM INSPECTION REPORT CITY HALL

Fire Alarm and Life Safety System Inspection Certificate

For

Daytona Beach City Hall
311 S. Ridgewood Ave.
Daytona Beach, FL. 32114

Tested to NFPA 72 Standards

This Inspection was performed in accordance with applicable NFPA Standards. The subsequent pages of this report provide performance measurements, listed ranges of acceptable results, and complete documentation of the inspection. Whenever discrepancies exist between acceptable performance standards and actual test results, notes and/or recommended solutions have been proposed or provided for immediate review and approval.

Inspection Date
May 22, 2004

Building: Daytona Beach City Hall
Contact: Scott R. Kroeger
Title: Safety

Company: Systems Solutions
Contact: Scott O'Neal
Title: Director of Sales & Service

Executive Summary

Generated by: BuildingReports.com

Building Information

Building: Daytona Beach City Hall	Contact: Scott R. Kroeger
Address: 311 S. Ridgewood Ave.	Phone: 386-252-6461
Address:	Fax:
City/State/Zip: Daytona Beach, FL. 32114	Mobile:
Country: United States of America	Email:

Inspection Performed By

Company: Systems Solutions	Inspector: Scott O'Neal
Address: 1120 Enterprise Court	Phone: 386-248-0460
Address: Suite A	Fax:
City/State/Zip: Holly Hill, FL 32117	Mobile: 386-547-0557
Country: United States of America	Email: DCramton@Systems-Solutions.biz

System Control Unit

Manufacturer: Fire-Lite	Inspection Date: 05/22/2004	IDC Style:
Model Number: 9200	Install Date: 06/02/1997	SLC Style:
Software Version:	Version Date: 06/24/2002	NAC Style:
Location: 1st West Maintenance Room	Current Protection:	

Monitoring

Type:	Mfg: Fire-Lite	Model #:
Test Time/Date: 5/22/04 6:49:11 AM	Restore Time:	

Inspection Summary

Category	Total Items		Serviced		Passed		Failed/Other	
	Qty	%	Qty	%	Qty	%	Qty	%
Initiating	72	94%	72	100%	72	100%	0	0%
Control	4	5%	4	100%	4	100%	0	0%
Indicating	all	1%	all	100%	all	100%	0	0%
Totals	77	100%	77	100%	77	100%	0	0%

Certification

Building: Daytona Beach City Hall	Company: Systems Solutions
Contact: Scott R. Kroeger	Inspector: Scott O'Neal
Signed:	Signed:

Inspection & Testing

Generated by: BuildingReports.com

Building: Daytona Beach City Hall		Control Panel: Fire-Lite 9200		
<i>The Inspection & Testing section lists all of the items inspected in your building. Items are grouped by Passed or Failed/Other. Items are listed by Category. Each item includes the services performed, and the time & date at which testing occurred.</i>				
Device Type	Location	Service	Time	Date
<i>Passed</i>				
Control				
Annunciator	1st West and south Exit x 2	Tested	6:49:23 AM	05/22/2004
Battery	1st West Maintenance Room	Tested	6:48:58 AM	05/22/2004
Communicator	1st West Maintenance Room	Tested	6:49:11 AM	05/22/2004
Control Panel	1st West Maintenance Room	Tested	6:48:47 AM	05/22/2004
Indicating				
Horn/Strobe	ALL	Tested	6:49:33 AM	05/22/2004
Initiating				
Duct Detector	1st North in room 125 AHU	Tested/Cleaned	7:19:13 AM	05/22/2004
Duct Detector	1st Southeast by room 123 AHU	Tested/Cleaned	7:24:29 AM	05/22/2004
Pull Station	1st West Elevator Exit	Tested	6:52:23 AM	05/22/2004
Pull Station	1st South Exit	Tested	7:03:11 AM	05/22/2004
Pull Station	1st East Entrance	Tested	7:06:33 AM	05/22/2004
Pull Station	1st South in room 151	Tested	7:29:13 AM	05/22/2004
Pull Station	1st South by room 173	Tested	7:33:01 AM	05/22/2004
Pull Station	1st Southeast Exit	Tested	7:35:16 AM	05/22/2004
Pull Station	1st Southeast Stair by 192	Tested	7:35:26 AM	05/22/2004
Pull Station	2nd South by office 230 Exit	Tested	7:28:18 AM	05/22/2004
Pull Station	2nd South by office 206	Tested	7:30:18 AM	05/22/2004
Pull Station	2nd Center Elevator Lobby	Tested	7:31:01 AM	05/22/2004
Pull Station	2nd South by office 280	Tested	7:34:52 AM	05/22/2004
Pull Station	2nd North In office 270 Exit	Tested	8:20:14 AM	05/22/2004
Smoke Detector	1st South by room 116A	Tested/Cleaned	7:03:37 AM	05/22/2004
Smoke Detector	1st Center by room 113	Tested/Cleaned	7:03:50 AM	05/22/2004
Smoke Detector	1st Center by room 146	Tested/Cleaned	7:04:19 AM	05/22/2004
Smoke Detector	1st Center by room 158	Tested/Cleaned	7:04:50 AM	05/22/2004
Smoke Detector	1st Center by room 103	Tested/Cleaned	7:05:19 AM	05/22/2004
Smoke Detector	1st East by room 133	Tested/Cleaned	7:08:06 AM	05/22/2004
Smoke Detector	1st East by room 141	Tested/Cleaned	7:08:54 AM	05/22/2004
Smoke Detector	1st North in room 125	Tested/Cleaned	7:18:58 AM	05/22/2004
Smoke Detector	1st Southeast inroom 123	Tested/Cleaned	7:25:03 AM	05/22/2004
Smoke Detector	1st West Elevator Lobby	Tested/Cleaned	7:27:11 AM	05/22/2004
Smoke Detector	1st East Entrance	Tested/Cleaned	7:27:30 AM	05/22/2004
Smoke Detector	1st East by room 127	Tested/Cleaned	7:27:56 AM	05/22/2004
Smoke Detector	1st East by room 145	Tested/Cleaned	7:28:41 AM	05/22/2004
Smoke Detector	1st South in room 124 AHU	Tested/Cleaned	7:28:49 AM	05/22/2004
Smoke Detector	1st South by room 116B	Tested/Cleaned	7:28:58 AM	05/22/2004
Smoke Detector	1st South by room 152	Tested/Cleaned	7:31:28 AM	05/22/2004

Smoke Detector	1st Southeast by room 152	Tested/Cleaned	7:31:55 AM	05/22/2004
Smoke Detector	1st Center in room 158	Tested/Cleaned	7:32:03 AM	05/22/2004
Smoke Detector	1st Center in room 165	Tested/Cleaned	7:32:21 AM	05/22/2004
Smoke Detector	1st Center by room 168	Tested/Cleaned	7:32:29 AM	05/22/2004
Smoke Detector	1st Center by room 174	Tested/Cleaned	7:33:35 AM	05/22/2004
Smoke Detector	1st Center by room 163	Tested/Cleaned	7:33:46 AM	05/22/2004
Smoke Detector	1st Center in room 176	Tested/Cleaned	7:34:10 AM	05/22/2004
Smoke Detector	1st Center by room 185	Tested/Cleaned	7:34:25 AM	05/22/2004
Smoke Detector	1st Center by room 123	Tested/Cleaned	7:34:43 AM	05/22/2004
Smoke Detector	2nd Center by office 226	Tested/Cleaned	7:29:29 AM	05/22/2004
Smoke Detector	2nd Center by office 240	Tested/Cleaned	7:29:47 AM	05/22/2004
Smoke Detector	2nd Center by office 220	Tested/Cleaned	7:30:05 AM	05/22/2004
Smoke Detector	2nd South by office 206	Tested/Cleaned	7:30:30 AM	05/22/2004
Smoke Detector	2nd Center by office 200	Tested/Cleaned	7:30:45 AM	05/22/2004
Smoke Detector	2nd Center Main Lobby	Tested/Cleaned	7:31:45 AM	05/22/2004
Smoke Detector	2nd Center by office 260	Tested/Cleaned	7:32:13 AM	05/22/2004
Smoke Detector	2nd Center by office 290	Tested/Cleaned	7:32:37 AM	05/22/2004
Smoke Detector	2nd Center by office 280	Tested/Cleaned	7:33:56 AM	05/22/2004
Smoke Detector	2nd North In office 250	Tested/Cleaned	7:37:00 AM	05/22/2004
Smoke Detector	2nd North In office 250	Tested/Cleaned	7:37:24 AM	05/22/2004
Smoke Detector	2nd North In office 262	Tested/Cleaned	7:37:47 AM	05/22/2004
Smoke Detector	2nd North In office 250	Tested/Cleaned	7:38:25 AM	05/22/2004
Smoke Detector	2nd North In office 250	Tested/Cleaned	7:39:09 AM	05/22/2004
Smoke Detector	2nd North In office 2 40A	Tested/Cleaned	7:40:14 AM	05/22/2004
Smoke Detector	2nd Center Break Room	Tested/Cleaned	7:40:41 AM	05/22/2004
Smoke Detector	2nd Center by office 226	Tested/Cleaned	7:41:21 AM	05/22/2004
Smoke Detector	2nd Center In office 226	Tested/Cleaned	7:42:09 AM	05/22/2004
Smoke Detector	2nd Center in office 230	Tested/Cleaned	7:46:11 AM	05/22/2004
Smoke Detector	2nd Center in office 240	Tested/Cleaned	7:47:14 AM	05/22/2004
Smoke Detector	2nd Center by office 246	Tested/Cleaned	7:47:59 AM	05/22/2004
Smoke Detector	2nd Center by office 242	Tested/Cleaned	7:48:29 AM	05/22/2004
Smoke Detector	2nd Center by office 221	Tested/Cleaned	7:49:35 AM	05/22/2004
Smoke Detector	2nd Center by office 220	Tested/Cleaned	7:50:01 AM	05/22/2004
Smoke Detector	2nd Center by office 200A	Tested/Cleaned	7:51:18 AM	05/22/2004
Smoke Detector	2nd Center by office 202	Tested/Cleaned	7:51:41 AM	05/22/2004
Smoke Detector	2nd Center Elevator Lobby	Tested/Cleaned	7:53:56 AM	05/22/2004
Smoke Detector	2nd North in office 290	Tested/Cleaned	7:54:22 AM	05/22/2004
Smoke Detector	2nd Center by office 210	Tested/Cleaned	7:55:25 AM	05/22/2004
Smoke Detector	2nd Center by office 215	Tested/Cleaned	7:55:51 AM	05/22/2004
Smoke Detector	2nd North In office 270	Tested/Cleaned	8:20:37 AM	05/22/2004
Smoke Detector	2nd North In office 270	Tested/Cleaned	8:21:20 AM	05/22/2004
Smoke Detector	2nd North In office 270	Tested/Cleaned	8:22:13 AM	05/22/2004

Inventory & Warranty Report

Generated by: BuildingReports.com

Building: Daytona Beach City Hall			Control Panel: Fire-Lite 9200	
<i>The Inventory & Warranty Report lists each of the devices and items that are included in your Inspection Report. A complete inventory count by device type and category is provided. Items installed within the last 90 days, within the last year, and devices installed for two years or more are grouped together for easy reference.</i>				
Device or Item		Category	% of Inventory	Quantity
Control Panel		Control	1%	1
Battery		Control	1%	2
Communicator		Control	1%	1
Annunciator		Control	1%	1
Horn/Strobe		Indicating	1%	all
Pull Station		Initiating	16%	12
Smoke Detector		Initiating	75%	58
Duct Detector		Initiating	3%	2
Type	Qty	Model #	Description	Install Date
<i>In Service - 2 Years or more</i>				
Battery	2	12volt 12amphrx2		06/01/2000
Fire-Lite				
Annunciator	1			06/02/1997
Communicator	1			06/02/1997
Control Panel	1	9200		06/02/1997
Duct Detector	2	SD300		06/02/1997
Horn/Strobe	1			06/02/1997
Pull Station	12			06/02/1997
Smoke Detector	58	SD300		06/02/1997

Fire Alarm System Log Sheet

Date	Time Started	Time Finished	Description of Troubles, Alarms, or Action	Initial
5-25-00			Installed Ann. OUT side Back Door	JS
1-18-10			Cleaned DUCT DETECTOR IN ALARM + RESET	JIM
1-19-10			Annual test + Inspection	AB
2-23-10			All Repairs FROM T+I Done	JS
5-1-10			DUCT DETECTOR IN ALARM IN RITE GRATE	JS
			Ordered New Duct Detector	JS
7-4-10	11:00	11:30	Duct Detector D16 - Active / Disabled	MJR
			Unit 103 South Center	
10-28-16			Replaced DUCT DETECTOR ADD 17 IN KITCHEN	JIM
1/18/11			Annual test & inspection	SAD
3/1/11			Replaced 2 Horn Strobes	JIM
3/9/11			Looked FOR Ground FAULT it Cleared	JIM
			Found Spoke STROBE ISY SOUTH EAST OUT SIDE	
3/10/11			it was covered with a 70 Box cover FAULT	JIM
1/10/12	8:45		Annual test & inspection	SAD
1/26/12			Replaced Pull Station SOUTH EAST 1ST FL	JIM
1/19/13	9:00		Annual test & inspection	SAD
1/7/14	9:00		Annual test & inspection	SAD
1/8/15	9:30		Annual test & inspection	SAD
1-28-16	2:00		Annual fire alarm test	SAD
3-28-16			FOUND Horn Strobe Removed	
3-28-16			BY contractor	JIM
5/3/16	1:30		Wired through missing Spoke/Strobe in Restaurant until Finished Remodel	SAD
12-22-17	8:00	12:00	Elevator Recall Elev. B	MJR
1-18-19	10:00		Annual Fire Alarm test	SAD

FIRE ALARM INSPECTION REPORT
PEABODY AUDITORIUM

PEABODY AUDITORIUM
600 AUDITORIUM BLVD
DAYTONA BEACH FL

FIRE LITE MS-9200 INSPECTION REPORT FOR AUGUST 1997

ZONE	AREA	TYPE DEVICE	LOCATION\DESCRIPTION	DEVICE\ITEM STATUS	REMARKS
		CONTROL PANEL	OPERATING POWER	OPERATING PROPERLY	FUNCTIONAL
		CONTROL PANEL	SYSTEM LEDS	OPERATING PROPERLY	FUNCTIONAL
		CONTROL PANEL	SYSTEM TROUBLE	OPERATING PROPERLY	FUNCTIONAL
		CONTROL PANEL	CENTRAL STATION	*** SPECIAL STATUS ***	SEE NOTES BY TECHNICIAN
✓	1ST FLOOR	MINISOUNDER/STROB	ELEV LOBBY	OPERATING PROPERLY	FUNCTIONAL
✓1	1ST FLOOR	SMOKE DET ION	ELEV LOBBY	OPERATING PROPERLY	FUNCTIONAL
✓2	1ST FLOOR	SMOKE DET ION	HVAC ROOM	OPERATING PROPERLY	FUNCTIONAL
✓3	2ND FLOOR	SMOKE DET ION	ELEV LOBBY	OPERATING PROPERLY	FUNCTIONAL
✓	2ND FLOOR	MINISOUNDER/STROB	MEN'S BATHROOM	OPERATING PROPERLY	FUNCTIONAL
✓	2ND FLOOR	MINISOUNDER/STROB	WOMEN'S BATHROOM	OPERATING PROPERLY	FUNCTIONAL
✓4	1ST FLOOR	SMOKE DET ION	ELEV EQUIPMENT ROOM (OUTSIDE EAST)	OPERATING PROPERLY	FUNCTIONAL
✓1		PULL STATION	WEST STAGE EXIT M01	OPERATING PROPERLY	FUNCTIONAL
✓2		PULL STATION	EAST STAGE EXIT M02	OPERATING PROPERLY	FUNCTIONAL
✓3		PULL STATION	EAST AUDITORIUM EXIT M03	OPERATING PROPERLY	FUNCTIONAL
✓4		PULL STATION	EAST LOBBY EXIT M04	OPERATING PROPERLY	FUNCTIONAL
✓5		PULL STATION	N-E BALCONY EXIT M05	OPERATING PROPERLY	FUNCTIONAL
✓6		PULL STATION	N-E BALCONY EXIT	OPERATING PROPERLY	FUNCTIONAL
✓7		PULL STATION	LOBBY EXIT	OPERATING PROPERLY	FUNCTIONAL
✓8		PULL STATION	N-W BALCONY EXIT	OPERATING PROPERLY	FUNCTIONAL
✓9		PULL STATION	N-W LOBBY EXIT	OPERATING PROPERLY	FUNCTIONAL
✓10		PULL STATION	WEST LOUNGE EXIT	OPERATING PROPERLY	FUNCTIONAL
✓11		PULL STATION	WEST AUDITORIUM EXIT	OPERATING PROPERLY	FUNCTIONAL
✓12		WATER FLOW	WOMENS BATHROOM (STORAGE ROOM)	OPERATING PROPERLY	FUNCTIONAL
✓13	1ST FLOOR	PULL STATION	EAST ELEV LOBBY EXIT M13	OPERATING PROPERLY	FUNCTIONAL
14	1ST FLOOR	RELAY ALT R	EAST ELEV EQUIP ROOM (OUTSIDE)	OPERATING PROPERLY	FUNCTIONAL
15	1ST FLOOR	RELAY BASE	EAST ELEV EQUIP ROOM (OUTSIDE)	OPERATING PROPERLY	FUNCTIONAL

1



8833UE00

Fire Alarm Inspection and Testing Report

Date: 08/08/13

Time: 10:45

Inspection Job #: 75042002

SERVICE ORGANIZATION

Name: Tyco Integrated Security
Address: 6830 SHADOW RIDGE DR, ORL, FL
Representative: CHRIS INABNIT
License No: #EF0000950
Telephone: (407) 712-1620

PROPERTY NAME (USER)

Name: CITY OF DAY BEACH (PENBOW AVENUE)
Address: 600 AUDITORIUM BLVD, DAY BEACH, FL
Owner Contact: RANDY
Telephone: _____

MONITORING ENTITY

Contact: TYCO IS
Telephone: (800) 289-2647
Monitoring Account Ref No (CS#): H624952028

APPROVING AGENCY

Contact: DAYTON BCH FIRE DEPT
Telephone: (386) 671-4000

TYPE TRANSMISSION

- ☐ McCulloh ☐ AlarmNet
☐ Multiplex ☐ Telular
☒ Digital ☐ AAGard
☐ Reserve Priority
☐ RF
☒ Other (Specify): SILENK KNIGHT PAC

SERVICE

- ☐ Weekly
☐ Monthly
☐ Bimonthly
☐ Quarterly
☐ Semiannually
☐ Annually
☐ Other (Specify): _____

Control Unit Manufacturer: FIRELITE / SILENK KNIGHT
Circuit Styles: B & Y / B
Number of Circuits: ADDRESSABLE / 3
Software Rev.: UNKNOWN / N/A
Last Date System Had Any Service Performed: 02/14/13
Last Date that Any Software or Configuration Was Revised: UNKNOWN

Model No: MS9200 / 5104

ALARM-INITIATING DEVICES AND CIRCUIT INFORMATION

Quantity of Devices Installed	Circuit Style	Quantity of Devices Tested
<u>10</u>	<u>B</u>	<u>10</u>
<u>3</u>	<u>B</u>	<u>3</u>
<u>2</u>	<u>B</u>	<u>2</u>

Manual Fire Alarm Boxes
Ion Detectors
Photo Detectors
Duct Detectors
Heat Detectors
Waterflow Switches
Supervisory Switches
Other (Specify): _____

Alarm verification feature is: ☒ Disabled ☐ Enabled



8833UE00

Fire Alarm Inspection and Testing Report

ALARM NOTIFICATION APPLIANCES and CIRCUIT INFORMATION

Quantity of Appliances Installed	Circuit Style	Quantity of Appliances Tested	
4	2	4	Bells
4	2	4	Horns / STROBES
			Chimes
4	2	4	Strobes
			Speakers
			Other (Specify):

No. of alarm notification appliance circuits: 2

Are circuits monitored for integrity? ☒ Yes ☐ No

SUPERVISORY SIGNAL-INITIATING DEVICES and CIRCUIT INFORMATION

Qty of Devices Installed	Circuit Style	Qty of Devices Tested		Qty of Devices Installed	Circuit Style	Qty of Devices Tested	
			Building Temp.				Fire Pump/Pump Controller Trbl
			Site Water Temp.				Fire Pump Low Fuel
			Site Water Level				Generator In Auto Position
			Fire Pump Power				Generator or Controller Trouble
			Fire Pump Running				Switch Transfer
			Fire Pump Auto Position				Generator Engine Running
			Other (Specify):				

SIGNALING LINE CIRCUITS

Quantity and style of signaling line circuits connected to system:

Quantity: N/A Style(s): N/A

See NFPA 72 section for Protected Premises Fire Alarm Systems, Performance of Signaling Line Circuits (SLC), table for Performance of Signaling Line Circuits for Class and Style

SYSTEM POWER SUPPLIES

(a) Primary (Main): Nominal Voltage: 120VAC Amps: 20A
 Overcurrent Protection: Type: C/B Amps: 20A
 Location (of Primary Supply Panelboard): EL PANEL
 Disconnecting Means Locations: BL

(b) Secondary (Standby): 3x12VDC Storage Battery: Amp-Hr. Rating: (2x7AHR)(1x4AHR)
 Calculated capacity in Amp-Hrs to operate system for 3 hours
 Engine-driven generator dedicated to fire alarm system: N/A
 Location of fuel storage: N/A

BATTERY TYPE

☐ Dry Cell ☐ Nickel-Cadmium ☒ Sealed Lead-Acid ☐ Lead-Acid ☐ Other (Specify):

(c) Emergency or standby system used as a backup to primary power supply, instead of using a secondary power supply:

☐ Emergency system described in NFPA 70, Article 700: ☐ Legally required standby described in NFPA 70, Article 701:

☐ Optional standby system described in NFPA 70, Article 702, which also meets the performance requirements of Article 700 or 701:



8833UE00

Fire Alarm Inspection and Testing Report

PRIOR TO ANY TESTING

NOTIFICATIONS ARE MADE

	Yes	No
Monitoring Entity	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Building Occupants	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Building Management	<input checked="" type="checkbox"/>	<input type="checkbox"/>
Other (Specify)	<input type="checkbox"/>	<input type="checkbox"/>
AHJ Notified of Any Impairments	<input type="checkbox"/>	<input type="checkbox"/>

Who

Time

TYCO IS
OCCUPANTS
MOD-RAND

10:45
10:45
10:45

SYSTEM TESTS and INSPECTIONS

Type	Visual	Functional	Comments
Control Unit	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Interface Equipment	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	SILENT KNIGHT 5104
Lamps/LEDs	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Fuses	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Primary Power Supply	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Trouble Signals	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Disconnect Switches	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	N/A
Ground-Fault Monitoring	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	

SECONDARY POWER

Type	Visual	Functional	Comments
Battery Condition	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Lead Voltage		<input checked="" type="checkbox"/>	
Discharge Test		<input checked="" type="checkbox"/>	
Charger Test		<input checked="" type="checkbox"/>	
Specific Gravity		<input checked="" type="checkbox"/>	N/A SLA

TRANSIENT SUPPRESSORS

☐

REMOTE ANNUNCIATORS

☒
☒

NOTIFICATION APPLIANCES

Type	Visual	Functional	Comments
Audible	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Visible	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>	
Speakers	<input type="checkbox"/>	<input type="checkbox"/>	
Voice Clarity		<input type="checkbox"/>	

INITIATING and SUPERVISORY DEVICE TESTS and INSPECTIONS

Loc. & S/N	Device Type	Visual	Functional	Factory Setting	Measured Setting	Pass	Fail
ALL	SMOKES (3)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>
	PULLS (10)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>
	W/F (2)	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>
	BAT	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>
	TELCO 1-2	<input checked="" type="checkbox"/>	<input checked="" type="checkbox"/>			<input checked="" type="checkbox"/>	<input type="checkbox"/>

Comments:



8833UE00

Fire Alarm Inspection and Testing Report

EMERGENCY COMMUNICATIONS EQUIPMENT

Phone Set
Phone Jacks
Off-Hook Indicator
Amplifier(s)
Tone Generator(s)
Call-In Signal
System Performance

Visual	Functional
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>

Comments

N/A

COMBINATION SYSTEMS

Fire Extinguisher Monitoring Device/System
Carbon Monoxide Detector/System
(Specify) N/A

Visual	Device Operation	Simulated Operation
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

INTERFACE EQUIPMENT

(Specify) ELEV. RECALL
(Specify) _____
(Specify) _____
Special Procedure: _____

Visual	Device Operation	Simulated Operation
<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

SPECIAL HAZARD SYSTEMS

(Specify) N/A
(Specify) _____
(Specify) _____

Visual	Device Operation	Simulated Operation
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>

Comments: _____

SUPERVISING STATION MONITORING

Alarm Signal
Alarm Restoration
Trouble Signal
Supervisory Signal
Supervisory Restoration

Yes	No
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>

Time

Comments

NOTIFICATIONS THAT TESTING IS COMPLETE

Building Management
Monitoring Agency
Building Occupants
Other (Specify) _____

Yes	No
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input checked="" type="checkbox"/>	<input type="checkbox"/>
<input type="checkbox"/>	<input type="checkbox"/>

Time

Who

11:59
11:59
11:59

MOD - RANDY
TYCO
OCCUPANTS

The following did not operate correctly (See Service Job): _____

Service Job#: _____

System restored to normal operation: Date: 08/08/13

Time: 11:59

On monitored alarm systems, I tested, and if necessary, connected the telephone line seizure feature to ensure it is working correctly. ☒ Yes ☐ No
THIS TESTING WAS PERFORMED IN ACCORDANCE WITH APPLICABLE NFPA STANDARDS.

Name of Inspector: CHRIS INABANTI

Date: 08/08/13

Time: 11:59

Signature: _____

Name of Owner or Representative: _____

Date: _____

Time: _____

Signature: _____

(UP*X/Yr)

Item #	Location/Description	UOM	Unit Price	x per Yr	Annual Total
<u>MIDTOWN CULTURAL CENTER (925 George Engram Blvd, Daytona Beach 32114)</u>					
Silent Knight Fahrenhyt IFP-100V					
1	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
2	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
3	Backflow Test: Annual	EACH		1	\$ -
4	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
5	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
6	Security Alarm: Monthly Monitoring	EACH		12	\$ -
<u>FIRE STATION 2 - (126 Botefuhr Avenue, Daytona Beach 32114)</u>					
FCI SBP-4					
7	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
8	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
9	Security Alarm: Monthly Monitoring	EACH		12	\$ -
<u>FIRE STATION 4 - (1675 Mason Avenue. Daytona Beach 32114)</u>					
Firelite 5024					
10	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
11	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
12	Security Alarm: Monthly Monitoring	EACH		12	\$ -
<u>FIRE STATION 5 - (627 N Nova Road, Daytona Beach, FL 32114)</u>					
Firelight MS 9200					
13	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
14	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
15	Security Alarm: Monthly Monitoring	EACH		12	\$ -
<u>FIRE STATION 6 - (2020 Beville Road, Daytona Beach, FL 32119)</u>					
Notifier SLG-2000					
16	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
17	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
18	Security Alarm: Monthly Monitoring	EACH		12	\$ -
<u>FIRE STATION 7 - (2545 LPGA Blvd)</u>					
Secutron MR2100					
14	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
15	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
16	Security Alarm: Monthly Monitoring	EACH		12	\$ -
<u>DICKERSON CENTER - (308 S Martin Luther King Jr Blvd, Daytona Beach, FL 32114)</u>					
FCI-SBP-2					
17	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
18	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
19	Security Alarm: Monthly Monitoring (APS)	EACH		12	\$ -
<u>YVONNE SCARLET GOLDEN CENTER - (1000 Vine Street, Daytona Beach, FL 32117)</u>					
GE Vigilant VS1 ANS25 Evac					
20	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
21	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
22	Backflow Test: Annual	EACH		1	\$ -
23	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -

Item #	Location/Description	UOM	Unit Price	x per Yr	Annual Total
24	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
25	Security Alarm: Monthly Monitoring	EACH		12	\$ -
HALIFAX PLAZA - (125 Basin Street, Daytona Beach, FL 32114) Honeywell-Notifier RP-2001; Panels-Fire lite 9200UD					
26	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
27	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
28	Backflow Test: Annual	EACH		2	\$ -
29	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
30	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
31	Security Alarm: Monthly Monitoring	EACH		12	\$ -
CITY HALL - (301 S. Ridgewood Avenue, Daytona Beach, FL 32114) Honeywell-Notifier RP-2001; Panels-fire lite 9200					
32	Fire Sprinkler: Quarterly Inspection (IT)	EACH		3	\$ -
33	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
34	Backflow Test: Annual	EACH		1	\$ -
35	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
36	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
37	Security Alarm: Monthly Monitoring	EACH		12	\$ -
JOSIE ROGERS HOUSE - (355 N Beach Street, Daytona Beach, FL 32114) Securtra MR2605					
38	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
39	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
40	Backflow Test: Annual	EACH		1	\$ -
41	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
42	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
ARCHIVES - (950 Bellevue Avenue - Bldg 3, Daytona Beach, FL 32114) Alarm: Honeywell-Notifier RP 2001 Monitor system: Silent Night					
44	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
45	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
46	Backflow Test: Annual	EACH		1	\$ -
47	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
48	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
49	Security Alarm: Monthly Monitoring	EACH		12	\$ -
PEABODY AUDITORIUM - (600 Auditorium Blvd, Daytona Beach, FL 32118) MS9200					
50	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
51	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
52	Backflow Test: Annual	EACH		1	\$ -
53	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
54	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
55	Security Alarm: Monthly Monitoring	EACH		12	\$ -
POLICE DEPARTMENT - (129 Valor Blvd, Daytona Beach, FL 32114) Silent Knight					
56	Fire Sprinkler: Quarterly Inspection	EACH		3	\$ -
57	Fire Sprinkler: Annual Inspection	EACH		1	\$ -
58	Backflow Test: Annual	EACH		1	\$ -

Item #	Location/Description	UOM	Unit Price	x per Yr	Annual Total
59	Fire Suppression: Inspection Annual (Dry System)	EACH		1	\$ -
60	Fire Suppression: Semi-Annual (Dry System)	EACH		1	\$ -
61	Fire Alarm: Annual Testing /Inspection	EACH		1	\$ -
62	Fire Alarm: Monthly Monitoring	EACH		12	\$ -
63	Security Alarm: Monthly Monitoring	EACH		12	\$ -
A. TOTAL FOR SERVICES BROKEN OUT BY LOCATION					\$ -
Quantities stated below as an estimate only and no guarantee is given or implied as to quantities that will actually be required during the contract period.					
Fire Alarm Monitoring Installation/Programming					
64	One time Installation and Programming Fee for upgrading fire alarm monitoring system with a wireless unit pre-approved by the project manager	EACH		14	\$ -
65	Reprogramming fee (after initial setup)	EACH		2	\$ -
Security System Installation/Programming					
66	Installation of future security systems will be done by quoting each individual location using the labor rates below				
67	Monthly security monitoring for future installations. (14 Locations X 12 months)	EACH		168	\$ -
68	Reprogramming fee (after initial setup)	EACH		2	\$ -
Maintenance and Repairs		<i>Est. ann Hr</i>			
69	Regular Rate (M-F 8-5)	HOURL		250	\$ -
70	Overtime Rate (M-F 5:01-7:59) & Saturdays	HOURL		50	\$ -
71	Sunday & City Observed Holiday Rate	HOURL		20	\$ -
Parts/Materials					
72	Parts/Materials furnished by the Contractor under this Contract will be at the Contractor's actual cost plus ___ percent (___%). Evidence of actual cost will be required. To establish a complete Contract amount for bid evaluation purposes, an estimated amount of \$2500 is added to the bid to cover the annual cost of parts/materials. This is not guaranteed and the actual amount will vary.	LOT	\$ 2,500.00		\$ 2,500.00
B. INSTALLATION/PROGRAMMING/MAINTENANCE/REPAIR/PARTS					\$ 2,500.00
ANNUAL TOTAL OF ALL SERVICES (A + B)					\$ 2,500.00